DEFENCE INFORMATION SERVICES
01047717 4

HRawson

MILITARY BOOKS

Published by Authority.

LONDON:
PRINTED UNDER THE AUTHORITY OF HIS MAJESTY'S STATIONERY OFFICE
BY HARRISON AND SONS, 45–47, ST. MARTIN'S LANE, W.C.,
PRINTERS IN ORDINARY TO HIS MAJESTY.

To be purchased, either directly or through any Bookseller, from
WYMAN AND SONS, LTD., 29, BREAMS BUILDINGS, FETTER LANE, E.C., and
54, ST. MARY STREET, CARDIFF; or
H.M. STATIONERY OFFICE (SCOTTISH BRANCH), 23, FORTH STREET, EDINBURGH; or
E. PONSONBY, LTD., 116, GRAFTON STREET, DUBLIN;
or from the Agencies in the British Colonies and Dependencies,
the United States of America, the Continent of Europe and Abroad of
T. FISHER UNWIN, LONDON, W.C.

(The prices in brackets are those at which the books are obtainable, post free, by Officers, Non-Commissioned Officers and Men, in the manner prescribed by the Regulations.)

ABYSSINIA. Expedition to. 2 vols. and maps. 1870. Half Mor., £5 5s. Cloth, £4 4s.

AFRICA. Continent of. Geology of. Notes on. 1906. 3s. (2s. 4d.)

AMHARIC LANGUAGE. Short Manual of the. With Vocabulary. 1909. 5s. (3s. 6d.)

ANIMAL MANAGEMENT. 1908. 1s. 6d. (1s. 4d.) *(Reprinting)*

ARABIC GRAMMAR. Two parts. 1887. (*Sold to Officers only.*) 10s. (10s. 6d.)

ARMOURERS, Instructions for, in the care, repair, browning, &c., of Small Arms, Machine Guns, "Parapet" Carriages, and for the care of Bicycles. 1912. 1s. 6d. (1s. 4d.)

Ditto. Amendments. Aug. 1912; Aug. 1914. Each 1d. (1d.)

ARMY ACCOUNTS. (*Reprinted from* THE ARMY REVIEW, January, 1914.) 3d. (3d.)

ARMY CIRCULARS AND ARMY ORDERS issued before Dec. 31, 1892, which are still in force and required for reference. Reprint of May, 1896. 3d. (3d.)

ARMY ORDERS. Monthly. Each 3d. (3d.)

ARMY ORDERS. Covers for. 9d. (9d.)

ARMY ENTRANCE Regulations:—

R.M. Academy. Admission to, from April 1, 1912. 1d. (1d.) *(Under revision)*

R.M. College. Ditto. 1d. (1d.) *(Under revision)*

Militia and Imperial Yeomanry. Officers of. 1907. 1d. (1d.)

Special Reserve of Officers, Malta Militia, Bermuda Militia, Channel Islands Militia, and Territorial Force. Officers of the. 1912. 1d. (1d.) *(Under revision)*

University Candidates. 1912. 1d. (1d.) *(Under revision)*

Military Forces of the Self-governing Dominions and Crown Colonies. Officers of the. 1912. 1d. (1d.) *(Under revision)*

Warrant Officers and N.C.O. of the Regular Army. Combatant Commissions as Second Lieutenants. 1914. Provisional. 1d. (1d.)

See also Commission; Medical Corps; Special Reserve; Territorial Force; Veterinary Corps.

(B 11031) Wt. 26060—235 75M 11/14 H & S

(As to prices in brackets, see top of page 2.)

ARMY LIST. The Quarterly (*not issued in October*, 1914). Each 15*s.* (10*s.* 6*d.*)

ARMY LIST. Monthly. Each 1*s.* 6*d.* (1*s.* 4*d.*) (*Issue suspended temporarily, see next item.*)

PROMOTIONS, APPOINTMENTS, &c., since the publication of the Army List for August, 1914, which was corrected to July 31, 1914. [Printed in consequence of the temporary suspension of the Monthly Army List.] 6*d.* (6*d.*)

Ditto. September 1914. [Ditto.] 6*d.* (7*d.*)

ARMY PAY, Appointment, Promotion, and Non-Effective Pay. Royal Warrant. 1914. (*In the press*)

ARMY ALLOWANCES Regulations. 1914. 6*d.*

ARMY REVIEW. Quarterly. Commencing July 1911. 1*s.* (Up to July 1914, 1*s.*; Oct. 1914, 11*d.*)

ARMY SERVICE CORPS:—

Regimental Standing Orders. 1911. 6*d.* (6*d.*); Amendments. 1*d.* (1*d.*)

Memorandum No. 25. 1*d.* (1*d.*)

Training. Part I. 9*d.* (8*d.*)

Ditto. Part II. Supplies. 1909. (Reprinted, 1914, with new Appendix XII.) (*In the press*)

Ditto. Part III. Transport. 9*d.* (9*d.*)

Ditto. Part IV. Mechanical Transport. 1*s.* 4*d.* (1*s.* 2*d.*)

Ditto. Amendments, July 1914, to Parts I. and III. 3*d.* (3*d.*)

ARTIFICERS. Military. Handbook. 9th edition. 1910. 1*s.* (11*d.*)

Ditto. Amendments. 1912; May 1914. Each. 1*d.* (1*d.*)

ARTILLERY AT THE PICARDY MANŒUVRES IN 1910. Translated from the French. 2*s.* 6*d.* (2*s.*)

ARTILLERY. Royal:—

Officers' Mess Management. (*See* Ordnance College.)

Practice. Instructions—

Garrison. Coast Defences. Seawards. 1914–15. 3*d.* (3*d.*)

Garrison. Siege and Movable Armament. 1914. 3*d.* (3*d.*)

Horse, Field, and Heavy. 1914. 6*d.* (5*d.*)

Standing Orders for—

Brigade of Mounted Artillery. 1*d.* (1*d.*) (*In the press*)

Lieut.-Colonel's Command, R.G.A. (Coast and Siege). 1*d.* (1*d.*)

Training—

Field. 1914. 9*d.* (9*d.*)

Garrison—

Vol. I. 1914. 6*d.* (6*d.*)

Vol. II. (Siege). 1911. 9*d.* (8*d.*)

Ditto. Amendments. Nov. 1914. 2*d.* (2*d.*) (*In the press*)

Vol. III. 1911. 1*s.* (11*d.*); Amendments. Feb. 1912. 1*d.* (1*d.*)

ARTILLERY COLLEGE. Reports upon the 14th to 18th Senior Classes Each 1*s.* (9*d.*) (*See also* Ordnance College.)

ARTILLERY. FIELD. The Tactics of. (*Von Schell.*) Translated. 1900. 1*s.* (10*d.*)

ARTILLERY INSTRUMENTS. Handbook of. 1914. 1*s.* 6*d.* (1*s.* 4*d.*)

ARTILLERY MUSEUM in the Rotunda, Woolwich. Official Catalogue, 1906. (*Sold at the Rotunda. Price* 1*s.* 6*d.*)

ARTILLERY AND RIFLE RANGES ACT, 1885, and MILITARY LANDS ACT, 1892. Byelaws under:—

Aldeburgh, 1896; Ash (Aldershot Camp), 1887; Finborough, 1901; Hythe, 1894; Inchkeith Battery, 1896; Kinghorneness, 1896; Landguard, 1887; Lydd—Dungeness, 1895; Middlewick, 1890; Millbrook, 1888; Orchard Portman, 1896; Scarborough, 1902; Scraps Gate, 1886; Shoeburyness, 1895; Southwold, 1896; Strensall, 1900; Wash, 1891; Whitehaven Battery (Cumberland), 1896; each 1*d.* (1*d.*)

(As to prices in brackets, see top of page 2.)

Artillery and Rifle Ranges Act, &c.—*continued.*
Purfleet, 1911. 1*s.* (9*d.*)
Salisbury Plain, 1900. 4*d.* (4*d.*)

ARTILLERY STORE ACCOUNTS AND THE SUPERVISION OF R.G.A. SUB-DISTRICTS. Notes on. 1914. 1*s.* (10*d.*)

ARTILLERY STORE ACCOUNTS AND THE CARE AND PRESERVATION OF EQUIPMENT OF ROYAL ARTILLERY, HORSE, FIELD, AND HEAVY BATTERIES. Notes on. June 1911. 6*d.* (5*d.*)

(*Under revision*)

BALLOONING. Military. Manual of. Part I. 1905. 1*s.* (9*d.*)

BARRACKS. Care of. Instruction in. 1901. 9*d.* (7*d.*)

BASHFORTH CHRONOGRAPH. Experiments with, to determine the resistance of the air to the motion of projectiles. Report on. 1870. 1*s.* (9*d.*)

BAYONET FIGHTING. Instruction in. 1*d.* (1*d.*)

BAYONET FIGHTING FOR COMPETITIONS. Instruction in. 1*d.* (1*d.*)

BERMUDA MILITIA ARTILLERY. Regulations, 1914. 9*d.* (7*d.*)

BICYCLES. Military. Handbook on. 1911. 1*d.* (1*d.*)

BRITISH MINOR EXPEDITIONS, 1746 to 1814. 1884. 2*s.* 6*d.* (1*s.* 11*d.*)

CADET LIST and **CADET UNITS.** (*See Territorial Force.*)

CAMEL CORPS TRAINING. Provisional. 1913. 8*d.* (7*d.*)

CAPE OF GOOD HOPE. Reconnaissance Survey of the, 1903-1911. Report on the. 1*s.* 6*d.* (1*s.* 1*d.*)

CAVALERIE. Translated from the French of Captain Loir. (*In the press*)

CAVALRY OF THE LINE. PEACE ORGANIZATION OF THE; and Arrangements for Mobilization consequent on the establishment of Cavalry Depôts. (Special A.O., July 19, 1909). 1*d.* (1*d.*)

CAVALRY SCHOOL, NETHERAVON. Standing Orders. 1911. 2*d.* (2*d.*)

CAVALRY TRAINING. 1912. (Reprinted, with Amendments, 1914.) 1*s.* (10*d.*)

(*In the press*)

CEREMONIAL. 1912. 3*d.* (4*d.*); Provisional Amendments, June 1914. 1*d.* (1*d.*)

CHEMISTRY. PRACTICAL. Quantitative and Qualitative. A Course of. 5*s.* (3*s.* 8*d.*)

CHEMISTS OF THE RESEARCH DEPARTMENT. Rules and Regulations. 1*d.* (1*d.*)

CHIROPODY Manual. 2*d.* (2*d.*)

CIVIL EMPLOYMENT FOR EX-SOLDIERS. Guide to. 1913. 2*d.* (2*d.*)

CIVIL EMPLOYMENT Regulations. 1913. 1*d.* (1*d.*)

CIVIL POWER. DUTIES IN AID OF THE. Special A.O., Dec. 17, 1908. (Amendments to "King's Regulations," and to "Manual of Military Law"). 1*d.* (1*d.*)

CLOTHING AND NECESSARIES (including Materials). Priced Vocabulary of. 1913. 1*s.* (11*d.*); Amendments, July, Oct. 1913; Jan., April, July 1914. Each 1*d.* (1*d.*)

CLOTHING Regulations:—
Part I. Regular Forces (excluding the Special Reserve). 1914. 6*d.* (6*d.*)
Part II. Special Reserve. 1914. 3*d.* (3*d.*)
Part III. Mobilization, Field Service, and Demobilization. 1908. 3*d.* (3*d.*)
Amendments to Parts I., II., and III. Nov. 1909; April, Oct. 1910; March, April, Sept., Nov. 1911; Feb., May, July, Sept. 1912; April, July 1913. Each 1*d.* (1*d.*)

CLUBS. Regulation Exercises for the, 1863. (*Reprinted* 1887.) 3*d.* (3*d.*)

COLCHESTER GARRISON. Standing Orders. 1913. 9*d.* (7*d.*)

COMMAND. ALDERSHOT. Standing Orders. 1914. 2*s* 3*d.* (1*s.* 9*d.*)

COMMAND. THE ART OF. By Colonel von Spohn. Translated. 1*d.* (1*d.*)

COMMAND. WESTERN. Standing Orders. Jan., 1910. 2*d.* (2*d.*)

(As to prices in brackets, see top of page 2.)

COMMANDS, Military, and Staff in the United Kingdom. Reorganization of. (Special A.O., Jan. 6, 1905, with alterations to date. Issued with Special A.O., Nov. 11, 1907.) 3*d.* (3*d.*)

COMMISSION IN H.M. REGULAR ARMY (from 1st April, 1912). Short guide to the various ways of obtaining a; &c., &c. April 1912. 2*d.* (2*d.*) (*See also* Army Entrance; *Medical Corps*; *Special Reserve*: Territorial Force; Veterinary Corps.) (*Under revision*)

COMPANY TRAINING. Notes on. For the use of the Special Reserve, Territorial Force, and newly-raised Units of the Regular Army. Sept. 1914. 1*d.* (1*d.*)

CONVEYANCE OF TROOPS AND ISSUE OF TRAVELLING WARRANTS. Instructions. 1910. 2*d.* (2*d.*)

COOKING. Military Manual. 6*d.* (5*d.*)

COURSES OF INSTRUCTION, 1914–15. 2*d.* (2*d.*)
Ditto, at Practice Camps, 1914. 1*d.* (1*d.*)

CREWS OF WAR DEPARTMENT VESSELS AND BOATS AT HOME STATIONS. Regulations for the Appointment, Pay, and Promotion of. 1911. 2*d.* (2*d.*)

CYCLIST TRAINING. Provisional. 1914. 3*d.* (3*d.*)

DIVISION ORDERS. Extracts from. 1880. 2*s.* 6*d.* (1*s.* 9*d.*)

DRAINAGE MANUAL. 1907. 2*s.* 6*d.* (2*s.*)

DRAWING PLATES. Military:—
Attack of Dufor's Countermines or 2nd plate of Mines; Carnot's First System; Detached Forts; Concealed Defences, 1, 2, 3, 4; Printing Plate, A, B, C, &c.; Detail Plate, No. 1; Do. No. 2; Neighbourhood of Woolwich; Village and Surrounding Ground. Each 2*d.* (2*d.*)
Attack of Fortress—Preliminary Operations; Do., Distant Attack; Do., Close Attack; Neighbourhood of Metz. Each 3*d.* (3*d.*)
Woods and Villages. *6 plates.* Each 6*d.* (5*d.*)
Neighbourhood of Woolwich. Southern Side. 1*s.* 6*d.* (1*s.* 1*d.*)

DRESS REGULATIONS. 1911. 2*s.* 6*d.* (2*s.*); Amendments, March, Aug. 1912. Each 1*d.* (1*d.*); Aug. 1913. 2*d.* (2*d.*)

DRUM AND FLUTE DUTY for the Infantry, with Instructions for the Training of Drummers and Flautists. 1887. 2*s.* (1*s.* 6*d.*)

DYNAMICS. Notes on. (*See* Ordnance College.)

EGYPT. BRITISH FORCE IN. Standing Orders. 1912. 1*s.* (10*d.*)

EGYPT. CAMPAIGN OF 1882 IN. Military History. With case of Maps. Condensed Edition. 1908. 3*s.* 6*d.* (2*s.* 8*d.*)

ELECTRICAL COMMUNICATIONS. FIXED. Instructions as to. 1912. 4*d.* (4*d.*)

ELECTRICITY AND MAGNETISM. Text Book for use of the Cadets at the R.M. Academy. 1911. 2*s.* 6*d.* (2*s.*)

ELECTRICITY. Notes on. 1911. 1*s.* 3*d.* (1*s.* 1*d.*)

ELECTRIC LIGHT APPARATUS. DEFENCE. Instructions for the Working of. 1911. 1*d.* (1*d.*)

ELECTRIC LIGHTING. Military. Vol. I. 1*s.* (11*d.*); Vol. II. 1*s.* 6*d.* (1*s.* 4*d.*); Vol. III. 1*s.* (11*d.*)

ENCOUNTER. THE BATTLE OF. By Hans von Kiesling. Part I. Practical. Translated. 1*s.* 6*d.* (1*s.* 3*d.*)

ENGINEER SERVICES Regulations. Peace:—Part I. 1910. 1*s.* (10*d.*); Part II. 1911. Technical Treatises. 9*d.* (7*d.*)

ENGINEER TRAINING. 1912. 6*d.* (6*d.*); Amendments, Jan. 1913. 1*d.* (1*d.*)

ENGINEERING. Field. Manual of. 1911. (*Reprinted* 1913.) 9*d.* (9*d.*)

(B 11031)

(As to prices in brackets, see top of page 2.)

ENGINEERING. Military :—

Part I. Field Defences. 1908. 1*s.* 6*d.* (1*s.* 3*d.*)
Part II. Attack and Defence of Fortresses. 1910. *(Out of print)*
Part III*a*. Military Bridging.—General Principles and Materials. 1913. 1*s.* (11*d.*)
Part III*b*. Ditto.—Bridges. *(In the press)*
Part IV. Mining and Demolitions. 1910. 1*s.* (11*d.*)
Part V. Miscellaneous. 1914. 1*s.* (11*d.*)
Part VI. Military Railways. 1898. *(Out of print)*

EQUIPMENT. INFANTRY. Pattern 1908 Web. 1913. 2*d.* (2*d.*)

EQUIPMENT Regulations :—

Part 1. 1912. [Reprinted, with Amendments, 1914.] *(In the press)*
Part 2. Details—

Sect.
I. Infantry. (Regular Army.) 1913. 6*d.* (5*d.*)
I*a*. Mounted Infantry. 1912. 6*d.* (5*d.*)
II. Cavalry. (Regular Army.) 1914. 3*d.* (3*d.*)
III. Army Service Corps. (Regular Army.) 1913. 6*d.* (5*d.*)
IV., IV*a*., and IV*b*. Army Ordnance Corps. Army Pay Corps. Army Veterinary Corps. (Regular Army.) 1914. 2*d.* (2*d.*)
V. Royal Army Medical Corps. (Regular Army.) 1914. 2*d.* (2*d.*)
VI.–IX. R.M. Academy; R.M. and Staff Colleges; Garrison Staff and Schools of Instruction; Military Prisons, Detention Barracks and Military Provost Staff Corps. (Regular Army.) 1914. 2*d.* (2*d.*)
X*a*. Engineer. General. Fortress, Survey, Railway, and Depôt Units. Peace and War. (Regular Army.) 1914. 2*d.* (2*d.*)
X*b*. Field Troop. (Regular Army.) 1912. 2*d.* (2*d.*)
X*c*. Field Company. (Regular Army.) 1914. 2*d.* (2*d.*)
X*d*. Divisional Signal Company. (Regular Army.) 1914. 2*d.* (2*d.*)
X*e*. Signal Company (Wireless). (Regular Army.) 1912. 2*d.* (2*d.*)
X*f*. Headquarters Signal Units. (Regular Army.) 1914. 2*d.* (2*d.*)
X*g*. Signal Company (Cable). (Regular Army.) 1912. 2*d.* (2*d.*)
X*h*. Signal Squadron. (Regular Army.) 1914. 2*d.* (2*d.*)
X*j*. Signal Troop with Cavalry Brigade. (Regular Army.) 1912. 2*d.* (2*d.*)
X*k*. Signal Troop with a Cavalry Brigade not allotted to a Cavalry Division. (Regular Army.) 1914. 2*d.* (2*d.*)
X*l*. Signal Company (South Africa). (Regular Army.) 1912. 2*d.* (2*d.*)
X*m*. Bridging Train. (Regular Army.) 1912. 2*d.* (2*d.*)
X*n*. Field Squadron. (Regular Army.) 1914. 2*d.* (2*d.*)
XI*a*. Horse Artillery. Q.F. 13-pr. 1913. 9*d.* (8*d.*)
XI*b*. Field Artillery. Q.F. 18-pr. (Regular Army.) 1914. 9*d.* (8*d.*)
XI*c*. Field Artillery. B.L. 5-in. Howitzer. 1908. 9*d.* (8*d.*)
XI*c*. Field Artillery. Q.F. 4·5-in. Howitzer. (Regular Army.) 1913. 9*d.* (8*d.*)
XI*d*. Reserve Brigades with Q.F. 18-pr. Equipment, Horse and Field Artillery, Staff and Depôts. Riding Establishment, School of Gunnery (Horse and Field), and Mounted Band. (Regular Army.) 1914. 6*d.* (6*d.*)
XI*e*. Mountain Artillery with B.L. 2·75-inch Equipment. Mountain Battery and Ammunition Column. Mule Transport. Provisional. (Regular Army.) 1914. 6*d.* (5*d.*)
XII*a*. Royal Garrison Artillery. (Regular Army.) 1914. 2*s.* 6*d.* (1*s.* 11*d.*)
XII*b*. Royal Garrison Artillery, Siege Artillery, Movable Armament, and Machine Guns in Armaments. 1913. 1*s.* (10*d.*)
XII*c*. Heavy Artillery. B.L. 60-pr. (Regular Army.) 1913. 9*d.* (8*d.*)
XIV. Cavalry School, Netheravon. (Regular Army.) 1914. 2*d.* (2*d.*)
XV. Camel Corps School, Egypt. (Regular Army.) 1914. 2*d.* (2*d.*)
XVI. Special Reserve. 1913. 4*d.* (4*d.*)
XVII. Officers Training Corps. 1912. 3*d.* (3*d.*)
Practice Batteries and Drill Guns (Fixed Mountings) of the Royal Garrison Artillery. (Part 2, Sections XII*a* and XVI, and Part 3.) 1909. 1*s.* 6*d.* (1*s.* 2*d.*)
Amendments to ditto. March 1911. 1*d.* (1*d.*)

Part 3. Territorial Force. 1914. 6*d.* (6*d.*)
Ditto. Details:—
Sec. IX. Artillery. 1912. 1*s.* (9*d.*)
Ditto. Amendments, April 1912; Feb. 1914. Each 1*d.* (1*d.*)
Sec. X. Engineer. 1912. 3*d.* (3*d.*)

(As to prices in brackets, see top of page 2.)

Equipment Regulations—*continued.*

Amendments to Parts 1 and 2. Jan., Feb., April, May, Aug., Sept., Dec. 1907; Mar. 1908; July 1909. Each 1*d.* (1*d.*)

Amendments to Part 2. Oct. (two issues), Nov. (two issues) 1910; June, Sept. 1911; Feb., April, July (two issues), Aug. 1914. Each 1*d.* (1*d.*)

Amendments to Parts 1, 2, and 3. Aug. 1908; April 1909; Jan., May, Aug., Dec. 1910; April, Aug. 1911; Nov. 1913. Each 1*d.* (1*d.*)

Amendments to Parts 1, 2, and 3. Oct. 1909; Feb. 1912; Mar., July 1913; April 1914. Each 2*d.* (2*d.*)

Amendments to Parts 2 and 3. Jan. 1909; Sept. 1912. Each 1*d.* (1*d.*)

ESTABLISHMENTS:—

PEACE:—

Part II. Territorial Force. 1913–14. 4*d.* (4*d.*) (*Under revision*)

Ditto. Changes in. Nov. 1913. 1*d.* (1*d.*)

Part III. Departmental and Miscellaneous Regular Establishments and Instructional Institutions. 1913–14. 2*d.* (2*d.*)

Part IV. Headquarters Establishments. Home, Colonies and India. 1913–14. 3*d.* (3*d.*)

Part V. Establishment of Commands Abroad and Summaries of the Military Forces of the Crown. 1913–14. 2*d.* (2*d.*)

WAR:—

Part I. Expeditionary Force. 1914. 8*d.* (8*d.*) (*Under revision*)

Part II. Territorial Force. 1911. 8*d.* (7*d.*)

Part V. Reserve, Depôt, and other Regimental Units maintained at Home after Mobilization. 1914. 4*d.* (4*d.*)

Part VI. Departmental and Miscellaneous Regular Establishments and Instructional Institutions maintained at Home after Mobilization. 1914. 2*d.* (2*d.*)

EXAMINATION PAPERS:—

Qualifying Certificates. Sept. 1905, March 1906, Sept. 1909, March, Sept. 1910, March, Sept. 1911; March 1912. Each 6*d.* (5*d.*)

Entrance: 1, R.M. Academy; 2, R.M. College. Nov.-Dec. 1905, June-July, Nov.-Dec. 1906, June-July, Nov.-Dec. 1907, June-July, Nov.-Dec. 1908, June-July, Nov.-Dec. 1910, June July, Nov.-Dec. 1911. Each 1*s.* (10*d.*)

Entrance: R.M. Academy, R.M. College, Qualifying Test for Commissions. Supplementary First Appointments in the Royal Marines. June-July 1912. 1*s.* (11*d.*)

Entrance: R.M. Academy, R.M. College, Qualifying Test for Commissions; Supplementary First Appointments in the Royal Marines; Appointments in the Indian Police Force; Appointments in the Police Force of the Straits Settlements; Cadetships in the Royal Navy (Special Entry). June-July 1913. 1*s.* (11*d.*)

Entrance: R.M. Academy, R.M. College, Qualifying Test for Commissions; Supplementary First Appointments in the Royal Marines; Appointments in the Indian Police Force; Appointments in the Police Forces of the Straits Settlements and the Federated Malay States; Cadetships in the Royal Navy (Special Entry). June-July 1914. 1*s.* (11*d.*)

Entrance: R.M. Academy, R.M. College, Qualifying Test for Commissions. Nov. 1912; Nov.-Dec. 1913. Each 1*s.* (11*d.*)

Freehand Drawing at the Army Entrance Examination of Nov. 1913. Specimen Question Papers to illustrate the kind of questions that will be set in. 6*d.* (5*d.*)

R.M. Academy, Fourth Class; and R.M. College, Fourth, Third, and Second Divisions. July, Dec. 1904, June 1905. Each 1*s.*

R.M. Academy, Fourth Class; and R.M. College, Senior Division. Dec. 1905, June, Dec. 1906, July, Dec. 1907. Each 1*s.*

(As to prices in brackets, see top of page 2.)

Examination Papers—*continued.*

Staff College. Admission. Aug. 1907, Aug. 1909, July 1911, June–July 1912, June–July 1913. Each 1*s.* (6*d.*)

Regular Forces, Canadian Permanent Forces, Special Reserve of Officers, Territorial Force, and Colonial Military Forces. May, Nov. 1906, May, Nov. 1908. Each 1*s.* (11*d.*)

Ditto. May 1909. 9*d.* (8*d.*)

Officers for Promotion. Dec. 1912; May, Dec. 1913; April 1914. Each 1*s.* (6*d.*)

Militia, Imperial Yeomanry, and University Candidates. Mar., Sept. 1904, Sept. 1905, Oct. 1906. Each 1*s.*

Special Reserve, Militia, Territorial Force, and University Candidates. Oct. 1911; March Oct. 1912; March, Oct. 1913. Each 1*s.* (6*d.*)

Special Reserve, Military, Territorial Force, Non-Commissioned Officers, and University Candidates. March 1914. 1*s.* (6*d.*)

Officers' Training Corps:—

Cadets of the Senior Division. Certificate A. Dec. 1908. 6*d.* (5*d.*)

Cadets of the Junior and Senior Divisions. Certificates A and B. Spring of 1909, Nov. 1909, Nov. 1910, May, Nov. 1911, March, Nov. 1912, March, Nov. 1913, March 1914. Each 6*d.* (6*d.*)

Foreign Languages. Modern. Oct. 1896; July, Oct. 1906; July 1908; April, July 1909; Jan., June, Oct. 1910; Jan., June, Oct. 1911; June 1912; June 1913; June 1914. Each 1*s.* (6*d.*)

EXPLOSIVES. Service. Treatise on. 1907. 1*s.* 6*d.* (1*s.* 2*d.*)

FIELD SERVICE. Manual for:—

Artillery. Field. Brigade. Q.F. 18-pr. 1908. 3*d.* (3*d.*) (*Under revision*)

Ditto. Ditto. (Howitzer) Brigade. 5-inch B.L. 1908. 3*d.* (3*d.*)

Ditto. Heavy (B.L. 60-pr.) Battery and Ammunition Column. Expeditionary Force. 1910. 3*d.* (3*d.*)

Ditto. Horse. Brigade. 13-pr. Q.F. 1908. 3*d.* (3*d.*) (*Under revision*)

Ditto. Ditto. Appendix to. R.H.A. Battery and Mounted Brigade Ammunition Column. 1*d.* (1*d.*)

Cavalry Regiment. Expeditionary Force. 1913. 3*d.* (3*d.*) (*Under revision*)

Engineers. Balloon Company. Expeditionary Force. 1910. 3*d.* (3*d.*)

Ditto. Bridging Train. Expeditionary Force. 1910. 3*d.* (3*d.*)

Ditto. Field Company. Expeditionary Force. 1914. 3*d.* (3*d.*)

Ditto. Field Squadron. Expeditionary Force. 1914. 3*d.* (3*d.*)

Ditto. Field Troop. Expeditionary Force. 1910. 3*d.* (3*d.*)

Ditto. Works Company. Expeditionary Force. 1910. 3*d.* (3*d.*)

Headquarters Units. Expeditionary Force. 1911. 3*d.* (3*d.*)

Infantry Battalion. Expeditionary Force. 1914. 3*d.* (3*d.*) (*In the press*)

Infantry (Mounted) Battalion. Expeditionary Force. 1913. 3*d.* (3*d.*)

Medical Service. Army. Expeditionary Force. 1914. 3*d.* (3*d.*) (*In the press*)

Signal Service. Signal Company (Air-Line). Expeditionary Force. 1913. 3*d.* (3*d.*)

Ditto. Ditto. (Cable). Expeditionary Force. 1913. 3*d.* (3*d.*)

Ditto. Ditto. (with Division). Expeditionary Force. 1913. 3*d.* (3*d.*)

Ditto. Ditto. (Lines of Communication). Expeditionary Force. 1914 3*d.* (3*d.*)

FIELD SERVICE POCKET BOOK. 1913. 1*s.* (11*d.*)

Ditto. Amendments. Set 1, April 1914. 1*d.* (1*d.*); Set 2, April 1914. 2*d.* (2*d.*)

(As to prices in brackets, see top of page 2.)

FIELD SERVICE REGULATIONS:—

Part I. Operations. 1909. [Reprinted, with Amendments, 1914.] 6*d.* (*In the press*)

Part II. Organization and Administration. 1909. [Reprinted, with Amendments, 1913]. 1*s.* (10*d.*)

Ditto. Amendments, Feb. 1914. 1*d.* (1*d.*)

FINANCIAL INSTRUCTIONS IN RELATION TO ARMY ACCOUNTS. 1910. [Reprinted, with Amendments to Sept., 1914.] 4*d.* (4*d.*); Appendix II. *Payment of Units proceeding to or from India as Ordinary Reliefs at Indian expense.* 1912. 1*d.* (1*d.*)

FLYING CORPS. ROYAL. Training Manual:—

Part I. Provisional. 1914. 1*s.* (10*d.*)

Part II. Military Wing. Provisional. 1914. 3*d.* (4*d.*)

FOREIGN LANGUAGES, STUDY OF. Regulations. 1913 2*d.* (2*d.*)

FORTIFICATION, PERMANENT. For the Imperial Military Training Establishments and for the Instruction of Officers of all Arms of the Austro-Hungarian Army. 7th Edition. Translated. 4*s.* (2*s.* 11*d.*)

FRANCO-GERMAN WAR, 1870-71. Translated from the German Official Account. Five Vols. £6 11*s.* 6*d.*

Also separately, in Volumes in cloth, Sections in paper covers, and Plans unmounted:—

First Part—History of the War to the Downfall of the Empire—

Vol. 1 (Secns. 1 to 5). Outbreak of Hostilities to Battle of Gravelotte. £1 6*s.* (*Out of print*)

Vol. 2 (Secns. 6 to 9). Battle of Gravelotte to Downfall of the Empire. £1 2*s.* (*Out of print*)

Second Part—History of the War against the Republic—

Vol. 1 (Secns. 10 to 13). Investment of Paris to Re-occupation of Orleans by the Germans. £1 6*s.* (18*s.* 6*d.*)

Vol. 2 (Secns. 14 to 18). Events in Northern France from end of Nov. In North-west from beginning of Dec. Siege of Paris from commencement of Dec. to the Armistice. Operations in the south-east from middle of Nov. to middle of Jan. £1 6*s.* (19*s.*)

Vol. 3 (Secns. 19 and 20). Events in South-east France from middle of Jan. to Termination of Hostilities. Rearward Communications. The Armistice. Homeward March and Occupation. Retrospect. £1 11*s.* 6*d* (£1. 2*s.* 6*d.*)

Section.

1. Events in July. Plan. 3*s.* (2*s.* 2*d.*)
2. Events to Eve of Battles of Wörth and Spicheren. 3rd edition. 3*s.* (*Out of print*)
3. Battles of Wörth and Spicheren. 3rd edition. 5*s.* (*Out of print*)
4. Advance of Third Army to the Moselle, &c. 2nd edition. 4*s.* (*Out of print*)
5. Operations near Metz on 15th, 16th, and 17th August. Battle of Vionville—Mars la Tour. 2nd edition. 6*s.* 6*d.* (*Out of print*)
6. Battle of Gravelotte—St. Privat. 5*s.* (*Out of print*)
7. Advance of Third Army and of Army of the Meuse against Army of Chalons. 6*s.* (*Out of print*)
8. Battle of Sedan. 3*s.* (*Out of print*)
9. Proceedings on German Coast and before Fortresses in Alsace and Lorraine. Battle of Noisseville. General Review of War up to September. 4*s.* 6*d.* (3*s.* 4*d.*)
10. Investment of Paris. Capture of Toul and Strassburg. 6*s.* (4*s.* 6*d.*)
11. Events before Paris, and at other points of Theatre of War in Western France until end of October. 5*s.* 3*d.* (3*s.* 11*d.*)
12. Last Engagements with French Army of the Rhine. Occurrences after fall of Strassburg and Metz to middle of November. 4*s.* 6*d.* (3*s.* 6*d.*)

(As to prices in brackets, see top of page 2.)

Franco-German War—*continued.*

Section.

13. Occurrences on Theatre of War in Central France up to Re-occupation of Orleans by the Germans. 6*s.* (4*s.* 6*d.*)
14. Measures for Investment of Paris up to middle of December. 4*s.* (3*s.*)
15. Measures for protecting the Investment of Paris and Occurrences before French Capital to commencement of 1871. 2*s.* 6*d.* (1*s.* 11*d.*)
16. Proceedings of Second Army from commencement of 1871 until the Armistice. 3*s.* 6*d.* (2*s.* 8*d.*)
17. Proceedings of First Army from commencement of 1871 until the Armistice. 3*s.* (2*s.* 3*d.*)
18. Occurrences on South-eastern Theatre of War up to middle of Jan. 1871. Events before Paris from commencement of 1871 to the Armistice. 8*s.* (6*s.*)
19. Occurrences on South-eastern Theatre of War from middle of January, 1871. Proceedings in rear of German Army and in Coast Provinces from Nov., 1870 until the Armistice. 13*s.* 6*d.* (9*s.* 8*d.*)
20. General Retrospect of War from beginning of Sept., 1870 to Cessation of Hostilities. Armistice and Peace Preliminaries. Return of German Army and Peace of Frankfort. The Occupation. The Telegraph, Post, Supply of Ammunition, Commissariat, Hospital Service, Divine Service, Military Justice, Recruitment, and Home Garrisons. Results. 5*s.* (3*s.* 9*d.*)

Analytical Index. 1*s.* 6*d.* (1*s.* 1*d.*)

Plans—

4. Battle of Colombey-Nouilly. 3*d.* (3*d.*)
5A. Battle of Vionville—Mars la Tour. Position of Contending Forces at Noon. 3*d.* (3*d.*)
5B. Battle of Vionville—Mars la Tour. Position of Contending Forces from 4 to 5 p.m. 3*d.* (3*d.*)
9A. Battle of Sedan. Position of Contending Forces towards Noon. 3*d.* (3*d.*)
9B. Battle of Sedan. Position of the Germans in the afternoon shortly before the end of the struggle. 3*d.* (3*d.*)

(*See also* SIEGE OPERATIONS.)

GERMAN ARMY. Cavalry. Drill Regulations. 1909. 3*d.* (3*d.*)
Ditto. Field Service Regulations. 1908. 1*s.* (10*d.*)
Ditto. Foot Artillery. Drill Regulations. Part IV. THE FIGHT. 1909. 3*d.* (3*d.*)
Ditto. Manœuvres Regulations. 1908. 3*d.* (3*d.*)

GERMANY. The Campaign of 1866 in. With 22 Plans in portfolio. 1872 (Reprinted 1907). 6*s.* (4*s.* 10*d.*)
Ditto. Moltke's Projects for. 1*s.* (10*d.*)

GUERNSEY AND ALDERNEY ROYAL MILITIA. Regulations. With the Militia Laws relating to the Islands. Provisional. 3*s.*

GUNS. Drill for. (*And see* **GUNS.** Handbooks for):—
60-pr. B.L. 1912. 1*d.* (1*d.*)
18-pr. Q.F. 1914. 1*d.* (1*d.*)
15-pr. B.L.C. 1914. 1*d.* (1*d.*)
15-pr. Q.F. 1912. 1*d.* (1*d.*)
13-pr. Q.F. 1914. 1*d.* (1*d.*)
12-pr. 12-cwt. Q.F. Land Service. 1914. 1*d.* (1*d.*)
10-pr. B.L. 1914. 1*d.* (1*d.*)
9·2-inch B.L. Mark IX., on Mark IV. Mounting. Land Service. 1914. 1*d.* (1*d.*)
9·2-inch B.L. "C" Mark IX., on Marks VA. and VB. Mountings. Land Service. 1914. 1*d.* (1*d.*)

(As to prices in brackets, see top of page 2.)

GUNS. Drill for—*continued.*

9·2-inch B.L. Marks X., X*., and X**., on Mark V. Mounting. Land Service. 1914. 1*d.* (1*d.*)

6-inch B.L. Marks VII. and VII*. Land Service. 1914. 1*d.* (1*d.*)

6-inch B.L. Howitzer. 1912. 1*d.* (1*d.*)

6-inch Q.F. Land Service. 1914. 1*d.* (1*d.*)

5-inch B.L. Howitzer. 1912. (Reprinted as 1914 with Amendments.) 1*d.* (1*d.*)

4·7-inch Q.F. Fixed Armament. Land Service. 1914 1*d.* (1*d.*)

4·7-inch Q.F., on Travelling Carriages. 1912. 1*d.* (1*d.*)

4·7-inch Q.F. Heavy Batteries. Provisional. 1914. 1*d.* (1*d.*)

4·5-inch Q.F. Howitzer. 1914. 1*d.* (1*d.*)

4-inch Q.F. Land Service. 1914. 1*d.* (1*d.*)

2·95 inch Q.F. 1914. 1*d.* (1*d.*)

GUNS. Handbooks for. (*And see* **GUNS.** Drill for):—

60-pr. B.L. Land Service. 1913. 1*s.* 6*d.* (1*s.* 3*d.*)

18-pr. Q.F. Land Service. 1913. (Reprinted, with Amendments, 1914.) (*In the press*)

15-pr. B.L.C. Marks I., II., II.*, and IV., with Mark I. Carriage, and Marks I., I*a.*, I*b.*, and I*c.* Limbers and Wagons. Land Service, 1912. 1*s.* (10*d.*)

15-pr. Q.F. Land Service. 1914. 1*s* 6*d.* (1*s.* 2*d.*)

13-pr. Q.F. Land Service. 1913. (Reprinted, with Amendments, 1914.) (*In the press*)

12-pr. B.L. of 6 cwt. Marks I. to IV. and IV*a* and Carriages Marks I * I.**, and II. Horse Artillery. 1905. 1*s.* (11*d.*)

10-pr. Jointed B.L. Mule Equipment. 1914. 1*s.* 6*d.* (1*s.* 2*d.*)

9·45-inch B.L. Howitzer. 1906. 9*d.* (7*d.*)

9·2-inch B.L. Mark IX., "C" Mark IX., and Marks X., X*., and X**. Land Service. 1912. 1*s.* (11*d.*)

8-inch R.M.L. Howitzer of 70 cwt. Movable Armament and Armament of Works. Land Service. 1901. 2*s.* (1*s.* 6*d.*)

6-inch B.L. and B.L.C. Guns, Mountings, &c. 1904. 1*s.* 6*d.* (1*s.* 4*d.*)

6-inch B.L. Marks VII. and VII*. Land Service. 1911. 9*d.* (8*d.*)

6-inch B.L. Howitzer, 30 cwt. Marks I. and I.* 1912. 1*s.* (10*d.*)

6-inch Q.F. Land Service. 1903. 1*s.* (10*d.*)

6-inch "B" Q.F. Land Service. 1911. 1*s.* (10*d.*)

5·4-inch B.L. Howitzer. Mark. I. 1902. 1*s.* 6*d.* (1*s.* 2*d.*)

5-inch B.L. Marks I.—V. 1904. 9*d.* (9*d.*)

5-inch B.L. Marks IV.—V. Land Service. 1903. 1*s.* 6*d.* (1*s.* 2*d.*)

5-inch B.L. Howitzer. 1909. 9*d.* (9*d.*)

4·7-inch Q.F. Fixed Armaments. Land Service. 1904. 1*s.* (11*d.*)

4·7-inch Q.F.B., on Travelling Carriages. Land Service. 1910 (Reprinted, with Amendments, 1914.) 9*d.* (9*d.*) (*In the press*)

4·5-inch Q.F. Howitzer. Land Service. 1914. 1*s.* 3*d.* (1*s.* 1*d.*)

2·95-inch Q.F. Mule Equipment and Man Transport Equipment. 1914. 2*s.* (1*s.* 6*d.*)

·303-inch and ·303-inch Converted Maxim Machine (Magazine Rifle Chamber), on Carriages, M.G., Infantry, Parapet; Tripod and Cone Mountings. 1911. 9*d.* (8*d.*)

Ditto, Amendments. Oct. 1914. 1*d.* (1*d.*)

0·303-inch Nordenfelt 8-barrel and Gardner 2-barrel converted from 0·4-inch and 0·45-inch M.H. Chamber, Magazine Rifle Chamber, on Carriages, 1900. 9*d.* (8*d.*)

HISTORICAL RECORDS OF THE BRITISH ARMY, viz.:—

Horse Guards; 17th Dragoons (Lancers). Each 5*s.* (3*s.* 7*d.*)

Dragoon Guards, 3rd, 4th, 5th, 6th, and 7th. Each 4*s.* (3*s.*)

(As to prices in brackets, see top of page 2.)

Historical Records—*continued.*

Dragoons, 1st, 3rd, 6th, 7th, 14th, and 16th. Each 4*s.* (3*s.*)
Ditto. 12th, and 13th. Each 3*s.* (2*s.* 3*d.*)
Marine Corps. 3*s.* (2*s.* 2*d.*)
Foot, 2nd, 5th, 6th, 7th, 8th, 10th, 11th, 13th, 15th, 16th, 17th, 18th, 19th, 20th, 21st, 22nd, 34th, 36th, 39th, 46th, 53rd, 67th, 71st, 72nd, 73rd, 74th, 86th, 87th, and 92nd. Each 4*s.* (3*s.*)
Do. 14th, 56th, 61st, 70th, and 88th. Each 3*s.* (2*s.* 3*d.*)

HISTORIES, SHORT, OF THE TERRITORIAL REGIMENTS OF THE BRITISH ARMY. 67 numbers, each 1*d.* In one volume, 5*s.*
Ditto. The Scots Guards. 1*d.* (1*d.*)
Ditto. The 6th (Inniskilling) Dragoons. 1*d.* (1*d.*)
Ditto. Revised Editions. 1*d.* (1*d.*) each :—

Alexandra, Princess of Wales's Own (Yorkshire Regiment).
The Bedfordshire Regiment.
The Black Watch (Royal Highlanders).
The Cameronians (Scottish Rifles).
The Cheshire Regiment.
The Duke of Wellington's West Riding Regiment.
The Durham Light Infantry.
The East Lancashire Regiment.
The East Surrey Regiment.
The Hampshire Regiment.
The Highland Light Infantry.
The King's Own Yorkshire Light Infantry.
The Lancashire Fusiliers.
The Northamptonshire Regiment.
The Oxfordshire and Buckinghamshire Light Infantry.
The Prince Albert's (Somersetshire Light Infantry).
The Prince of Wales's Leinster Regiment (Royal Canadians).
The Princess Charlotte of Wales's (The Royal Berkshire Regiment).
The Princess Louise's Argyll and Sutherland Highlanders.
The Royal Inniskilling Fusiliers.
The Royal Sussex Regiment.
The Royal Warwickshire Regiment.
The Royal Welsh Fusiliers.
The Suffolk Regiment.

HOSPITALS. MILITARY FAMILIES'. Nursing Staff Regulations, Dec., 1909. 1*d.* (1*d.*)

HOSTILITIES WITHOUT DECLARATION OF WAR FROM 1700 TO 1870. 2*s.* (1*s.* 7*d.*)

HYGIENE. ELEMENTARY MILITARY. Manual of. 1912. 6*d.* (6*d.*)

INDIAN EMPIRE. OUR. A Short Review and some Hints for the use of Soldiers proceeding to India. 6*d.* (6*d.*)

INFANTRY TRAINING. (4-Company Organization.) 1914. 6*d.* (6*d.*)

INSTITUTES. Garrison and Regimental. Rules for the Management of. 1912. 1*d.* (1*d.*)

INTELLIGENCE DUTIES IN THE FIELD. Regns. for. 1904. 2*d.* (2*d.*)

ITALIAN CAVALRY TRAINING REGULATIONS. 1911. Training for Marches, Tactics of Minor Units, and Training of Patrols. Translated. 4*d.* (3*d.*)

JAMAICA. Standing Orders. 1912. 1*s.* (9*d.*)

JERSEY. ROYAL MILITIA OF THE ISLAND OF. Regulations. 1914. With the Jersey Militia Law, 1905. 1*s.* 3*d.* (11*d.*)

KING'S REGULATIONS AND ORDERS FOR THE ARMY. 1912. [Reprinted, with Amendments up to Aug. 1914.] 1*s.* 6*d.* (1*s.* 4*d.*)
(In the press)

DEFENCE INFORMATION SERVICES
01047717 4
ADCMPA
UK/S/MISC/MANU1(12)/A

[*Crown copyright reserved.*

HQTC-A
MILPAM ARCHIVES
ARMY DOCTRINE CENTRES

MANUAL

OF

MAP READING

AND

FIELD SKETCHING.

1912.

(Reprinted, with additions, 1914.)

GENERAL STAFF—WAR OFFICE.

LONDON:
PRINTED UNDER THE AUTHORITY OF HIS MAJESTY'S
STATIONERY OFFICE
BY EYRE AND SPOTTISWOODE, LTD., EAST HARDING STREET E.C.,
PRINTERS TO THE KING'S MOST EXCELLENT MAJESTY.

To be purchased, either directly or through any Bookseller, from
WYMAN AND SONS, LTD., 29, BREAMS BUILDINGS, FETTER LANE, E.C., and
54, ST. MARY STREET, CARDIFF; or
H.M. STATIONERY OFFICE (SCOTTISH BRANCH), 23, FORTH STREET, EDINBURGH, or
E. PONSONBY, LTD., 116, GRAFTON STREET, DUBLIN;
or from the Agencies in the British Colonies and Dependencies,
the United States of America, the Continent of Europe and Abroad of
T. FISHER UNWIN, LONDON, W.C.

1914.

Price One Shilling.

This Manual is issued by command of the Army Council for the guidance of all concerned.

WAR OFFICE,

29th October, 1914.

CONTENTS.

PART I.

			PAGE
CHAPTER	I.	INTRODUCTION	5
,,	II.	DEFINITIONS	8
,,	III.	SCALES	11
,,	IV.	CONVENTIONAL SIGNS AND LETTERING	17
,,	V.	BRITISH AND FOREIGN MAPS, AND METHODS OF REPRESENTING HILL FEATURES	20
,,	VI.	COPYING AND ENLARGING MAPS	25
,,	VII.	THE SERVICE (PRISMATIC) COMPASS AND PROTRACTOR. THEIR USE IN MAP READING AND MARCHING	29
,,	VIII.	APPROXIMATE METHODS OF FINDING THE TRUE NORTH	40
,,	IX.	MAP READING	41
,,	X.	GENERAL PRINCIPLES OF SKETCHING	47
,,	XI.	SKETCHING WITH A CAVALRY SKETCHING BOARD	51
,,	XII.	ENLARGING SMALL SCALE MAP AND ADDING EXTRA INFORMATION ON THE GROUND.—REPORTS ...	55
,,	XIII.	EYE AND MEMORY SKETCHING	64

PART II.

CHAPTER	XIV.	PLANE-TABLE SKETCHING	67
,,	XV.	PANORAMA DRAWING	74
,,	XVI.	ELEMENTARY INSTRUCTION IN MARCHING BY THE STARS	81
APPENDIX	I.	FOREIGN MEASURES	82
,,	II.	THE ANEROID BAROMETER	83
,,	III.	*FINISHING UP* SKETCHES FOR TACTICAL SCHEMES	84
,,	IV.	MUTUAL VISIBILITY OF POINTS	86
,,	V.	NOTES ON THE MAPS ISSUED BY THE GEOGRAPHICAL SECTION OF THE GENERAL STAFF FOR THE USE OF THE BRITISH EXPEDITIONARY FORCE ON THE CONTINENT	89
INDEX	...	... ...	94

z (33)24475 Wt 26060—235 75,000 11/14 E & S A 2

LIST OF PLATES.

PLATE	1.	SCALES	TO FACE PAGE 13
„	2.	CONVENTIONAL SIGNS AND LETTERING USED IN FIELD SKETCHING	„ „ 17
„	3.	CONVENTIONAL SIGNS AND LETTERING USED ON ORDNANCE SURVEY MAPS ...	„ „ 19
„	4.	SLOPES	„ „ 24
„	5.	HACHURING AND CONTOURS (1" O.S. MAP)	AT END OF BOOK
„	6.	COLOURED MAP	„ „ „
„	7.	INDIAN MAP	„ „ „
„	8.	„ „	„ „ „
„	9.	CANADIAN MAP	„ „ „
„	10.	GERMAN MAP	„ „ „
„	11.	FRENCH MAP	„ „ „
„	12.	MAP OF SWEDEN ON THE LAYER SYSTEM	„ „ „
„	13.	PRISMATIC COMPASS	TO FACE PAGE 30
„	14.	SERVICE PROTRACTOR	„ „ 33
„	15.	LINES OF EQUAL MAGNETIC VARIATION	„ „ 40
„	16.	PLANE TABLE	„ „ 67
„	17.	CONVENTIONAL METHODS OF SHOWING OBJECTS IN NATURE	AT END OF BOOK
„	18.	LANDSCAPE SKETCH OF FOX HILLS ...	„ „ „
„	19.	PANORAMA FOR USE FROM AN ARTILLERY POSITION	„ „ „
„	19A.	RANGE-TAKERS' CARD	„ „ „
„	20.	EXAMPLE OF A LANDSCAPE SKETCH (CHITRAL EXPEDITION)	„ „ „
„	21.	EXAMPLE OF A LANDSCAPE SKETCH (BATTLE OF LIAO-YANG)	„ „ „
„	22.	SPECIAL ½" MAP OF ENGLAND FOR TRAINING PURPOSES	„ „ „
„	23.	$\frac{1}{253440}$ OR ¼" MAP OF N.W. EUROPE ...	„ „ „
„	24.	BELGIUM. $\frac{1}{100000}$ TACTICAL MAP ...	„ „ „
„	25.	INDEX TO FRENCH $\frac{1}{80000}$ AND BELGIAN $\frac{1}{100000}$ MAPS	„ „ „

Note.—Plates 5, 6, 7, 8, and 12 have not been included in this edition, but four new plates have been added.

MANUAL

OF

MAP READING

AND

FIELD SKETCHING.

PART I.

CHAPTER I.

Introduction.

1. This manual is intended for the use of candidates for commissions in the regular army, cadets of the Royal Military Academy and of the Royal Military College, and for the instruction of officers and non-commissioned officers in map reading and in making field sketches for military purposes.

All regimental officers must be so trained as to be proficient in the following subjects :—

i. Map reading.
ii. Map enlarging.
iii. Adding topographical information to an existing map or to an enlargement.
iv. A certain amount of sketching on blank paper.

Selected officers, who show special aptitude in iv, should receive further instruction in sketching on blank paper (*see* Part II).

i. *Map reading.*

An officer, or non-commissioned officer, may be said to be proficient in map reading when on examination a map conveys to him a clear impression of the ground features as represented by contours or shading, and of all the natural or artificial features exhibited on the map. Further, he should be able to identify his position on the ground quickly and to recognize all visible objects marked on the map.

This requires close study and constant practice, and is an important branch of military education.

ii. *Map enlarging.*

This should be executed by the methods described in Chapter VI; usually the scale of the enlargement will not exceed 4 inches to 1 mile.

iii. *Adding topographical information to a map.*

This comprises one of the most probable and most important duties in sketching that an officer may be detailed to carry out in the field. Troops will rarely now be operating in an entirely unmapped country, but the existing maps will often fail to give the military information which is essential to the conduct of operations. Officers may therefore be employed on service, on work of this nature.

iv. *Sketching on blank paper.*

It will occur, though possibly rarely, that no map exists of a locality. It is therefore necessary that officers should be able to make a sketch. Such a sketch is not intended to be an accurate survey, but must include all information which is likely to affect the military object in view.

It should also be remembered that a rough sketch to an approximate scale is a valuable addition to a written report on a locality, and should be executed whenever time permits, if it is not possible to enlarge an existing map and add such information as is necessay to the enlargement.

2. A military map or field sketch should show all the features of, or in, a country, natural and artificial, which are of importance from a military point of view, *i.e.*, those which might affect the dispositions, movements, security, or supply of troops. A military *map* is the work of a trained *surveyor*, using special instruments and elaborate methods, with unlimited time at his disposal, and aiming at minute accuracy. A field *sketch* is a sketch of ground made with such instruments and under such conditions regarding time, weather, etc., as generally exist in the field.

3. Military *maps* may be conveniently classified into strategical maps on very small scales, small scale maps, and large scale maps.

Strategical maps are used for conducting the operations of an army as a whole. Examples of this class are the $\frac{1}{1000000}$ (about 16 miles to 1 inch) and the 6 mile to 1 inch map of Belgium and N.E. France.

Small-scale maps, such as maps on the scale of 1 inch, $\frac{1}{2}$ inch, or $\frac{1}{4}$ inch to the mile (or similar scales) are required to assist troops to manœuvre and fight. Of these, maps on the scale of 1 inch to the mile will usually only be available for the use of the higher commanders and their staffs. Subordinate commanders and regimental officers will normally be supplied with maps on the scale of $\frac{1}{2}$ inch or $\frac{1}{4}$ inch to the mile.

Large scale maps (2 inches to 1 mile and upwards) are not always available in war. When available they would only be issued to certain units in small quantities. They are especially useful, when squared, to heavy artillery working in co-operation with aeroplanes.

4. Field *sketches*, which are usually made on a scale of from 1 to 4 inches to 1 mile, are of two kinds. They may be occasionally required to illustrate in detail the disposition of troops, to indicate lines of advance in attack, or to represent minor features of ground of tactical importance when maps are not available for enlargement. Such sketches should be as accurate as time and the means available will permit, but the minute accuracy which is required by the surveyor in the production of his map is not expected and should not be attempted. These sketches are executed by officers who have received special instruction, and are usually carried out with special instruments, such as the plane table.

Rough field sketches are also required in the circumstances described in para. **1** iv above. Every regimental officer, and

a proportion of non-commissioned officers, should be able to make such sketches with such instruments as they are likely to have on service. These instruments are:—

i. The service compass.
ii. The service protractor.
iii. The cavalry sketching board, or some improvised form of sketching board.

5. This manual is therefore divided into two parts.

Part I.—The elementary instruction, embracing map reading and such field sketching as is likely to be required of regimental officers and non-commissioned officers on active service.

Part II.—Further instructions in field sketching for officers who may be employed on special duty.

CHAPTER II.

Definitions.

6. *Topographical forms.*

Basin: A term used to describe (*a*) a small area of level ground surrounded or nearly surrounded by hills; and (*b*) a district drained by a river and its tributaries, as the "basin of the Thames."

Col: A depression between two adjacent mountains or hills; or a break in a ridge; or the neck of land which connects an outlying feature with a range of mountains or hills, or with a spur.

Crest: The edge of the top of a hill or mountain; the position at which a gentle slope changes to an abrupt one; the top of a bluff or cliff.

Escarpment: An extended line of cliffs or bluffs.

Gorge: A rugged and deep ravine.

Knoll: A low detached hill.

Plateau: An elevated plain.

Re-entrant: A valley or depression running into a main feature.

Saddle: A col.

Spur: A projection from the side of a hill or mountain running out from the main feature.

Underfeature: A minor feature, an offshoot of a main feature.

Watercourse: The line defining the lowest part of a valley, whether occupied by a stream or not.

Watershed: A ridge of high land separating two drainage basins; the summit of land from which water divides or flows in two directions. A watershed does not necessarily include the *highest points* of a chain of mountains or range of hills.

This list does not profess to be exhaustive; there are many terms in common use such as hill, mountain, river, slope, island, pass, cliff, &c., which it does not appear necessary to define.

7. *Technical terms.*

Angle: Back-angle, the direction or bearing in a traverse of a station which has been passed.

Closing-angle, the bearing taken from the last station in a traverse to some fixed point, to ascertain whether the traverse closes satisfactorily.

Forward-angle, the forward direction or bearing from one station in a traverse to the next in succession.

Base, or **Base-line:** A carefully chosen and accurately measured line upon which a triangulation depends.

Bearing: True bearing is the angle a line makes with the true north line.

Magnetic bearing is the angle a line makes with the magnetic north line.

In each case the angle is measured from North by East and South, *i.e.*, in the same direction as the hands of a watch move.

Ray: A line drawn to represent the direction of an object without reference to the points of the compass.

Contour: The representation of an imaginary line running along the surface of the ground at the same height above mean-sea-level throughout its length. Contours may also be defined as the plans of the lines at which a water surface (of the ocean, for instance) would intersect the surface of the earth were it raised successively by equal amounts.

Datum, or **Datum-level:** An assumed level to which altitudes are referred.

Fall of a river: Its slope, usually measured in inches (or feet) per mile; thus 9 inches per mile.

Form-line: An approximate contour; a sketch contour.

Gradient: A slope expressed by a fraction. Thus $\frac{1}{30}$ represents a rise or fall of 1 foot in 30 feet.

Hachures: Vertical hachuring is a conventional method of representing hill features by shading in short disconnected lines drawn directly down the slopes in the direction of the flow of water on the slopes. (*See* Plates 5, 10, and 11.)

Horizontal Equivalent: Sometimes written H.E., is the distance in plan between two adjacent contours measured in yards. In Fig. 1, if S.L. is a slope, H.E. is the horizontal equivalent for that particular slope and vertical interval (*see* definition below).

FIG. 1.



Local Magnetic Attraction: The deviation of the magnetic needle of a compass from its mean position owing to the presence of masses of magnetic iron-ore or of iron in the neighbourhood.

Meridian or **Meridian-line:** A true north and south line.

Magnetic Meridian: A magnetic north and south line.

Magnetic Variation: The angle between the true north and the magnetic north. This angle varies slightly from year to year. It is called E. or W. variation, according as the magnetic N. is E. or W. of the true N.

Orienting or **Setting** a map or plane-table is the process of placing the map or plane-table so that the north line points north.

Plotting: The process of laying down on paper field observations and measurements.

Resection: A method by which the sketcher determines his position by observing the bearings of, or drawing lines from, at least two previously fixed points.

Section: The outline of the intersection of the surface of the ground by a vertical plane.

Spot Level: The record on a map of the exact height of a particular point.

Traverse: The survey of a road, river, or track by measuring a continuous series of straight lines along its course and the angles at their junctions.

Triangulation: The process of fixing the position of points on the area to be surveyed, by means of a measured base and a network of triangles dependent on it.

Vertical Interval: Sometimes written V.I., and always given in feet, is the difference of level between two adjacent contours.

L.F. in Fig. 1 is the vertical interval between contours at L. and S.

CHAPTER III.

Scales.

8. The word **scale** is used to denote the proportion which a distance between any two points on a sketch or map bears to the horizontal distance between the same two points on the ground. Thus, if the distance between two farms on a map be 1 inch, and the horizontal distance on the ground be 2 miles, the scale of the map will be 1 inch to 2 miles. Similarly the statement that a map is on a scale of $\frac{1}{250000}$ implies that a distance of 1 inch on the map represents an actual distance of 250,000 inches, or 3·95 miles.

(1) Scales on maps of the United Kingdom, India, and Canada are usually expressed in words showing the relation between inches on the map and miles on the ground, thus 1 inch to 1 mile, ½ inch to 1 mile, &c.

(2) Foreign maps and maps of British African Colonies and possessions are constructed on scales which bear the proportion of 1 to some multiple of 10, such as 1 to 250,000 or 1 to 1,000,000.

The scale adopted for the military map of South Africa is 1 to 250,000.

The following examples are explanatory of the two methods of expressing scales :—

(i.) Scale $\frac{1}{63360}$, or 1 inch to 1 mile.

(ii.) 1 : 100,000 (or $\frac{1}{100000}$), or (on a Foreign map) 1 centimetre to 1 kilometre.

The fraction in each case is called the **Representative Fraction** or **R.F.,** and means that 1 unit on the map (numerator) represents a certain number of the same units on the ground (denominator), thus from i above—

1 inch on the map represents 63,360 inches on the ground (= 1 mile);

from ii

1 inch on the map represents 100,000 inches on the ground (= 1·58 miles); or 1 centimetre on the map represents 100,000 centimetres (= 1 kilometre) on the ground.

The advantage of (i) is that the eye, having once been trained to recognise the length of an inch on paper, can readily estimate the distance between any two points on a map with considerable accuracy.

To find the number of English miles to the inch for any map that has a R.F., divide the denominator of the R.F. by 63,360; this gives the number required : thus if R.F. is $\frac{1}{50000}$, then the number of miles to the inch = $\frac{50000}{63360}$ = 1·26.

To find the number of inches to the mile, divide 63,360 by the denominator of the R.F.: thus, if R.F. is $\frac{1}{50000}$, then the number of inches to the mile = $\frac{63360}{50000}$ = ·79.

9. The measure of length which a scale is to show, whether feet, yards or miles, is termed the *unit of measure*, and scales are usually, though not necessarily, constructed of such a length as to represent a distance which is a multiple of ten such units, as 100 feet, 50 yards, 80 miles.

A scale should usually be from 4 to 6 inches long, and to construct it the number of tens, hundreds, or thousands of the "unit of measure," which will occupy such a length on paper, should be calculated.

10. The size of the scale generally used for field sketches depends mainly on the object with which the sketch is made, and the amount of topographical information which is required to be given. Reconnaissance sketches of an area of ground to explain a plan of attack, or to show lines of advance, of a road or river, or of a defensive or

PLATE I.
To face page 13.

Scale $\frac{1}{15840}$, or 4 inches to 1 mile.



Scale $\frac{1}{31680}$, or 2 inches to 1 mile.



Scale $\frac{1}{100,000}$, or 1 inch to 1·58 miles



1771

H & C. GRAHAM LTD, LITHOS, LONDON, S.E.

outpost position, are usually made on scales ranging from 1 to 4 inches to 1 mile. Sketches which may be required for the defence of a village or town, or for the selection of a camp or billeting area, are generally made on the scale of 4 inches to 1 mile.

11. The service protractor (*see* Plate 14) shows scales of $\frac{1}{2}$ inch, 1 inch, 2 inches and $2\frac{1}{2}$ inches to 1 mile; also scales of miles for R.F's. of $\frac{1}{80000}$, $\frac{1}{100000}$ and $\frac{1}{250000}$, and a scale of kilometres for $\frac{1}{100000}$ (1 centimetre = 1 kilometre). Thus the *normal* scales of English and foreign maps can be drawn from the protractor.

Example.—To draw a scale of 4 inches to 1 mile to show divisions of 100 yards from the protractor. Here the most convenient scale shown on the protractor is that of 2 inches to 1 mile. The distances shown on this scale are twice those on the scale to be drawn. The scale is to be between 4 and 6 inches in length. On measuring off 4 inches from the scale of inches on the back of the protractor and applying this distance to the 2 inches to 1 mile scale, it is found that 4,000 yards is the nearest convenient round number, which gives a length of more than four inches. Draw a line equal in length to 4,000 yards on the 2 inches to 1 mile scale, this line represents 2,000 yards on the scale of 4 miles to 1 inch. Divide this line into 4 equal parts, each representing 500 yards. This can be done by taking a measurement of 1,000 yards on the 2 inches to 1 mile scale. These are called *primary divisions* of the scale. Sub-divide the left division into 5 parts each representing 100 yards. These are called *secondary divisions.* The zero of the scale should be placed as shown in Plate 1, and the primary and secondary divisions be numbered outwards from it.

Primaries should be chosen so as to show miles or kilometres in units, tens or hundreds, or yards, in thousands or five hundreds, according to the unit of measure shown and the size of the scale. Thus a scale of miles or kilometres should show primaries of miles or kilometres; a scale of yards or metres should show primaries of thousands of yards or metres for scales up to $\frac{1}{31680}$, and five hundreds of yards or metres for larger scales. Secondaries should show $\frac{1}{4}$ miles, twentieths of kilometres, or hundreds of yards. Military *sketches* can rarely be of sufficient accuracy to make it necessary to show smaller secondaries, these are however shown on the protractor, which may be used to measure distances on military *maps*.

12. The following example show how a scale may be constructed when no protractor is available :—

Ex. 1.—To construct a scale of 4 inches to 1 mile to show divisions of 100 yards.

Here 4 inches represents 1 mile, or 63,360 inches :—

$$\text{The R.F. is } \frac{4}{63{,}360} = \frac{1}{15{,}840}.$$

The scale is to be between 4 and 6 inches in length ; it will therefore show between 1 and $1\frac{1}{2}$ miles. Take any round number of yards between these limits, say 2,000.

The length of the scale will be $\frac{2{,}000}{15{,}840}$ yards, or $\frac{2{,}000 \times 36}{15{,}840}$ inches

$= 4{\cdot}54$ inches,

or, if it is preferred, the result may be obtained from a proportion sum, thus :—

Yards in a mile.		Yards in the scale.		Inches representing a mile		Length of scale in inches.
1,760	:	2,000	: :	4	:	4·54

In calculating the length of a scale it should be worked out to two places of decimals of an inch.

Draw a line 4·54 inches long, and divide it into 4 equal parts, each representing 500 yards. Subdivide the left division into 5 parts, each representing 100 yards, as shown in Plate 1.

A scale of inches will be found on the service protractor, from which the required lengths can be measured. (*See* Plate 14.) The first place of decimals is given by the subdivisions on the bottom line, the second place by counting upwards the required number along the diagonal line starting from the first place of decimals. Thus, for a line 2·5 inches, put one point of the dividers at *a* the other at *b*. For 2·55 inches, count up 5 divisions from *a* to *c*, and put one point at *c* and the other on the same horizontal line at *d*.

Ex. 2.—To construct a scale of 2 inches to 1 mile to show hundreds of yards.

In this case 5,000 yards, being nearly 3 miles, will clearly be represented by a length of nearly 6 inches.

$$\text{The R.F.} = \frac{2 \text{ inches}}{1 \text{ mile}} = \frac{2 \text{ inches}}{1{,}760 \times 36 \text{ inches}} = \frac{1}{31{,}680}.$$

Then 5,000 yards will be represented by $\frac{5{,}000 \times 36}{31{,}680}$ inches,

or 5·68 inches.

Draw a line 5·68 inches long.

Divide this into five equal parts (each being therefore 1·14 inch long).

Subdivide the left division into 10 equal parts, each 0·11 inch long; each of these will represent one hundred yards. (Plate 1.)

Ex. 3.—To construct a scale of 1 inch to 1 mile to show miles and quarters of a mile.

Here it is clear that all that has to be done is to take a length of say 6 inches representing 6 miles, divide this into inches and the left division into quarters.

Ex. 4.—To construct a scale of $\frac{1}{100000}$ to show miles.

Here 1 mile is represented by $\frac{1}{100000}$ mile.

$$i.e.,\ \text{by}\ \frac{63{,}360}{100{,}000}\ \text{inch} = 0{\cdot}634\ \text{inch}.$$

Hence, if the whole scale represents 10 miles, it will be 6·34 inches long, each mile will be 0·63 inches long, and if the left division is divided into fourths to show quarters of a mile, each of these small divisions will be 0·16 inch long. (Plate 1.)

In military operations distances are occasionally measured by the time required to traverse them, and in this case the linear scale may be usefully supplemented by a scale of hours.

Ex. 5.—To construct a scale of time for a column of troops marching at the rate of 3 miles an hour.

As an example, the scale of the map may be taken as 1 inch to 2 miles, which gives

$$\text{R.F.} = \frac{1}{63{,}360 \times 2} = \frac{1}{126{,}720}$$

If the scale be made 6 inches long, it will represent 12 miles, *i.e.*, the distance marched in 4 hours. Divide this into 4 parts and each will represent an hour's march. By dividing the left division into 12 parts, each will show the distance marched in 5 minutes.

Ex. 6.—**To construct a scale of miles for a foreign map on which no R.F. is given.**

(1) Suppose the map has a scale of versts (1 verst = 42,000 inches) shown. Measure the length in inches of any number of versts, and say that 10 versts are found to measure 1 inch, then the

$$\text{R.F.} = \frac{1}{\text{No. of inches in 10 versts}} = \frac{1}{420{,}000}$$

40 miles will be represented by $\frac{40 \times 1{,}760 \times 36}{420{,}000} = 6{\cdot}03$ inches.

Draw a line 6·03 inches long and divide into 4 parts, each will represent 10 miles, divide the left quarter into 10 to show single miles.

In the heading of the scale, after the R.F., the number of miles to the inch should be stated. In this case 1 inch represents 420,000 inches. Therefore, the number of miles to the inch (*see* para. 8)

$$= \frac{420{,}000}{63{,}360} = 6{\cdot}63$$

(2) If neither the R.F. nor the scale be given, the distance on the ground between any two points shown on the map must be ascertained, either by reference to another map with a scale marked on it, or by actual measurement on the ground.

Suppose in this case that the distance between two villages measures, on the map, 1·5 inch, and the actual distance between them is ascertained to be 3,000 yards,

$$\text{then R.F.} = \frac{1{\cdot}5}{3{,}000 \times 36} = \frac{1}{72{,}000}$$

Since this is a smaller fraction than the R.F. ($\frac{1}{63360}$) of 1 inch to the mile, the scale of the map is rather less than 1 inch to the mile. If, therefore, we take 6 miles, we shall obtain a scale of suitable length.

6 miles will be represented by $\frac{6 \times 1{,}760 \times 36}{72{,}000} = 5{\cdot}28$ inches.

Draw a line 5·28 inches long and divide it into 6 parts, each of which will represent a mile.

The left division may be subdivided to show quarters of a mile.

PLATE 2.
To Face Page 17

CONVENTIONAL SIGNS & LETTERING USED IN FIELD SKETCHING

Note: Words which should appear on the Sketch are shewn in black

Road enclosed by hedge, Fence, ditch, or obstacle of any kind

A 2 Miles — Embankment — Cutting — B 4 Miles — C 6 Miles

Road without Fence etc

P 1 Mile — Metalled — Unmetalled — Q 2 Miles — R 3 Miles

Brown tint denotes metalled road suitable for traffic at all times. Metalled roads likely to be cut up in bad weather dotted brown if brown colour is not available the word "Metalled" or "Unmetalled" should be inserted and any other necessary remarks added.

Footpath

Fields with walls, hedges, Fences, ditches or any obstacle

It is unnecessary to state the nature of the cultivation unless such information is required by the object of the sketch.

Hops 10' high — Wheat 4' high — Heath — Orchard — Rough Pasture

Wood

Nature of wood to be given in writing thus:- "Oak" "Pine" etc. & whether passable or impassable & by what arm also the value of the wood as cover.

or — or — if colour available

Church or Chapel

with Tower — with Spire — without Tower or Spire — Windmill

Railway

Embankment — Cutting — Single or Double — HAWLEY 4 Miles — to EYNSFORD 6 Miles

Bridge — Brick or Stone etc — Tunnel — Sta. Station — Level crossing

When there is not sufficient time to draw the cross-bars, a railway may be shewn by a broad black or red line with the word "Railway" written along it.

Telegraph

Entrenchments

Villages

Scale 4" to 1 Mile — Inn — Forge — HAWLEY

under 4" to 1 Mile — EYNSFORD

Clearance or Demolitions

Lake — Cliffs Quarry or precipitous ground — Sand — Stone — Wood — Bridge with piers — Ford — Iron — Ferry — Bridge — Marsh — State nature of Foreshore & at what state of the tide it is practicable for landing — Lighthouse L.H. — R. AVON — Flying bridge — Width 10 Ft.

Obstacles

BRITISH TROOPS

Mounted Troops (add M.I. if Mounted Infantry): In Line; Column of route; Other formation; Vedette

Artillery: Guns in action; Guns on march

Infantry: In Line; Column of route; Other formations; Sentry

Transport: On march; Parked

Opposing forces coloured blue

15° — Magnetic

ABBREVIATIONS

P. ..... Post Office
T. ..... Telegraph
S.P. ..... Sign Post
oW ..... Well

W. & C. GRAHAM LTD., LITH^RS, LONDON, S.E.

CHAPTER IV.

Conventional Signs and Lettering.

Conventional signs.

13. Conventional signs enable the draughtsman to give an amount of information on a sketch, or map, which could not, conveniently, be otherwise conveyed. They should be simple in character, so that they may be easily understood, and not numerous. It is better to write descriptions on the face of a sketch, or in the margin with a line and arrow head showing the point referred to, in language which cannot be mistaken, than to crowd it with symbols of which the meaning is liable to be misunderstood.

Plate 2 shows the conventional signs approved for field sketches. These signs should be studied, and used in making a field sketch. In cases of great haste, however, it is sometimes more convenient to describe the object than to draw its symbol.

The conventional signs used on Ordnance Survey maps differ slightly from those used in field sketching, the latter being modified in some cases so that they may be simpler to draw. The conventional signs used on the 2 miles = 1 inch Ordnance Survey are shown on Plate 3.

A **Road** is drawn with continuous lines when it is enclosed by a fence, ditch, or obstacle of any kind, and with dotted lines when unenclosed.

It should be noted whether a road is metalled or unmetalled, and occasionally it is desirable to give its width. Thus 14′ m. would mean a road the metalled portion of which is 14 feet wide. 14 feet of metalling will allow of two lines of traffic in opposite directions; less than 14 feet will not. Metalled roads suitable for traffic at all times should be coloured brown; those likely to

be cut up in bad weather dotted brown. If no colour is available the word "metalled," or "unmetalled," and any additional information required should be inserted.

A **Railway** is shown by a continuous, thick, black line with cross-bars; the word "single," or "double," should be written along it as the case may be.

Opposite the point where a main road or railway is stopped by the margin the name of the nearest important town or village should be written and also its distance from that point in miles, *Thus—Canterbury* $3\frac{1}{2}$ *miles.*

Form Lines and **Heights** are drawn in brown or red. Form lines should be shown by almost continuous lines, broken occasionally by very short spaces and dots where the hand requires a rest.

Cultivation is denoted by inserting in writing the nature of the crops. If they present any obstacle to the advance of troops, or afford cover, a note to that effect should be added; but such information should only be given if required by the object of the sketch.

A **River** is drawn in blue, with its name written along its course, and the direction of its current indicated by an arrow. The width of the river, and any further information as to the bottom and banks required to show its nature as an obstacle should be noted on the sketch. The bed of a river or stream which is dry at the time of sketching should be shown in black, a note as to its liability to flood being made on the sketch.

The nature of a **Bridge** is indicated by the word *iron, stone, wood, suspension, &c.* The principal dimensions of important bridges and their suitability for heavy traffic should be stated.

Heath, Heather, or **Marsh** is shown by writing the word, *heath, heather*, or *marsh* in black. When finishing up the sketch the conventional sign shown on the plate may be added if time permits.

In the case of **Woods** it should be noted in writing whether they are passable for troops of all arms or not; their nature, whether of fir, oak, &c.; and the degree of cover which they afford should be stated.

CONVENTIONAL SIGNS FOR THE HALF-INCH TO ONE MILE MAP OF GREAT BRITAIN.

1st. Class Roads ....
2nd. ....
3rd. ....

Fenced / Unfenced

Passenger lines .. .. L. & N.W.R. / CHESTER & CREWE

Mineral lines & Tramways . N. E. R. / Pontop & South Shields

Canals . . . .

Rivers .. . . .

Streams . . . .

Parks . . . . .

Woods . . . . .

Marsh . . . . .

Co. Boundary . . . . .

Windmill 8

Windpump 1

Post Office . . . . P *Post & Tel. Office* . . . . T

Trig. Sta. & Alt. 895 △ *Level Dot* 107

Churches . . . . + *Site of Battle* 1761

Lt Ho. & Lightship . . *Single Trees* . . . .

Railway Sta.
Road over Railway
Railway over Road
Railway over Railway
Level Crossing
Railway over Stream
Railway over River
Isolated Br.
Tunnel
Viaduct

Ferry
Ford
Road over River
Isolated Br.
Aqueduct

300 / 200 / 100 *Contours*

Rifle Range

On the older editions the Woods are shown in Green.

The letters P and T indicating Post and Telegraph Offices are not written to those towns which would obviously have a Post or Telegraph Office.

The conventional *colours* are shown on Plate 2. For rough sketches, coloured chalk pencils may be used.

Troops.—It may be necessary to show the disposition of troops on a sketch, as, for instance, when making proposals for the distribution and action of a given force. It is not desirable to spend time in drawing troops in any form to scale. It is sufficient to draw a symbol which will attract the attention, writing the necessary information as regards strength and unit alongside or in the margin.

In outpost sketches, the letters P, S, R, may be written instead of piquet, support, and reserve.

The direction of a *patrol* is shown by an arrow.

Lettering.

14. Whatever lettering appears on a sketch must be easily legible, should not interfere with the detail, and should show clearly to what it refers. These are the only essential conditions.

It is within the power of all officers to adopt and use some simple style of lettering which shall be clear, and quickly written. Each letter should be separate.

The principal words, *i.e.*, names of towns, villages, and rivers should be in simple block letters. (*See* Plate 2.)

All lettering should be horizontal, excepting the names and directions of rivers, railways, roads, and canals, which should be written along them; words descriptive of the nature and condition of a tract of country should be written so as to, as far as possible, extend over the portion of ground described.

CHAPTER V

British and Foreign Maps, and Methods of Representing Hill Features.

15. The chief difficulty felt by most students in reading maps is in understanding the methods used to represent hill features. These consist of various artifices by means of which the inequalities of the ground are shown.

The following systems are employed for showing hill features on maps:—

1. Contours, or approximate contours, *i.e.*, form lines.
2. Contours and hachuring, *i.e.*, shading.
3. Hachuring alone.
4. Layer system (altitude tints).

Plates 7, 8 and 9, show maps in which hill features are represented by contours.

Plate 5 shows maps representing hill features by contours and hachuring combined.

Plates 10 and 11 show hachuring alone.

Plates 6 and 12 show maps in which the hill features are represented by the layer system.

16. Contours.—These are best explained by the following simple practical illustrations:—

All students will be familiar with the ordinary wooden or plaster models sometimes used to represent in relief hills and other geographical features.

Say we have such a model, the scale of which we know to be $\frac{1}{1\frac{1}{2}}$, *i.e.*, one inch on the model represents one foot on the ground.

We place the model in an empty tank or bath, and pour in water until there is one inch of water in the bath.

The watermark will cut the model one inch vertically above its base, all round. We draw in this watermark with an indelible pencil.

We now add water until there are two inches in the bath, and the new watermark is drawn in.

We continue to add water by inches in this way, and to draw in the successive watermarks, until the model is completely covered with water.

FIG. 2.

View of a hill with contours supposed to be visibly marked.



Plan of the same hill.

On removing the model we find it marked with a succession of lines, which we know are vertically one inch above the other. These lines are "Contours."

Now if we make a drawing of the model as seen from above, *i.e.*, a "plan" of the model to the actual scale, we shall have marked on it "Contours" at one inch vertical interval—or in other words, we have a map of the actual ground, on the scale of $\frac{1}{12}$, with "Contours" at *one foot* vertical interval.

In practice, for ordinary scales, "Contours" at so close an interval as one foot would be too numerous. The interval between the "Contours" depends generally on the scale. Fig. 2 gives the views of a hill with "Contours" 100′ apart.

17. Contours have certain advantages for the map reader over other artifices, viz. :—

i. They show the hill forms with exactness, and not vaguely, as is the case with shading.
ii. They require little artistic talent to draw.
iii. They obscure the detail less.
iv. They can be reproduced by lithography in the field.

They present, however, a disadvantage to the map maker, in that the methods required to produce them involve great labour and consequently expense. This explains why only the best maps are contoured, and then only at considerable interval of height. In view of these advantages and disadvantages as regards contours, a kind of compromise is adopted for Field Sketching, and the method of showing hill features to be used is that of **form-lines** which are approximate to contours sketched in by eye.

18. Certain points should be noticed by the student as regards the information conveyed by contours or form-lines. Thus :—

i. If a map shows contours close together, the slope there will be steeper than in places where the contours appear further apart. In Fig. 3, plan, the ground is steeper at A B than at C D. This is at once apparent if sections be drawn as follows :—

Draw equidistant and parallel dotted lines equal in number to the number of contours which it is desired to show in section, in this case three. Number the bottom dotted line to correspond to the lowest contour, in this case 100, the remaining lines are numbered 200 and

300 to correspond to the remaining contours. Mark a dot *b* on the lowest dotted line to represent the point where the section line A B cuts the 100 contour in plan. From *b*, measure off *b c*, = *b c* in the plan. At *c*, draw *c*,*c* perpendicular to the 100 dotted line, so as to cut the 200 dotted line at *c*. Then measure *b a*, = *b a* in the plan, and draw *a*, *a* similarly to cut the 300 dotted line at *a*. Draw the line A *a c b* B in the section. The line C D is similarly drawn, and the slopes A B and C D can be compared.

Section drawing of this nature is purely for instructional purposes and has no practical value.

FIG. 3.



ii. When contours bend they portray a spur or projection; or they portray a valley or re-entrant. To ascertain

which, the numbering of successive contours must be examined if there is no distinctive shading in addition to contours.

In Fig. 4, reading the contours down from 300 feet to 100 feet, and imagining them raised on uprights to scale corresponding to these heights, the bend A B is seen at once to be a spur; the bend C D a valley.

iii. Referring to Plate 4, slopes may be **uniform,** like A B, **convex,** like C D, or **concave,** like E F.

Now, if contours be drawn in plan to represent a short distance of these slopes, it will be apparent that their spacing in each case is distinctive of the particular kind of slope represented, as follows:—

i. When the contours are evenly spaced as in plan (1) the slope represented is uniform.

ii. When the spacing, reading from high to low, decreases, as in plan (2), the slope is convex.

iii. When the spacing, reading from high to low, increases, as in plan (3), the slope is concave.

It may be noticed that uniform and concave slopes, (1) and (3),

FIG. 4.



afford no dead ground. Convex slopes (2), on the other hand, do afford dead ground.

19. Slopes may be expressed either in degrees or as a gradient.

Slopes are usually expressed in military terms as a gradient, *i.e.*, by a fraction—Thus $\frac{1}{30}$ represents a rise or fall of 1 foot in 30 feet.

SE

(1.) *Uniform* (2.)



(1.) *Uniform.* (2.)



24475.

PLATE 4.

To face page 24.

NS.

K.

(3.) *Concave.*



ANS.

EX.

(3.) *Concave.*



An approximate rule for expressing as a gradient a slope given in degrees is to divide the number of degrees by 60. Thus a slope of 3° is equivalent to $\frac{1}{20}$, a slope of 10° is equivalent to $\frac{1}{6}$. This rule does not hold for steep slopes.

20. The following slopes are generally practicable for wheeled vehicles, but much depends upon the surface of the ground.

For short distances the slope may be $\frac{1}{7}$ for artillery.

" " " " " " " $\frac{1}{10}$ for transport animals.

Steeper than $\frac{1}{10}$ is inconvenient for animals or wheeled traffic.

Traction engines can draw their own weight up $\frac{1}{10}$, twice their weight up $\frac{1}{20}$, three times their weight on the level or up slopes not exceeding $\frac{1}{33}$. (For the method of measuring slopes, *see* para. **54.**)

21. The student should exercise himself in studying the system of contours as a means of depicting hill features. He should imagine some type of ground with various combinations of spur, valley, and slope, and then endeavour to portray these by contours. Conversely, he should draw contours with various curves and spacing, number these successively, and work out the ground they represent. Such preliminary exercises will greatly assist him to read hill features on contoured maps fully, rapidly, and with accuracy.

CHAPTER VI.

Copying and Enlarging Maps.

22. Copying.—Maps which are to be simply copied without reduction or enlargement, may be first traced on tracing paper, and then, a piece of carbon paper being placed between the tracing and a clean sheet of paper and both very firmly fastened down by drawing pins, the tracing may be transferred by following the lines with a pointed instrument.

In the field, an excellent substitute for carbon paper can be made by rubbing lead pencil dust on a piece of tracing paper; in fact, this is to be preferred to carbon paper. Any sharp piece of wood will do for the tracing instrument.

A map may also be transferred direct without a tracing; but there is some danger of damaging the original with the point.

Tracing cloth is useful for copying: it is tough and will bear much handling. Draw on the glazed side, and put washes of water colour, if required, on the back, darker than they are intended to appear on the front.

23. Enlarging.—When it is required to enlarge a map, squares of any convenient size may be drawn on the original, and the paper on which the new map is to be made ruled with squares whose sides bear the required ratio to the sides of the squares on the original. The original is then copied by eye, so that objects occupy the same positions relatively to the squares as they did in the original. (*See* Fig. 5.)

Ex. 1.—It is required to enlarge to 4 inches to 1 mile a map of which the scale is $\frac{1}{2}$ inch to 1 mile. Squares, $\frac{1}{4}$ inch sides, are drawn on the map. Then to find the length of sides of squares on the enlargement, we have :—

$$\tfrac{1}{2} : 4 :: \tfrac{1}{4} : \text{Length required.}$$

Whence sides of squares required = 2 inches.

Ex. 2.—A plan with R.F. $\frac{1}{100000}$ is to be copied at 4 inches to a mile. Squares, $\frac{1}{4}$ inch sides, are drawn on the plan. The R.F. of 4 inches to 1 mile being $\frac{1}{15840}$, the length of sides of squares on the copy is obtained by proportion, thus :—

$$\tfrac{1}{100000} : \tfrac{1}{15840} :: \tfrac{1}{4} : \text{Length required.}$$

Whence required side of square = 1·58 inches.

Army Book 153 and most service pocket books contain paper ruled in quarter-inch squares. When such paper is available, it is usually only necessary to rule squares on the map which is to be enlarged.

FIG. 5 (i).

Portion of 1/2" Map of England

FIG. 5 (ii).



Enlargement 4 inches to 1 mile.

When no squared paper is at hand the following is a rapid and simple method :—

FIG. 6.



Draw a circle of any convenient size in the centre of the portion to be enlarged. From its centre O draw rays to mark the direction of the North point and to prominent points on the map A, B, C, D. Produce these rays, if necessary, to cut the circle at n, a, b, c, d.

Now draw a similar circle on the paper and draw the North point as before, cutting the circle at n'. Measure na, nc, nd, and nb, and lay off $n'a'$, $n'c'$, $n'd'$, $n'b'$ equal to them respectively. Then from the centre draw rays to a', b', c', d', and set off O'A' as many times larger than OA as the copy is to be larger than the map. This fixes A'. B', C', and D' are similarly fixed, and the intervening detail is drawn in by eye.

In Fig. 6 the enlargement is twice the scale of the map.

24. Combined Sketches.—Where several sketches are to be employed to produce a combination sketch with rapidity, each should not make his enlargement independently. One sketcher should make an enlargement for the whole area. Lines should then be drawn dividing up the whole into sheets; one sheet for each sketcher. A tracing should be made of each man's portion so that when he fills it in, his work will be based on a skeleton which exactly fits at the edges with those of the neighbouring sketches.

25. A unit exists in War Establishments called the Printing Company R.E. This unit can enlarge a $\frac{1}{2}''$ sketch or map up to 4" to 1 mile by photographic methods; or any sketch on any scale up to 8 times the original scale.

The enlargement is traced, and the tracing is divided up and handed to various sketchers to fill in, as explained in Chapter XII.

The completed tracings are then returned to the Printing Company which will reproduce any number of copies of the completed sketch.

CHAPTER VII.

The Service (Prismatic) Compass and Protractor. Their use in Map Reading and Marching.

26. The service compass consists of a magnetic needle balanced on a pivot, and carrying a dial divided into degrees, contained in a metal box, round which is a brass ring graduated to show every

fifth degree and the points of the compass (*see* Plate 13). The metal cover, C, opens on a hinge, and is fitted with a glazed window, W, on which is traced a fine black hair line, V, for use as a sighting-vane. Opposite the hinge of the cover is fitted a prism, R, through which can be read the graduated edge of the dial, while at the same time an alignment of the object and of the sight-vane on the cover is observed through the slit above it. The prism should be moved up or down in its slot till the figures on the dial are properly focussed. A clamping-screw, S, is provided for clamping the needle when not in use, and a "check-spring," A, for checking its oscillations when observing. A brass ring, B, is attached for convenience in holding it.

The dial is "luminous" for night work, the north point is marked with a large diamond-shaped figure. A revolving glass is fitted over the compass dial, and on the glass is a black direction mark, radiating from the centre, at the end of which is a small brass "setting vane," the latter working over an external arc graduated to 360°. A brass screw, J, is used to clamp the glass. On the inside of the cover are two luminous patches, PP, which give a good alignment of the instrument at night when it is held in the hand with the cover wide open. There are two small holes, HH, in the brass window-edge of the cover, so that, if the glass breaks, a horse-hair can be run between them, and an extemporized sight-vane be utilized.

The compass dial is graduated with two sets of figures which read eastward of the meridian (*see* definition, Chapter II), or from left to right, like the hands of a watch. The outer set is for use with the prism, and commences at south in order that the bearing of the object may appear under the eye. Thus the vane being directed on an object which is 50° from north, it is that number measured from south which appears under the prism; or, in other words, 180° is over the north end and 360° over the south end of the needle. The inner set of figures is of use for direct readings (*i.e.*, without the prism) as for compass marching, or when the instrument is used with the plane-table.

The prismatic compass gives "bearings" and not "angles" (*see* definitions, Chapter II). The horizontal angles between any distant objects are obtained by taking the difference of their observed bearings.

Example.—The angle between two points, A and B, is required. Their bearings are observed to be respectively 50° and 110°. The angle required = 110° − 50° = 60°.



PRISMATIC COMPASS

PLATE 13.

To face page 30.

27. *(a). To use the compass as a hand compass.*

Hold the compass level in the hand, or place it on a level surface; when the card comes to rest.

The check spring can be used to steady the swing of the card so that it may more rapidly come to rest.

The graduation of the *inner* ring of figures, immediately under the index line, gives the magnetic bearing.

(b). As a prismatic compass.

In order to obtain the bearing of a distant point, the observer directs the sighting vane of the compass on the object and reads its magnetic bearing in the prism.

(c). As a night marching compass.

28. Marching on a Compass Bearing.—To use a compass with advantage on a dark night, it is essential that it should be prepared with "luminous paint." This substance must be kept exposed to the light before using it, or it will be found to be non-luminous when required. As a general rule, a compass exposed for half an hour before sunset will be sufficiently luminous to work by for some 6 to 9 hours afterwards.

In the *Service prismatic compass* the magnetic north is marked by a broad black arrow-head. The compass is so constructed that upon the black direction mark being turned to point to the required "bearing," as shown on the external ring, and the arrow-head being made to correspond with the black direction mark, the *line between the luminous patches in the lid indicates the line of advance.*

It will thus be seen that in the service compass no attempt is made to read degrees or points by means of luminous paint: such a proceeding is impracticable, and if depended upon would only lead to disappointment and failure. The utmost that can be expected from luminous paint is for a compass prepared with it to show a faint luminosity of the dial, just sufficient to throw up in relief the black direction mark and arrow-head.

As a rule, the darker the night the greater the assistance afforded by the luminous paint. During a moonlight night a luminous compass is of no greater value than an ordinary compass with a clearly marked north point.

29. In using a compass during a night march, some means should be adopted to prolong the line of advance as shown by the compass, and thus clearly indicate the route to be followed. A stick painted white or with white paper pasted on it, or, best of all, one prepared with luminous paint is most useful. The operator, standing perfectly steady, should wait until his compass has come to rest, and then hold the stick, at an angle of 45° to 60° with the horizontal plane, in the direction indicated by the line between the luminous patches in the compass-lid.

With the stick thus held it is easy to pick up some object to march on, and the advance is then resumed until it is considered desirable to halt, allow the compass to settle, and observe the direction of advance afresh.

30. But it may happen that, owing to clouds or fog, no terrestial objects to march on between the halts are visible, then the only safe way is for an assistant to stand behind the observer and work as follows :—The guide with the compass and luminous stick, as soon as the compass becomes steady, gives the word "steady." The assistant, carefully noting the alignment of the luminous stick, then advances in what he judges to be the right direction, until the guide halts him, before he is lost to sight, by giving a low whistle.

The guide, having thus halted his assistant, notes by means of the compass whether the latter is standing on the true line of advance or to the right or left of it. He then moves up, and placing himself on what he judges to be the correct alignment, sends forward his assistant again.

The rate of advance obviously depends on the distances covered between halts; after the first few advances the assistant will have ascertained the number of yards he can safely proceed without being lost to sight, and on reaching that distance he will halt without waiting for the whistle. This is important, since the whistling might give notice to the enemy as the force approaches the objective.

Slabs of cardboard or wood, prepared with luminous paint, are of great assistance in this tedious process of sending on an assistant; a slab, 12 inches square, can be seen at from 70 to 150 yards distance, according to the condition it is in, and by this means the rate of advance can be greatly accelerated.

Besides the guide and his assistant, a third person should be employed to keep a careful record of the distances traversed.

PROTRACTOR RECTANGULAR.

6" Wood "A" Mark II.

To face page 33.

21175.


BEVELLED SIDE
SCALE OF MILES 1/80.000 (1 INCH=1·26 MILES)
MILES
YARDS
SCALE OF MILES 1/100.000 (1 INCH=1·58 MILES)
SCALE OF MILES 1/250.000 (1 INCH=3·94 MILES)
YARDS 2 INCHES 1 MILE
Hole 3/16 dia.
Hole 3/16" dia.
JONES & Co 1910.
A II 37
FLAT SIDE
YARDS ½ INCH=1 MILE
YARDS 1 INCH=1 MILE
SCALE OF INCHES.
PROTRACTOR 6"x 2" EXACTLY
KILOMETRE = 1000 METRES = 1094 YARDS = 0·62 MILE (= 5/8 MILE NEARLY)
SCALE OF KILOMETRES 1/100000 (1 C/M = 1 KILOMETRE.)
YARDS 2½ INCHES = 1 MILE

31. *The Service Protractor* (Plate 14).

The service protractor for sketching is made of boxwood exactly 6 inches in length and 2 inches in breadth, it is divided on both sides as shown on Plate 14.

On it four scales of yards are shown :—

$2\frac{1}{2}$ inches to one mile.
2 " " " "
1 " " " "
$\frac{1}{2}$ " " " "

on these scales the primary divisions show hundreds of yards.

Three scales of miles are shown :—

$\frac{1}{80,000}$ or 1 inch to 1·26 miles.
$\frac{1}{100,000}$ " " " " 1·58 "
$\frac{1}{250,000}$ " " " " 3·94 "

One scale of kilometres $\frac{1}{100,000}$ is also shown.

The edge graduated in degrees is for reading and plotting angles, the arrow point showing the centre from which the angles are drawn.

32. *Plotting and reading angles.*

The direction of an object observed with the compass, expressed in degrees from the magnetic north measured round up to 360° with the hands of a watch, is the bearing of the object, and can be laid down or p'otted on a map or sketch with a protractor from the point of observation.

In *plotting angles*, if these angles are magnetic bearings, and if it is required to plot any bearing from a point A (Fig. 7), then a line must be drawn through A, showing the magnetic meridian. In practice it is not necessary to go to the trouble of drawing this meridian through every point from which a compass reading is taken. Starting from some selected point, a magnetic meridian is first drawn, and then a number of lines parallel to it. These

latter serve as a general guide for placing his protractor on any point afterwards in the correct position. One of them will be near enough to the point to guide the eye.

FIG. 7.



NOTE.—In above figure the protractor is unshaded when in position for plotting bearings between 180° and 360°.

It is usual to draw these parallel lines representing magnetic meridians about the width of the protractor apart. The protractor

can always be set with its long edge parallel to these lines, by making one of the lines cut each of the shorter edges at opposite and similar divisions, or by eye.

One end of these meridians should be marked with an arrow-head to avoid the possibility of protracting the bearings in the reverse direction.

The protractor is laid on the map or sketch with the arrow at the point whence the bearing is to be drawn, and with its long edges set north and south, *i.e.*, parallel to the lines.

If the bearing is under 180°, the graduated edge of the protractor is laid to the right or east; if over 180°, to the left or west, the north margin of the sketch being uppermost.

The bearings of the various points in Fig. 7 are read thus :—

At A	C, 3°	At B	F, 181°	At G	K, 309°
	D, 40° 15′		G, 220° 15′		L, 66° 15′
	E, 60°		H, 232°		
	B, 85° 45′		A, 254° 45′	At D	L, 120°
	F, 110°		C, 309°		K, 242°
	G, 139°		D, 315°		
	H, 171° 30′		E, 347°	At F—C, 322° 45′	

To plot the bearings taken from A the protractor is adjusted with its centre at this point and its graduated edge to the east. The positions of all the bearings under 180° are marked off, and fine lines of indefinite length drawn through them from A, as shown; those over 180°, if any, would next be protracted.

The point at which the bearing is to be laid down may be so near the edge of the paper that the graduated edge is off it. In this case lay the protractor with the graduated edge inwards, and produce the required bearing outwards *through* the centre.

33. The bearing from one point to another on a map or sketch may be read by means of the protractor as follows :—If the true bearing is required, a meridian, or line parallel to the true north and south line, must be drawn through the initial point; if the magnetic bearing is required, a magnetic meridian must be so drawn. A line is then drawn joining the two points, produced if necessary so as to be longer than the width of the protractor. The protractor is laid on the map with its centre at the initial point as described in para. **32.** The point where the line joining the two points on the

map cuts the graduated edge of the protractor gives the reading in degrees. If it is necessary to lay the graduated edge to the right or east, in order that the line between the two points may cut it, then the bearing must be read off the outer row of figures (*i.e.*, the bearing is between 0 and 180°). If the edge of the protractor has to be laid to the left or west, then the inner lines of figures must be used (*i.e.*, the bearing is between 180° and 360°).

34. *True and magnetic bearings.*

(*See* definitions, Chapter II.)

Sometimes one of these is given and it is required to convert it to the other by adding or subtracting the variation as the case may be. For example in all operation orders true bearings are given (*see* F.S. Regs., Part I, Sec. 9, vii). The reason for this is that most compasses have variations of their own, due to imperfections of manufacture, independent of the magnetic variation. It is, therefore, necessary to ascertain the exact variation of a compass when it is first obtained and to check the variation periodically.

In all countries which have been surveyed and of which accurate maps are published, such as the United Kingdom, the simplest method of finding the variation of the compass is the following:— Obtain a sheet of the survey showing the county in your neighbourhood, if possible on a scale larger than 2 miles = 1 inch.

Select on the map a well-marked and accessible point, go there with the compass and look out for some landmark, at a good distance, which is shown on the map. Take the bearing of this landmark with your compass. Then find the true bearing with the protractor as described in para. **33.** The difference between the true and the magnetic bearings gives the variation of the compass.

35. The beginner may be puzzled in converting true into magnetic bearings or in finding the variation of the compass unless he draws a figure.

Examples.

(1) The variation of the compass is 13° West. The magnetic bearing of a point P is 29°. What is the true bearing? First draw

a circle and mark on it the known facts, *i.e.*, the position of the true and magnetic N. Points, thus :—

FIG. 8.



As the bearing given of the point P is a magnetic bearing, lay the protractor with the arrow-head at the centre of the circle and its edge along the magnetic N. line. Then measure off 29° to the east and mark in the point P.

FIG. 9.



The position of P with relation to the true N. can then be read off viz. : 29°−13°=16°.

(2) True bearing A to B is 227°. Variation of compass is 10° E. What is the magnetic bearing of B from A? Proceed as in Example (1).

First draw the circle, put in the true and magnetic north. Then measure off 227° from the true north line, this gives the position

FIG. 10.



of B. The magnetic bearing of B from A can then be seen to be $227° - 10° = 217°$.

(3) The true bearing of a point P is 250°, the magnetic bearing of the same point is 265°. What is the variation of the compass?

FIG. 11.



Draw the circle and the true north line. Then measure off from the true north line the true bearing of P, *i.e.*, 250°. Mark in P. Now start from P and measure off 265° from west to east, *i.e.*, lay the

protractor along the line from the centre of the circle to P, with the arrow head at the centre of the circle and the graduated edge of the protractor to the left or west. Mark off the magnetic north line. Then the variation is 265° – 250′, and as the magnetic N. is to the left or west of the true north, the variation is 15 W.

(4) You wish to find from an Ordnance map the magnetic bearing of a point B from a point A. Variation of compass is $16\frac{1}{2}$ W.

FIG. 12.



Join the two points by a pencil line. Through A draw in pencil true and magnetic N. Points. Measure with the protractor the angle (by E and S) between the magnetic N. and B.

FIG. 13.



CHAPTER VIII.

Approximate Methods of Finding the True North.

36. i. With a compass, if the magnetic variation, which can be obtained approximately from Plate 15, is known.

ii. In the northern hemisphere, in ordinary latitudes, the true bearing of the Pole Star is always within 2° of north.

iii. In the southern hemisphere the Southern Cross may be used as follows:—Consider the Southern Cross as a kite; prolong the greater axis 4½ times in the direction of the tail, and the point reached will be approximately the South Pole of the heavens. If a piece of paper be marked off along its edge by twelve dividing lines giving eleven equal divisions and be held so that the first and third divisions coincide with the head and tail stars respectively, the intersection of the twelfth line and the edge of the paper will give the approximate south point.

iv. At the equinoxes (end of March and end of September) the sun rises due east and sets due west.

v. At apparent noon the sun is on the meridian. Apparent noon may, however, differ from mean local noon (12 o'clock by a watch) by as much as 16 minutes. Moreover most countries now keep standard time of some particular meridian for use in railways and telegraphs throughout the country so that the time in actual use may differ considerably from the mean local time. At noon by the watch the sun may be a considerable amount off the meridian.

vi. *In the Northern Hemisphere.*—Hold the watch horizontally with the face upward. Point the hour hand at the sun. Then a line from the centre of the dial to a point halfway between the figure XII and the pointer of the hour hand is approximately a south line.

In the Southern Hemisphere.—Hold the watch as before, but in this case point the line from the centre of the dial to figure XII at the sun. then the line found as above is in this case approximately a north line.

CURVES OF EQUAL MA

Shewi

APPROXIMATE ANNUAL



_____ *Lines of West Variation*

- - - - - - - - " *East* "

TIC VARIATION, 1912.

o the

GE IN MINUTES OF ARC.

Plate 15.

To face page 40.



\+ *indicates an annual increase*

\- " " *decrease*

War Office, June 1912.

This method is a very rough one. It should never be used in the tropics, and the higher the altitude, *i.e.*, the further from the equator, the more reliable it is.

NOTE.—None of the methods given in para. **36** is to be used for determining the magnetic variation (*see* para. **34**).

CHAPTER IX.

MAP READING.

37. Proficiency in map reading is attained when the study of a good map enables the student to visualize in imagination the country portrayed. Maps vary greatly in style of reproduction, and in the amount of information they convey. Notwithstanding their great military uses, they have their limitations, and should never be considered a complete substitute for the examination of the country itself. As already explained, dependence on active service will have to be placed on maps of small scale. The smaller the scale the less completely can a country be portrayed in detail. Even with the best large scale maps, valuable military information as to the form of the ground, more particularly as regards underfeatures, may often not appear. Generally speaking, maps are more lacking in complete information as regards form than as to detail. The expense of close contouring being prohibitive, it would be exceptional to get a 6-inch map contoured at 20 feet vertical intervals. Even were it so contoured, such a map could not be used in substitution for a visit to the ground to determine exactly where a firing line could best be placed, or precisely what concealment the ground in front could afford an enemy. Since the vertical intervals would be 20 feet, underfeatures less than 20 feet in height would not appear on the map. Thus, undulations of ground might exist which would give cover to a man, but would not be shown on the map. Such is particularly the case with gently undulating country, and sunk roads. It will, therefore, be seen that maps are an aid to, not a substitute for, the study of the country itself.

38. On taking up a map, look at once for the scale: this is the key to distances. Then carefully examine the heights and the

method of showing the form of the ground. With contoured maps (the most useful) the vertical intervals used should be noted, as well as spot levels that may indicate under-features. Some maps show only spot levels. These will be found generally on the heights, along main roads, along railways, at villages and sometimes in valleys and other situations. This method of scattered levels is generally combined with a pictorial method of shading.

Plate 5 shows contours, vertical hachuring, and spot levels.

Plates 6 and 12 show maps on the layer system.

Plate 10 shows a German map. Plate 11 a French map, with spot levels and vertical hachures. The heights in both cases are shown in metres. (Scales of kilometres altered to show miles.)

39. A failing in many uncontoured maps is the sparse number of levels given in valleys, or at the foot of hills; the tops of hills are often liberally supplied. In such cases, much assistance to the map reader is afforded when prominence is given to streams by colouring them blue, thus showing up the valleys in which they run. If this is not done, run a blue pencil over the stream.

40. An important item to look for on a map is the direction of true or of magnetic north. In all descriptions made with reference to a map, the points or degrees of the compass are used to express the direction of one object from another. In the small scale maps of the Ordnance Survey the sheet-line margins are rectangular and are drawn parallel to a central meridian. For sheets through which this meridian passes the marginal lines are nearly true north and south, with the north towards the top of the sheet; but for sheets to the east and west the margins deviate from the true north, the maximum deviation, however, in the extreme east and west counties is not more than 4° east or west respectively. Where a magnetic, or a true north point is shown, it may save errors to draw on the face of the map a few lines parallel with it to remind the reader of its direction. In quoting a bearing, the true bearing only should be given and this should be stated. (*See* F.S. Regs., Part I, Sec. 9, vii.).

41. A map is said to be "**set**" when it is laid out to correspond with the ground, so that the true north on the map points to the North Pole. If the directions between features on the ground be now compared with these directions as shown on the map they will be seen to be parallel.

A map may, therefore, be set as follows:—

i. **With Compass.**—If the magnetic north line is shown on the map, lay the compass over it (produced if necessary) and, without disturbing the compass, turn the map slowly round until the north end of the magnetic north point on the map is exactly under the north end of the needle. In doing this it may be necessary to make an allowance for any special variation of the compass (*see* para. 34). If the true north line is shown on the map place the compass with its centre on a true meridian, and turn the map until this line makes with the needle an angle equal to the variation, and on the correct side of it. If the true north line is not shown, use the side of the map as described in para. 40. Thus, with a variation 17° W, the side sheet line of an Ordnance Survey 1-inch map, would have to be turned till 17° to the right (or east) of the needle of the compass.

ii. **By Objects.**—A map can be set by objects on the ground without using the north point or compass as follows:—

(*a*) *When you can identify your position on the map.*

Identify your position on the ground where you stand as some point marked on the map. Also identify on the map some distant object you can see. Join these two on the map by a straight line. Then turn the map about the point, marking your position till this line points to the distant object.

(*b*) *When you do not know your exact position.*

Place yourself between or in prolongation of a line joining any two points which can be identified. Revolve the map until the line joining the two points on the map points towards the two positions in the country. The map is then set.

A map may be set approximately for reading by identifying on the map several prominent objects that can be seen, or by standing on or near some straight feature marked on the map, such as a straight road, railway, river, canal, &c. The map is then held so that the directions between these objects as they appear on the ground and on the map are parallel to one another.

42. *To find your position on a map.*

i. When two points marked on the map can be identified in the country and the map can be set.

First set the map by one of the methods described in para. **41.** Then if A and B (Fig. 14) be two convenient points in the country, which can be identified as *a*, *b* on the map, align a ruler through

a on A and draw a line towards yourself, then align the ruler through *b* on B and draw a line towards yourself. The intersection of these lines *x* is your position.

This process is called *resection* (*see* definition, Chapter II), and is of the greatest use both in map reading and in sketching, for by means of it an observer can find his position from two known points.

The service prismatic compass can be used for resection as follows (*see* Fig. 14):—

FIG. 14.



An observer standing at *x* identifies two points *a* and *b*, which are marked on his map or sketch as A and B in the country. He wishes to fix his exact position. He takes the bearing of A from his position, and finds it to be say 30°. Then the observer's position *x* on the map is such that if the bearing 30° is plotted from it the line would pass through *a* on the map—in other words, the bearing of *x* from *a* is 180° + 30°, or 210°. Plot this bearing at *a*. The bearing of B is taken in a similar manner and plotted at *b*. The intersection of the two bearings gives the observer's position *x*.

The simplest method in plotting resections is to plot the bearings taken from the observer's position at the stations identified on the map or sketch with the protractor reversed, *i.e.*, turned to left or west for bearings under 180°, and to the right or east for bearings over 180°.

In fixing a position by resection, the angle made by the intersection ($a\ x\ b$, Fig. 14) should not be too obtuse or too acute, *i.e.*, the angle should not be greater than 130° or less than 50° if the resection is to be accurate.

ii. When your position can be identified as in line with two known points or on a given straight line, such as a road, railway, canal, &c., and one point can be identified in the country to one side of the given line, set the map.

FIG. 15.



Then if A and B be two points on the ground in line with the observer's position, identified as a and b on the map, and C be a point on the ground on one side of A, B, identified as c on the map, align the ruler through c on C and draw a line towards yourself, the intersection of this line with $a\ b$ at x gives your position.

43. Map Reading on the Ground. — Having mastered the various methods and artifices used in making maps, the student should then go out, and *from* some high post of observation compare large and small scale maps with the ground. Two methods of study should be alternated:

i. Examine the map carefully in detail for some time, say, 10 minutes, and visualize what it conveys. Then look at the country and compare it bit by bit. In the study of the map, use a scale, measuring the distances between objects; and from your position note the general form of the ground as portrayed on the map, the directions of valleys and spurs, relative heights, steep slopes, flats, probable dead ground, woods, &c.

ii. Have a good look at the country first. Estimate distances and heights. In your mind convert distance into inches according to the map scale, thus summing up in your mind what you expect to see on the map. When you have some definite idea of what the map should look like, turn to it and compare notes.

44. In the above exercises, all errors made should be carefully thought out. More will be learnt by systematically working the mind and imagination than by immediately looking from the ground to the map, or vice versâ. Moreover, the second exercise of visualizing the map from the ground is excellent training for sketching.

The above exercises should be carried out with both large and small scale maps for the same country. It is instructive, for instance, to compare on the ground a 1-inch map with a $\frac{1}{2}$-inch map.

45. Small scale maps, *e.g.*, $\frac{1}{2}$-inch, are apt to puzzle the beginner in a country so full of detail as England. Much detail is necessarily omitted on such a map. Thus, in traversing a road, he may find small by-roads omitted, and feel puzzled because he cannot estimate his progress by merely counting each turning met with. It is a help to check oneself by time as a measure of distance. If the map shows the next cross-road a mile ($\frac{1}{2}$ inch) ahead, it will take about 20 minutes to walk: so if a cross-road is met with in 10 minutes, it may safely be considered to be some road other than the one on the map. Again, short but decided bends in a road often are not shown; whilst all curves and bends look more decided on the ground than on maps.

With practice the beginner will learn to read into the $\frac{1}{2}$-inch map a great deal of information which it does not appear at first sight to convey. Taking the specimen of that map given in Plate **6**, and examining the country immediately north and north-east of Oxenton Hill (near the centre of the left margin), it will be seen that this ground is covered with a pale green wash, indicating that it lies between the 200 and 100 contours. From the direction of the streams it appears that the ground falls generally in a N.N.W. direction towards Beckford. Just S.E. of Oxenton Hill is a detached knoll marked 534, and a spur runs out from this knoll in a direction slightly east of north. From the course of the stream, which passes by the *G* of *G*retton Field, it may be assumed that this spur passes through the copse marked just south of the *n* in Alsto*n*e, and

ends in the sharp bend in the river south of the *s* in Little Washbourne. West of this spur there is obviously a re-entrant, with its head at the col connecting knoll 534 with Oxenton Hill, and it may be presumed that the clearly marked re-entrant just south of the *A* in *A*lstone runs into this main re-entrant, and that both finish at the re-entering bend in the river near Little Washbourne Church. There is clearly a spur running N.N.W. from Alstone towards Beckford dividing the Little Washbourne stream from the next small stream to the west. Thus, though this ground is shown by an even wash of colour, the map clearly indicates that it consists of a series of spurs and re-entrants, and not of one even slope.

If the reading of small scale maps be practised in this manner, they will be found to contain a mass of information which is not apparent to the untrained eye.

46. It is occasionally useful to ascertain from a map whether certain points shown on it are mutually visible on the ground. The best methods of doing this are given in Appendix IV.

CHAPTER X.

General Principles of Sketching.

47. The essentials of a military sketch are:—

i. It must be relevant to the object for which it is undertaken.
ii. It must be clear and legible.
iii. It must be completed in time to be of use.
iv. It must be as accurate as circumstances permit.

48. The main principles which underly all map-making, from the most accurate survey to the roughest sketching, are the same. Let us suppose that a representation on paper is required of a given piece of country. It is obtained by first "fixing" on the paper to a given scale the relative positions of a certain number of points on the ground, and thus constructing a framework or skeleton on which we can "hang" the details that lie between the points. These details are filled in subsequently by rougher methods.

The selection of these points of the frame work, or "ruling points," as they are called, is the primary stage in the construction of the map or sketch. They will be points which are most clearly defined on the ground, such as hill-tops, tall trees, church spires, &c.

The distance apart of the ruling points, will depend on the type of the map being constructed, but for sketching purposes it may be taken that all conspicuous well-defined features will be utilized as ruling points—the more that can be "fixed" the better, the idea being that the more points that are "fixed" the less chance is there of the intervening detail being incorrectly drawn in by eye.

To fix the position of these ruling points one of the two methods will be usually adopted, *i.e.*, triangulation or traversing.

49. Triangulation.—In this method we consider our ruling points as making up a series of triangles. Say we have four ruling points—A, B, C, D,

FIG. 16.



where C is visible both from A and B, and D from A and C. If we measure A B on the ground, and by some means or other observe the angles A B C and B A C, we can plot A B to any given scale, draw the angles A B C—B A C, and so fix the position of C.

If we now go to A and to C and observe the anglas D A C and A C D, we can, without actually measuring the length A C on the ground (since we have already had A C plotted on the paper), fix

the position of D; so it is seen that, by measuring one distance between two given points and taking angles from the various points to each other, we can fix the position of any number of ruling points.

The measured distance, in this case A B, is known as the "base," and the points fixed by taking angles are known as "intersected stations" or simply "intersections."

The angle made by the lines A C and B C (otherwise the "rays" from A and B respectively) is the "intersected angle." To obtain the best results this angle should be as near 90° as possible.

50. The usual method of measuring distances, such as the base A B, is by pacing. The beginner before starting work should pace some known distance several times so as to ascertain the number of paces he takes to, say, 100 yards. With a little practice a man of ordinary build can acquire the habit of pacing yards with sufficient accuracy for practical purposes.

51. Rays may be taken either with a ruler (straight edge) or with the prismatic compass. The former method is the simplest and quickest, and is sufficiently accurate for such field sketching as is required of the regimental officer. The ruler is pivoted on the point from which the observation is to be taken, say A (Fig. 16), and then aligned on the ruling point which it is desired to fix, say B. A line is then drawn from A to B. In fixing the position of A on the paper it is necessary to consider the general shape of the area to be sketched. This may be done either by examining a map or by looking at the ground. The position A is then chosen so as to bring the whole of the area on to the paper.

As soon as the ray A B is drawn a compass should be placed on the paper, while the ruler is still pointing from A to B, and the magnetic north line be marked on the paper.

In taking all future rays the sketch should first be set as described in para. **41.** Rays are then taken from A to D and C, the other visible ruling points.

We then proceed to B, which is fixed by pacing, and after setting the sketch take a ray to C. The intersection of the rays A C and B C fixes C.

In practice it is not necessary to draw continuous rays. It is sufficient to mark the intersection. To obtain good intersections the angles made by the rays should be between the same limits as in

resecting (para. **42**), *i.e.*, between 50° and 130°. As soon as two or more ruling points have been fixed, other points from which such ruling points are visible may be fixed by resection as described in para. **42.**

52. Intersections and resections may be made by means of the prismatic compass, bearings being taken as described in para. **27,** and plotted as described in para. **32.** This method is usually more accurate than the method of taking rays with a ruler, but is much lower.

Fig. 7, p. 34, shows a base A B and stations C, D, E, F, G, H, L, K, fixed by intersection.

53. Traversing.—This method will usually be confined to cases where the ruling points are not mutually visible, *e.g.*, in bush country, and so the triangulation method of intersections is not possible. It is also more suitable when the sketch is one of a "route," *e.g.*, a road sketch, rather than of an "area."

Say we have three points A B C (Fig. 17) which we wish to fix we can see B from A, and C from B, but not C from A. If A is not

FIG. 17.



already a fixed point on the sketch we plot it in any convenient position on the paper; we then observe the "direction" of B from A by some means or other, and measure the distance A B.

If we plot the direction on the paper, and measure off the distance A B to scale, we have the position of B. We can then proceed in a similar manner to fix C.

CHAPTER XI.

Sketching with a Cavalry Sketching Board.

54. The cavalry sketching board is a small board which can be strapped to the fore-arm. A magnetic-compass is fixed in the board. Two rollers on opposite sides of the board enable a long strip of paper $7\frac{1}{8}$ inches wide to be carried, the paper being unwound from one roller and wound up on the other as the sketch proceeds. The rollers can be clamped by rotating their ends in the direction noted on the board.

The compass is fitted into a circular metal collar in which it revolves. A fine index line is marked across the glass, which can be adjusted to any required position by turning the glass. Before commencing to sketch it should be so adjusted that when the index line coincides with the needle, the direction of the paper is that of the general direction of the route to be followed.

On the back of the board is a clinometer graduated to 50° and protected by a sheet of celluloid. In order to measure any slope the board is held upright with its straight end parallel to the slope, and the clinometer is freed by pressing the knob. On releasing the pressure, the clinometer is clamped and the slope can then be read off.

55. The cavalry sketching board is suitable for mounted or dismounted sketching. On horseback it should be strapped to the left arm, midway between elbow and wrist. The left hand (the bridle hand) should be kept high, to prevent the board from knocking on the pommel of the saddle. When sketching on foot the straps should be held firmly in the left hand, which should be close up to the back of the board, so that the board may be revolved on the forefinger and thumb.

56. Setting the Compass. Before starting work the compass should be "set" so that the direction of the road runs generally up the length of the paper. The general direction of the route may sometimes be seen from the starting point. If not, its magnetic bearing may be given, or its true bearing may be taken from a map.

i. When the direction is seen.—Turn the board so that the "line of direction" marked on it points along the direction of the route. Holding the board steady, move the line marked on the cover of the compass until the knob end is over the north point of the needle.

ii. When the magnetic bearing is given.—At first ignore the needle. Put the line on the compass cover on the "line of direction," the knob end towards the roller containing the sketching paper to be unrolled when at work; then turn the knob backwards (*i.e.*, by west) through an angle equal to the bearing given. Then when the board is turned until the knob end of the line on the cover of the compass is over the north end of the needle, it is set.

This may be explained by means of a diagram as follows:—

FIG. 18.



Here A B is the line of direction on the board, the circle represents the compass and C D the movable line on the cover, with the

knob end at C. Suppose the magnetic bearing given as the general direction to be followed be 40°. Then we wish to arrange so that whenever the board is set, the bearing of the direction line A B is 40°. To do this we move the line on the cover so that it coincides with the line of direction A B with the knob pointing the way we wish to go. Then we move the knob end of the line 40° to the west, or in the reverse direction to the readings of the compass. Now whenever the board is turned so that the magnetic needle coincides with the line C D, the north point of the needle being under the knob C, C becomes the magnetic north and the bearing of the line of direction A B becomes 40°, which is what we want.

If in the course of the work the sketch runs off the paper, reset the compass and start afresh, having drawn a line right across the paper and marked the ending and restarting point A in each portion. Be careful to mark the north point on each section of the sketch.

57. The following rules should be observed when sketching, either mounted or dismounted, with the cavalry sketching board :—

i. Turn the horse, or body if dismounted, in the direction of the *object.*

ii. Revolve the board until it is "set" by the compass.

iii. By moving the left arm or hand to the right or left, bring the point marking your position, whence the line showing the new direction is to be drawn, *immediately under the eye.* Now align the ruler from this point in the required direction, and, placing the pencil point at it, draw the line *away* from you. It is well to take a second look at the compass at the moment of drawing the line, so as to guard against the board having been moved while the ruler was being aligned on the object.

Any slight alteration of the position of the board, in order to obtain a more exact coincidence of the needle and the index line, is best accomplished at this juncture by gently turning the left wrist and forearm.

The correct alignment of the ruler on any distant point is a matter of judgment and "eye." With a little practice the ruler can be aligned, and the direction drawn in, correct to within 2° or 3°, in between 10 and 20 seconds.

Most horses soon get accustomed to the work, and will stand steady enough for a brief period immediately after being reined up.

After a little practice the ruler can be dispensed with, except for long "shots," and the directions of objects drawn in by placing the pencil point at the place representing the position of the observer and drawing a line in the required direction.

58. Accurate work is not expected with this instrument, but for executing a rapid reconnaissance on horseback, where great accuracy is not required, its handiness makes it eminently useful; for such a purpose the route should be simply "traversed," as described in Chapter IX. The position of prominent points off the route may be fixed by intersections, taken from stations on the route, the position of which has been fixed by traversing.

The **forward bearings** should be taken to the furthest *visible* parts of the route, irrespective of distance.

In settled weather an aneroid barometer may be used for fixing levels. (*See* Appendix II.

The clinometer on the back of the board is of use for measuring slopes roughly in the vicinity of the sketcher.

59. The principal use of a horseback sketch executed as above is to serve as a diagram to illustrate a road report. The report being the essential part of the work, the sketcher must make notes as he rides along, and must generally be on the alert. It is, therefore, not desirable to count paces, for this system is vexatious and laborious and prevents the sketcher from studying the country through which he rides. For the above reasons the best way is to measure distance by *time:*

Allow 12 miles an hour for a canter,
8 „ „ trot,
4 „ „ walk,
under normal conditions.*

Then draw a scale of minutes at the trot on the ruler. Thus:—
Scale of sketch 2 inches to 1 mile,—

In one minute at a trot $\frac{8}{60}$ mile, or 235 yards, will have been covered. This distance can be taken direct from the 2-inch scale on the edge of the board, or by calculation, $\frac{8}{60}$ mile will be represented by $\frac{8}{60} \times 2$ inches $= \cdot 27$ inch.

In using this scale at the walk, halve it. When walking half the time and trotting the other half, take three-quarters.

---

* Practice in keeping the horse at an even pace is essential.

If it is known that the particular horse which is being ridden has not got the *normal* speeds, a special scale should be made.

The best pace to work at is a steady trot.

60. The cavalry sketching board *is also very useful* for work on foot, particularly when completing a previously prepared enlargement (*see* Chapter XII). It may also be used for making a road report on foot or on a bicycle. The methods in this case are similar to those described above, distances being measured by pacing or by counting the revolutions of a cycle wheel. In the latter case it is necessary to ascertain beforehand the distance covered by one revolution, and to prepare a scale of cycle revolutions accordingly.

CHAPTER XII.

Enlarging Small Scale Map and Adding Extra Information on the Ground.—Reports.

61. The methods to be employed in enlarging an *existing map* to a larger scale have been described in Chapter VI, and exemplified in Figs. 5 and 6.

It may be expected in most future wars, that officers will be in the possession of small scale maps. But it is not possible on a small scale map to indicate satisfactorily the positions of small bodies of troops. It must also be remembered that maps are rarely quite up-to-date, and that maps on small scales *necessarily omit* details and certain tactically important information. It will therefore sometimes happed that a map on a larger scale is necessary, and this is obtained by enlarging the small scale map. It will now be necessary to ensure that the information is correct and to supplement it by sketching in and writing additional matter which may be required for the tactical object in view. This process of enlarging and adding extra information is of *greater practical value* than anything else dealt with in this manual, except map reading.

Occasionally when enlarging a map, it is possible to omit certain information which the map contains, and which is of no military value, in order to allow of greater space for the inclusion of new information, but care must be taken that nothing essential is omitted.

62. The best results are usually attained by the following procedure:—

(*a*) Carefully study the tactical object involved with the aid of the $\frac{1}{2}$-inch map provided.
(*b*) Bicycle or ride rapidly over the ground, or to such high points as it is necessary to visit in order to appreciate with the aid of field glasses what special information is wanted.
(*c*) Enlarge that portion of the $\frac{1}{2}$-inch map selected for the sketch to the required scale.
(*d*) Fill in the enlargement on the ground, chiefly by eye sketching, and make the necessary notes.
(*e*) Finish off the sketch, and, if necessary, add a report.

63. With regard to (*d*), where the map contains a number of well-defined features, the position of which can be fixed upon the enlargement, the details of the country between such points can usually be sketched in by eye without difficulty. When, however, the map contains few features, the position of which can be definitely fixed on the enlargement, it will usually be necessary to fix some additional ruling points either by triangulation or by traversing as described in Chapter X.

The beginner should select some point, the position of which can be fixed from the map as a starting point, and from this complete a framework of sufficient ruling points to enable him to fill in the intervening detail by eye. As he acquires skill he will be able to complete the detail at each point before leaving it, so that he need not go over the same ground twice.

64. The formation of the ground can be shown more completely than is possible on a small scale map by the interpolation of form lines, *i.e.*, approximate contours, between those obtained from the enlargement; slopes being shown as explained in Chapter V, *e.g.*, if the enlargement shows contours at a vertical interval of 100′ intermediate 20′ form lines can be put in by eye.

The beginner should place himself at some point on a contour which has been obtained from the map, preferably as high up on a spur from which a good view can be obtained as possible. He should then note the position on the ground of the next contours obtained from the map. If the slope is uniform the distance between the contours can be divided by form lines without difficulty. If it is not uniform the approximate place where the slope changes should be marked on the sketch, the steeper portion of the slopes being

shown by placing the form lines closer together, the gentler slopes by placing them wider apart, as described in Chapter V. The position of water-courses should next be carefully noted and marked in. The position of under features or knolls not shown on the map can usually be fixed either by reference to some neighbouring point marked on the map and by intersection; their approximate height can then be estimated by reference to the position on the ground of some neighbouring contour marked on the map. When the form lines on the principal spurs and water-courses have been marked in and the position of under features has been fixed, the sketcher will have little difficulty in joining up the form lines so as to show the shape of the ground. Form lines should be numbered when first marked in so as to ensure that they are correctly joined up.

65. Some sketchers prefer to execute (*c*) before (*b*) of para. **62,** when the area to be sketched is clearly defined in the instructions, or when better facilities exist for enlarging before going to the ground. As regards (*c*) it is important that the information given should be complete and relevant. The sketcher must avoid the not uncommon error of paying attention only to such matters as affect the particular solution of the problem which he may happen to favour. Information useful to all likely solutions must be given, for the officer to whom the report is rendered must not be fettered in his judgment.

Similarly, notes should state facts, not contain orders. Such expressions on a sketch as "Guns will occupy (3)," "Infantry will advance via Deep Lane" are wrong. They should be "Good artillery position for one battery at (3)," "Covered approach for infantry (4) to (5)."

66. The enemy's troops and works would be shown on a sketch on service. This is "information." But the sketcher's own troops would not be shown unless specially ordered.

In peace exercises, when sketchers are ordered to show the positions they recommend for their own troops and works, they must remember that this is a separate exercise, and does not relieve them from executing the sketch and notes on the lines laid down in para. **65.**

67. Next in importance to supplying the particular information required, is the preparation of such information in the right way. The common-sense rule, that the sketcher should do what he would like to find done if he had to use the sketch and report himself, is the general guide. Typical forms of reports cannot cover every

case, and it is desirable to keep the mind alert to examine and treat each problem on its merits, rather than to try and remember lists of headings. The treatment must be intelligent rather than mechanical.

To assist officers undertaking this work, the following suggestions as to the type of information that should be added and as to the method of arranging it are given. It is not possible to foretell for what tactical purpose the information is required, but the instructions in the following paragraphs may be taken as a general guide.

68. In drawing up his report the reconnoitring officer should be as concise as possible, and should be careful to confine his information to what is relevant.

The most satisfactory method is to divide the report into two parts. The first part should contain a general description of the outstanding features of the reconnaissance, to enable the reader to get a grasp of the subject without having to wade through a mass of detail. The second part should contain the details in tabular form. For the same nature of reconnaissance (road report, river report, etc.) the headings in Part II, should usually be the same; those in Part I, however, should be varied according to the tactical object of the reconnaissance. The disadvantages of a cut-and-dried form are counterbalanced by the greater ease with which items of information can be turned up or reports collated.

Where the names of foreign places or towns are spelt in various ways, the anglicised form should be used, followed by the local form in brackets.

Care should be taken to distinguish between what are impressions or hearsay only and what are facts.

69. *Road reconnaissance.*

i. The information should supplement that given on the sketch, and not repeat what is already shown.

ii. The information should be definite, *e.g.*, it is not enough to know that animals can be watered in a stream, but the numbers for which there is room, its depth, etc., must be given.

iii. *Tactical Information.*—Definite information is specially important when tactical questions are dealt with. Thus it is not sufficient to say that a certain ridge forms a defensive position. Information on the following is usually required: limits of the position and force required to hold it; nature of ground in front and flanks, and of

soil for digging; localities which would form strong defensive points, artillery positions, own and enemy's; what the view is like, points from which an extended view is obtainable and the average field of fire; best lines of attack and counter-attack; communications and water.

In order to make a good tactical reconnaissance it is advisable, before starting, to find out with what "special idea" the reconnaissance is to be undertaken.

iv. *Road Details.*—Roads should not be classified solely by their width, though information as to their width may be important (*see* para. **13**). The surface condition and material for repair must be considered. The ease with which troops can deploy from them is important. The nature of the fences or ditches enclosing the road should be mentioned.

v. *Gradients.*—Only such gradients should be mentioned as will affect the rate of marching.

vi. *Bridges.*—It is not necessary to give details of every culvert, but bridges of any importance should be fully reported on. It is important to know if a bridge will bear mechanical transport. The type of bridge, material, length, width, height above ground or water, parapet, and approaches should be noted.

vii. *Turnings.*—Mention turnings only when they present some difficulty, *e.g.*, through a town where the names of the streets should be given.

viii. *Observation Points.*—Places from which a view can be obtained should be noted, with the direction and extent. The names of distant objects that can be identified should be mentioned, such as churches, country houses, &c.

ix. *Local Administration.*—System of local administration should be noted; the identity of influential individuals or functionaries should be established.

x. *Supplies.*—For a thorough report on a district an expert is almost essential, but much useful information can be obtained by the non-expert without going into too great detail. Enquiries in the towns will produce better results in a shorter time than visiting a large number of farms.

In the former seek for flour mills and find out the normal amount of grain kept in stock. From the butchers ascertain if the locallity is self-supporting, or if much frozen meat is brought in. For groceries find out the biggest firms, and ascertain at what intervals of time

stocks are renewed: the date of the last order will show how long present stocks will last. Find out how many rations of tea expressed in $\frac{1}{3}$ oz. and of sugar in 4 oz. he has in hand; the lower number of the two divided by the number of days the stock is estimated to last will give the approximate number of consumers. This enables the number of grocery rations obtainable to be estimated, as other groceries are usually present in sufficient quantities.

HEADINGS FOR PART II.

Place.	Distance in Miles.		Details of Road.	Remarks.
	Intermediate.	From		

70. *River reconnaissance.*

i. Owing to the variety of tactical uses to which a river may be put, the particular object of the reconnaissance should be ascertained before starting, and the report drawn up accordingly.

ii. The headings in Part I will vary according to the tactical object, those in Part II, which contains nothing but facts about the river, need not vary.

iii. The velocity of a river can be found by throwing a piece of wood well out and timing it over a measured number of feet. Mean velocity = $\frac{4}{5}$ surface velocity. $\frac{7}{10}$ mean velocity in feet per second = number of miles per hour.

iv. Ice 3 inches thick will bear men in small detachments; 6 inches thick, horses and carts; 9–12 inches thick, wagons and guns.

HEADINGS FOR PART II.

Crossing.	Details.	Fit for mechanical Transport.	River.			Quays.		Boats and barges usually available.	Approaches.		Remarks.
			Breadth yds.	Depth ft.	Velocity m. per hr.	Right bank.	Left bank.		Right bank.	Left bank.	

71. *Railway reconnaissance.*

i. It should be borne in mind that an expert would be required to write an adequate report on which to work a railway.

ii. *Stations.*—In ordinary circumstances a rough sketch of the stations, on which the following information is shown, would suffice:—The approaches; number of lines; cross-overs; number, length, breadth, and height of platforms; number and length of sidings; water; turntables; end-loading and other ramps; goods sheds, lighting.

iii. *Forming-up places.*—Places suitable for forming-up troops before entraining or after detraining, with their area, approaches, water supply, &c., should be reported.

v. *Track.*—As regards the line itself, the gauge, any unusual gradients, type of fuel used, any triangles, and details of any bridges of importance should be noted. In case of a single line the distance between crossing-places.

73. *Billeting reconnaissance.*

i. In reconnoitring areas for billeting purposes the population of the town, village, or parish, whichever is available, must be taken as the basis of calculation. In addition to estimating the number of men per inhabitant that can be accommodated, the number of vehicles per inhabitant should also be given.

ii. Billets without subsistence can be provided at varying rates.

The best class of village in a rich agricultural district will take up to 10 men per inhabitant; a residential town or village with good houses and wide streets about 5 men per inhabitant; while industrial towns with a dense population and a poor type of house will take still fewer.

iii. There are various questions affecting billeting, such as supplies, railways, &c.: as a rule, these subjects should be treated generally in Part I. of the report, details only being given when particularly required.

iv. Particular care should be paid to giving details concerning the water supply, any large buildings, such as schools or country houses, which will accommodate a considerable number of troops, and any open spaces where troops can collect or vehicles be parked.

v. In many civilized countries chief officials of localities keep detailed lists showing billeting accommodation. Efforts should be made to obtain these.

vi. In a billeting report based on the population of each parish, the small hamlets in each parish should be mentioned by name, as well as the parochial headquarters.

PART II.

Name of Parish, Town, or Village.	Pop.	Billets.			Nature of surrounding country.	Water Supply.	Railways.	P.O. Tel. O. Tph. O.	Supplies.	Remarks.
		Men.	4-horse vehicles.	6-horse vehicles.						

74. *Reconnaissance of an enemy's position with a view to attack.*

The following are the chief points on which information is desirable:—

i. The general front of the position, so far as it can be ascertained. The probability of advanced troops covering the real position will have to be considered.

ii. Points from which a good view of the country occupied by the enemy can be obtained.

iii. Localities to which the enemy is seen to be devoting attention, and any others which would appear likely to be of special tactical value to him. The position of any trenches, obstacles, &c., that can be located should be carefully noted.

iv. Lines which afford the attack most cover during their advance and which offer facilities for covering fire, both from guns and rifles, where it is exposed to hostile view and fire.

v. Tactical points on the above lines of advance and elsewhere, the possession of which will favour the development of superiority of fire over portions of the enemy's position.

vi. The manner in which the flanks are secured, whether they rest on natural obstacles or whether there are any indications of supporting troops and works echelonned to the rear.

75. *Defensive reconnaissance.*

When it is intended to occupy a defensive position, with a view to subsequent offensive action, the chief points to be noted are :—

i. The extent of the position, the localities of special tactical importance in it and the means of securing the flanks.

ii. The minimum force necessary to occupy the position.

iii. The positions for the artillery and for the infantry firing lines. These should be considered together, so that the best use of the ground may be made.

iv. The best line or lines for the counter attack.

v. The most favourable lines for the enemy to attack on, and positions from which his artillery can best support such attacks.

vi. Any tactical localities, the possession of which might enable the enemy to develop superiority of fire against some part of the position.

vii. Any advanced position, the occupation of which might have the effect of misleading the enemy and forcing him to a premature deployment.

76. Notes on the way to finish up sketches will be found in Appendix III.

CHAPTER XIII.

Eye and Memory Sketching.

77. Although it is improbable that an officer unprovided with instruments would be required to sketch a large area of country, it may happen that on service, he will find it necessary to send in a plan of the country in the immediate vicinity of his post. For instance, an officer in command of an outpost company, he would probably

have to furnish to his superior officer a sketch of the ground on which his troops were disposed. Moreover; a plan-sketch is a useful addition to any written report.

Without any instrument whatever, it is possible to execute, with fair accuracy, a plan-sketch which from a military point of view may prove of considerable value. The making of such a sketch is much facilitated by the mastering of the principles of sketching described in Chapter X.

The sketcher requires a pocket book, such as Army Book 153, or a flat board, and ruler.

Board.—A piece of board of convenient size, a smooth-covered book, the lid or a biscuit tin, or any similar article to which a sheet of paper can be attached. (To keep the paper stretched over the board, or other article, perhaps the simplest way is to secure it with two pieces of string, tied tightly round paper and board at either end.)

Ruler.—A slip of wood, or stout cardboard, with a straight edge.

Not being provided with a protractor or a scaled ruler, the sketcher must construct a scale to which to draw his sketch. The scale to be adopted for any sketch depends on the area of the country to be sketched, and on the size of the sheet of paper available. Assuming that the maximum area required is a square mile, the scale can be a comparatively large one; for even an ordinary pocket-book (such as Army Book 153) would permit of this area being drawn, on a single page, on a scale of 4 inches to 1 mile. In most officers' pocket books squares of a certain size are ruled on the pages; *e.g.*, in Army Books 152 and 153, the squares are $\frac{1}{4}$ inch. If, therefore, a book of this kind is available, a ready-made scale is at hand, otherwise a scale must be thought out.

The sketcher should decide on what he thinks will be a suitable length to represent 100 yards, or other distance, and mark it on the edge of his improvised ruler, as well as on the edge of a slip of paper. By moving the latter along the ruler's edge as many lengths of 100 yards, or other distance, can be marked off as are considered necessary. The divisions should be numbered as usual, and the scale should be drawn at the bottom of the sheet of drawing paper. If at some future time a foot rule, yard measure, or anything of the kind, divided accurately into inches, is forthcoming, the number of yards to the inch can be discovered and a representative fraction worked out.

It is useful to remember that the lines on a sheet of ruled foolscap are as nearly as possible one-third of an inch apart. So a strip of such paper, cut lengthways, makes a handy scale, the intervals between the lines being approximately equal to 100 yards on the 6-inch scale, 150 yards on the 4-inch, 200 on the 3-inch, 300 on the 2-inch, and 600 on the 1-inch. Another useful measurement to know is that the diameter of a halfpenny equals one inch.

78. The sketch is executed by first arbitrarily fixing on the paper a point to represent the position of the sketcher.

Then, pivoting his ruler on the point thus fixed on the sketch, he aligns the ruler on distant points, and draws rays on his sketch in their direction.

It is necessary for the sketcher to get his eye well down along the alignment of the ruler so that the direction of the ray may be obtained as accurately as possible.

The detail required on the sketch is filled in before the sketcher moves from his position. Having completed this, he marches in the direction of a point whose direction is fixed by a ray on the paper, and plots to scale along this ray the distance traversed.

In order to set his sketch for further work, he must align this ray on the back station, from which he has come. He then proceeds as before to obtain intersections and fills in the detail to be sketched in around his new station.

79. It will often happen on service that reconnaissances have to be made under conditions which make any sketching on the ground impossible. In such circumstances a memory sketch will often furnish a useful complement to a report. When possible, rough notes as to direction, distances, and the shape of the ground should be made during the reconnaissance in order to assist the memory, but it will be found that with practice a fair representation of the ground may be drawn without any notes at all.

In observing ground with a view to making a sketch of it subsequently from memory, it is important to distinguish between the essentials for the purpose of the reconnaissance and details of minor importance. No attempt should be made to burden the memory with the latter.

Plate 16.

To face page 67.



Plane-Table, Portable, Mark II, 18 Inches Square.

PART II.

CHAPTER XIV.

Plane-table Sketching.

The plane-table.

Note.—*The use of the plane-table at the military colleges is authorized for the purpose of teaching cadets the elementary principles of the construction of a sketch.*

80. The plane-table is merely a portable table. The table or board can be carried separately from the stand, and when fixed to it can be turned round to "set" the sketch without moving the legs. The stand is usually a folding tripod, and, for greater compactness, is sometimes collapsible. The adjuncts to the plane-table are the sight-rule and the trough compass; the plane-table should also be provided with a waterproof cover.

81. The sight-rule should be about as long as the shortest side of the table, and the fittings should be of gunmetal or brass, not iron or steel. A common defect of sight-rules is that the slit in the rear vane is too small. When working in hilly country the centres of the tops of the vanes should be joined by a string, tense when the vanes are upright, to enable rays to be taken on steep slopes. It is convenient for the sight-rule to be graduated with useful scales, for instance, 2 inches to 1 mile, as in the Service pattern.

82. The trough-compass should not be combined with the sight-vane. The 6-inch trough-compass in mahogany box with sliding lid, which throws the compass off its pivot, is the best. Trough-compasses should be stored horizontally. If not already adjusted to float horizontally, they can be adjusted by tying string round the elevated end of the needle and dropping sealing-wax on to the string. Where a trough-compass is not available, the Service prismatic compass can be used instead.

83. Mounting a plane-table.—With an ordinary plane-table which has a plain board, pin the paper on to the board with drawing-pins. All arrangements of clips should be avoided.

84. The plane-table is the most accurate instrument employed in making military maps and sketches and it is important that the student should master the methods described. The following are *general maxims* which should always be observed :—

i. See that the leg-screws and clamping-screws are taut before beginning work.

ii. Spread the legs of the table widely, especially with collapsible patterns (since the steadiness of the table largely depends on the spread of the legs). In soft soil the legs should be well pressed into the ground. The board should be horizontal.

iii. Always keep the pencil sharp ; there should be no error in essential features greater than the thickness of a pencil line. An H pencil is suitable, the point being kept fine by rubbing on a piece of glass paper fixed on the board by a drawing pin. With acute intersections, which must sometimes be used, fineness of line is absolutely necessary. No good results can be expected with a blunt pencil. Points required afterwards for resection should be marked by fine dots surrounded by a circle.

iv. When it is required to draw a ray from a point, put the pencil upright on the table with the edge of the base just touching the point, and lay the sight-vane against the pencil. Instead of a pencil, some expert plane-tablers use the finger ; but pins would not be used by a good plane-tabler.

v. When drawing a ray from a point on the sketch, set the point of the pencil into the point first, so as to get the correct angle at which the pencil should be held when drawing it along the sight-vane. Without this precaution large errors creep in.

vi. Whenever the plane-table has to be set up or oriented by a previously drawn short ray it is most important that the ray, when it is first drawn, should be extended by marking short lengths of it at or near the edges of the board. These marks give a good line along which to lay the sight-vane.

vii. When drawing a ray to a distant object, mark its approximate position, as estimated, by a small circle on the ray. Write the name of the object along the ray.

viii. In making an intersection with a second or third ray, it is not necessary to draw the whole ray. About a $\frac{1}{2}$ inch of it across the point of intersection will suffice.

ix. Never set the plane-table by the compass if you can set it by an alignment on some distant point or points already fixed.

85. The steps to be taken in making a plane-table sketch are as follows :—

i. **Select a Base Line.**—This should be on level ground. It should occupy a fairly central position, though this is of no great importance.

Both ends of the base should be visible from well-marked natural points in the area to be surveyed, and from each other.

The length of the base would usually be from $\frac{1}{2}$ mile to 1 mile, but the longer the better. A good rule is that the base should be about 2 inches long on the paper; but this is longer than can usually be obtained. If possible mark the ends of the base; or, if this cannot be done, measure between existing points or objects; or else measure in the same line as two existing objects. A base is usually selected on high ground because its ends then afford good points of observation. In some districts, however, where the higher ground is much wooded, and gaps are short, it is often better to select a base in an open valley. From this the prominent features of the hills on each side can be more easily fixed; and, when fixed, can be used as stations to fix detail in the valley.

ii. **Measure the Base.**—This must be done by careful pacing, the accuracy of the triangulation depending on the correctness of the base.

iii. **Fix Points by Intersection.**—The most suitable position for the base on the board must be carefully considered before commencing work; the amount of country to be surveyed, and the position of the prominent points required for resection, being taken into consideration.

Set up the plane-table at one end of the base, and draw rays to the other end of the base and to prominent obtects within the area to be surveyed, or not far outside.

Place the compass in its box on a corner of the table, and move the compass until the needle points steadily to the centre division; then draw a line on the table at each side of the box, marking the north end. Remove the compass. Check the position of the needle subsequently in the course of the work at intersected stations. Go to the other end of the base; place the sight-vane along the pencil line representing the base; set the plane-table by moving the board until the sight-vane is aligned on the first end of the base; then draw rays to the same prominent objects used before, thus fixing their position by intersection.

It may sometimes happen that one end, A, of a base AB, has to be selected because there is a prominent object there, but that a better station, C, is close at hand to take rays from. C has, however, no object to define it, *e.g.*, it may be in an open field. It may be used to observe from by fixing its position from A. The board is set at A on B, a ray is drawn to a big stone or stick put at C, and the distance AC is measured carefully and plotted. The object at A can be used for resection purposes.

Next go to one of the points intersected which makes a well-conditioned triangle with the base, test its position by setting up by one end of the base and by an alignment on the other, and then draw rays to all the other intersected points which are visible and to any new points which may be likely to be useful. Except in the immediate neighbourhood of the base, it is desirable that each intersected point should be fixed by three rays, particular care being taken to ensure the greatest possible accuracy in fixing points which may afterwards be used for resection.

It is by no means necessary to cover the whole of the sketch with intersected points; but it is important that the positions and levels of ruling-points should be fixed, others being sketched in by eye to save time.

It often happens that on proceeding to an intersected point, X (*e.g.*, church spire) the table cannot be set up over it, or the ground just there may afford no view of points you want to fix. The table should then be set up near it, and on a line between it and some other fixed point. Pace along this line the short distance you are from X, plot it to mark the point over which your table now is, and work from it as a station.

iv. **Fill in the Detail; mainly by Resection.**—Resection from three known points, sounds a formidable process, but in reality it is very simple. It is the principal means by which the bulk of the detail, which cannot be eye-sketched from intersected ruling-points, should be fixed.

The method is as follows:—

Set up the plane-table at any point from which three previously fixed points can be seen. Orient the table by the trough-compass, and from the three fixed points draw back-rays. If these three rays pass through a point, this point is the required position.

If they do not pass through a point, the rays will form a small triangle called the "**triangle of error.**" The true position is now to be determined by the following rules :—

I. If the "triangle of error" is inside the triangle formed by the three fixed points, the position is inside the triangle of error; and if outside, the position is outside the triangle of error.

II. In the latter case the position will be such that it is either to the left of all the rays when facing the fixed points, or to the right of them all. Of the six sectors formed by the rays, there are only two in which this condition can be fulfilled.

III. Finally the exact position is determined by the condition that its distances from the rays must be proportional to the length of the rays, *i.e.*, the position on the sketch must be nearest to that side of the triangle formed by the shortest ray, and furthest from that formed by the longest ray.

FIG. 19.



In Fig. 19, for instance :—

By condition I the point must be outside the triangle of error.
„ „ II „ „ „ in sector 6 or in sector 3.

By condition III the point must be in sector 6,* since the distances from it to the rays must be proportional to the lengths of the rays, and by estimation it will be where shown.

Having thus determined the position, place the sight-rule along the line joining it and the most distant of the points used; set the sight-rule on the point by revolving the plane-table; clamp and test on the other two points. If there is still an error (which should, however, be much smaller), go through the process again.

The best position is inside the triangle formed by the three fixed points, of which two are near and one is distant. Accuracy of *position* is ensured by two points being near, accuracy of *setting* is ensured by aligning on the distant point. Generally fix from near points. Set by a distant point.

It is very necessary to be able to make fixings by this method both rapidly and accurately. It is the essential foundation of all rapid plane-table sketching. The plane-tabler in open country need not pace or measure a yard after he has fixed his base. In addition to the speed which results from a free use of resection there is also a gain in accuracy, since there is no piling up of errors, and each fixing is dependent only on the main intersected or other well-fixed points.

When there are a number of points, any three of which may be used for resection purposes, recollect in choosing the point to be used that—

(1) When the three points chosen, and the observer's position lies on or near the circumference of a circle, the accurate determination of the observer's position is not possible by this method.

(2) The three points chosen should be such that the rays from them do not intersect at acute angles, and thereby make a badly shaped triangle of error.

(2) Choose points which are most accurately fixed on the sketch (*e.g.*, those of the base or directly fixed from the base). Beginners are often discouraged and distrust this method, because they cannot get an absolute fixing for their position when resecting from points, which have not themselves been accurately fixed on the sketch. The method, however,

* To make this clear, take a point anywhere in sector 3. It will be seen that it lies nearer to at least one of the long rays than to the shortest ray, and condition III would not be fulfilled.

is an absolutely exact and accurate one. It will have been noticed that the trough compass is only used to orient the plane table approximately, and that the final fixing does not at all depend on the compass. It is important that this should be remembered.

Two useful methods, which can often be adopted with good results, should be noted:—

(1) If the sketcher can place himself anywhere on a line prolonged through two points previously fixed, he can set his board by them and fix his position on this line by resecting from any third fixed point which gives a good angle of intersection.

(2) If on setting up at any point C it is noticed that a ray to some other useful point D has been omitted when at a previous station A, draw a single ray to D from C. Then go to D and use this ray to set the table. Resect from A, by pivoting the sight vane about the point A, and drawing a ray backwards from A till it cuts the ray D C. The intersection of these rays is the position of D.

v. **Resection from Two Points.**—It will sometimes happen that only two fixed points or stations are visible; in this case the plane-table must be oriented by the compass, and rays must be drawn back from the two fixed stations intersecting in a point which must be taken as the required position. It is clear that such a fixing depends entirely on the compass, and may, therefore, be very inaccurate. In parts of South Africa such a fixing would, on account of local magnetic attraction, be entirely worthless, and it is obvious that as a general rule compass fixings should be avoided.

This method should, if possible, only be used for putting in detail, and not for throwing out points on which future work will depend.

Whenever a fixing has been made the local detail should be drawn in; a combination of measurement and estimation should be used; the amount of estimation permissible will depend on the scale. Thus, on scales of 2 inches to 1 mile and smaller scales it is not necessary to pace the width of roads or sizes of houses: these are put in conventionally. On a scale of 2 inches to a mile a distance of 8 yards is less than $\frac{1}{100}$ inch, so that any distance may be estimated which is not likely to be 8 yards in error, and so on. When time presses, minute accuracy must be sacrificed.

vi. **Traverse Detail which cannot be fixed by Resection.**—It will sometimes happen even in open country that there are parts of the work, such as valleys and woods, in which plane-table fixings cannot be made; in this case it is necessary to have recourse to plane-table traversing. Plane-table traversing has to be much used in flat country unprovided with prominent landmarks, and was used in the mapping carried out during the operations in China in 1901.

The method is as follows:—Set up the plane-table at some known point and orient it by some other known point that can be seen, the further away the better. Then proceed as directed in Chapter X, fixing the direction with the sight rule, and pacing the distance.

Traversing does not give accurate results, and should only be used where unavoidable.

86. The above are the methods of using the plane-table to fix the positions of ruling and subsidiary points. The detail is sketched in as the sketcher progresses for any section of ground where sufficient ruling points have been fixed to enable this to be done. Experience will teach the sketcher how to select the order in which he will visit ruling points, so as to end at one which affords a good view for sketching in by eye the remainder of each section.

Beginners usually make the error of utilizing instruments too much in field sketching, and of fixing far more points of detail than is compatible with rapidity of work. It is, therefore, important to remember that when ruling points are fixed correctly, small displacements of intervening detail are of no importance compared with the value of rapid methods of work, so long as such information is given as is required by the object of the sketch. As the student progresses he should fix such detail more and more by eye.

CHAPTER XV.

Panorama Drawing.

87. A useful branch of field sketching is the representation of a landscape in a conventional form, or the art of representing the country in elevation instead of in plan. Such sketches, which are

called panoramas, are useful to illustrate a report, and may add considerably to its value and clearness. A panorama is often an invaluable adjunct to a report upon an artillery position, and may be of assistance when firing at moving objects from under cover, for switches, and in night firing (*see* Field Artillery Training).

It may be premised that, from a military point of view, it is not necessary to be an artist to produce a useful panorama. Indeed, it is better almost that the artistic sense should be absent, and that instead of idealizing a landscape, it should be looked at with a cold, matter-of-fact military eye. Thus the sketcher would note rather the capabilities of the country for military purposes than it beauties of colouring or the artistic effects of light and shade.

The beginner often feels much discouraged because his first attempts are so unlike what he wishes to draw, but with patience and practice and a close attention to the hints in this chapter, he will find that in time he will be able to produce useful work. Let it be understood that however rough the picture may be, it will still be useful if intelligently drawn. Another difficulty is that of drawing the trees, houses, &c., as they are seen in the landscape. Absolute accuracy in the details of their appearance is not essential. So long as the sketcher can faithfully produce the outline of the important military points of the panorama, the other details can be drawn in a conventional manner. It is better to stick to bare outline as far as possible and leave shading alone, except such as is required to indicate distance in a conventional manner. Unnecessary shading in a panorama tends to confuse and detracts from its clearness.

Let the beginner learn by degrees, drawing small and easy subjects to commence with, before trying anything too ambitious. Let him copy other drawings, and thus gain confidence in his own powers. Plate 17 shows some examples of methods of drawing objects in nature in a conventional manner.

88. The sketcher should study the ground very carefully before commencing to draw it. He should make a free use of the field glasses or telescope to assist in resolving details which appear confused and in defining accidents of ground that are not clear to the naked eye. The more carefully the country is studied beforehand, the easier will it be to draw it. In commencing to draw a panorama, the first thing to do is to choose a suitable point of view from which to sketch it. This depends on two things:—(*a*) The extent of

country to be included in the panorama, and (*b*) a position from which a good view can be obtained. In a measure, these two conditions are closely associated. The wider the extent of the panorama, the further off must be the position from which it is drawn. It will be understood that the wider the visual angle, the more inconvenient it is to draw all that it includes, and it may thus be necessary to make a panorama of the country in two or more sections and to join them together afterwards.

Having chosen the point of view, the next task is to draw the picture. Here the beginner is confronted with a series of difficulties, some of which are:—

i. How to begin.

ii. How to keep the dimensions in the picture proportionate to the apparent dimensions in nature.

iii. To overcome the difficulties of perspective, and to get the receding effect of distant objects.

iv. What to include in the drawing and what to leave out.

To take these points in detail—

i. First select the position from which the sketch is to be made. This should be some point where the sketcher can sit down comfortably with a good view of the ground on which he wishes to report. The position should be as central as is convenient. The beginner should use squared paper, such as that in Army Book 153. Until he has acquired some skill in the use of a pencil he should use two, one hard for drawing in the distance, the other medium for the middle distance and foreground. A ruler about a foot long with a piece of string about one foot long tied round its centre, will be of assistance in measuring distances and angles.

ii. The next step is to settle the length of the panorama. This depends on the extent of ground to be reported on, but if this is large it is not necessary or advisable to attempt to include the whole in one panorama. As much as is convenient may be drawn from one point of view, and the remainder of the ground be shown in a second panorama, viewed from elsewhere, normally about one foot, *i.e.*, about the length of a double sheet of Army Book 153 when opened at the centre, may be taken as a convenient limit.

Hold the ruler horizontally at such a distance from the eye that one end coincides with the left of the distance or skyline of the

country to be sketched, and the position of the thumb on the ruler with the right. Now, without altering the position of the ruler, measure by means of the string the distance of the ruler from the mouth. Tie a knot to mark this distance, then if the knot be held in the teeth and the string pulled taut the ruler will be kept at a uniform distance from the eye when making future measurements. This is important as otherwise the results will vary.

Mark off on the paper the horizontal limits thus measured on the ruler, and then measure the vertical limits in a similar manner by holding the ruler vertically. These vertical limits should be marked on both ends of the paper.

Now consider the skyline carefully and select some prominent point on it as nearly as possible directly opposite to your position. The hill with the flagstaff on it in Plate 18 is such a point. Fix the position of this point by measuring its distance from the edge of the paper and its height from the bottom of the paper. From this point measure off the distances to other prominent points, such as the two fir woods on the skyline (Plate 18), measure carefully their relative heights, with reference to the bottom of the paper, and mark their positions on the sketch.

Next consider the middle distance and the ground near you. Select, if possible, some tall objects which cut the ground to be sketched vertically, such as the two railway signals, the side of house and the outer trees of the fir wood in the left foreground. Measure the distances with the ruler as before, and mark the positions of these objects on the paper with horizontal lines. If no suitable tall objects are available any prominent objects will do.

In this way the positions of a number of ruling points are fixed, and a framework is made in much the same way as when making a triangulation.

iii. The chief difficulty experienced by the beginner is in being unable to produce the receding effect in his picture; in other words, perspective. A close attention, however, to the following simple rules will overcome this difficulty quite sufficiently for military purposes.

First of all, as regards the size of the objects. It will be noticed in looking at the landscape that, as objects are placed further off, they appear smaller. Therefore, make them so in drawing the panorama.

The further off the details in the country are, the thinner must be the lines with which they are drawn. Thus—

In drawing the nearest part of the picture, use a medium pencil with thick strokes.

FIG. 20.



A simple Example of Perspective

(The vanishing point A to be spectally noted)

The middle distance, which lies between the foreground and the background, should be depicted in strokes of medium thickness, or with an ordinary pressure.

Lastly, the background, or far distance, should be drawn in fine strokes with a hard pencil, or with one used with a very light hand.

In other words, the nearer an object is, the thicker and heavier the strokes with which it is drawn, and the further off it is situated, the thinner and lighter must be the strokes.

iv. What to include and what to leave out of a panorama is a matter of judgment, but the following points are of importance:—All details that have any bearing on the military situation should be carefully drawn. For example, in making a panorama of an enemy's position, hedges, fences, &c., that would be held by him, or that would assist an attack, should be put in carefully. Obstacles such as rivers, marshes, and so on, are of importance. Church towers and steeples, factory chimneys, outstanding and easily recognized trees, such as poplars, being landmarks, are useful. Woods should also be included. The foreground, *i.e.*, the ground immediately in front of the sketcher, is rarely of tactical importance, and except when it is it should be omitted. These are not all the points, but they serve to indicate the line to be taken. When drawing villages it is not necessary to put in every house, but to represent generally the shape and extent of the village, while carefully drawing the outline of any special feature that serves as a landmark, such as the church or a big house or building.

There is always a tendency to exaggerate the heights of hills, this must be avoided, as it leads to misrepresentation. There is also a tendency to exaggerate the size of houses, &c., in the distance. This has the result of making these appear nearer than they are.

89. Having considered the above difficulties, the sketch can now be commenced. First draw in the outline of the skyline lightly with the aid of the points already fixed. Then draw in as accurately as possible the other principal objects, the position of which has been marked. Now the picture will be divided into sections by these objects. In finishing the picture, each of these sections should be taken in detail and all that there is to be seen in it of military value should be drawn in, and thus the picture is completed, section by section.

The preliminary work of a landscape sketch should be drawn with a very light hand, and the smoother the paper the better.

In finishing the drawing, it is best to commence with the background, and work, gradually thickening the strokes, towards the front, where the thickest and blackest strokes are used.

It is of great assistance to clearness to show water, roads, &c., in conventional colours by means of chalks.

The last thing to do is to insert the information, viz., the point, referring to a map if there is one, from which the sketch is drawn, and the direction in which the centre of the picture is situated, the names of places and the ranges to them, &c.

The date and state of the weather should be included; a panoramic sketch is much affected by atmospheric conditions.

For these and other details, *see* Plate 18. Plate 19 shows a sketch prepared on squared paper for use in an artillery position; Plate 19A being the corresponding range-taker's card.

Plate 20 shows a sketch actually executed during the Chitral Expedition, 1895. This, although a very useful sketch, omits some points which it would have been desirable to insert, *e.g.*, the compass direction.

Plate 21 shows a sketch executed by one of the British officers attached to the Japanese Army in Manchuria to illustrate his report on the Battle of Liao Yang.

The sketches represented in these Plates show in some casss more shading, &c., than is either generally necessary or possible under service conditions, the process of printing having considerably elaborated the originals.

90. Finally, the telescopic sketch, as it might be called, may be considered. This is a sketch which is made by the help of a telescope or good field glasses, of a distant piece of country, of which the details cannot be clearly seen by the naked eye. At first this may seem difficult, but practice will soon overcome it. First the subject should be looked at carefully with the naked eye, and an outline enlargement of it should be made on the paper. Then the detail should be filled in bit by bit with the aid of the telescope. The telescope should be on rests, and the paper directly under the eye-piece, so that after studying the subject through the telescope the sketcher can look at once on the paper and draw in what he sees.

CHAPTER XVI.

Elementary Instruction in Marching by the Stars.

91. Night marching under the best conditions is an operation demanding the greatest care and practice on the part of the guide. The method of night marching by means of the Service Prismatic Compass has been described in Chapter VII.

The most favourable conditions for a night march are a clear starlight night and no moon.

The guide first ascertains the magnetic bearing on which he intends to march during the night.

He next selects a star, which has the required bearing. The methods that can be employed in the selection of the star are as follows :—

The black direction mark on the glass face of the service compass is turned till it coincides with the required bearing shown on the external ring. When the black arrow head is made to correspond with black direction mark, the line between the luminous patches on the lid indicates the line of advance.

A stick is set up in prolongation of this line, and a star can be selected which is in the alignment with the stick. The advance can then be continued on that star for 10, 15, or 20 minutes, according to the position of the star in the heavens. He should then halt and take a fresh observation.

92. The most convenient stars to select for marching on are those which happen at the time to have an altitude of from 15° to 30° ; stars below 15° may become lost in haze, whilst for those above 30° the head has to be inconveniently raised. Speaking broadly, a star at these altitudes will rarely move more than 5° in azimuth (*i.e.*, to a flank) in 20 minutes. Hence if at the end of every 15 or 20 minutes the observer halts and takes a fresh bearing, he can count on keeping direction correctly.

Although it is of assistance to an observer to know the stars, it is not *necessary* that he should do so. Anyone can, with care, march on a compass bearing, with the stars as points to direct him, with satisfactory results, although he may be totally ignorant of the

names of the stars or even of the constellations. The great point is to be sure that the compass bearing is correctly taken and prolonged, and that the star selected is adhered to until a change is required.

Appendix I.

FOREIGN MEASURES.

Metric System—

Used in

Argentine Republic, Austria-Hungary, Belgium, Bolivia, Brazil, Bulgaria, Chili, Columbia, Costa Rica, Ecuador, France, Germany, Greece, Hayti, Holland, Italy, Norway, Portugal, Rumania, San Domingo, Servia, Spain, Sweden, Switzerland, Turkey, United States (partially), Venezuela.

Measures of Length.

—	Inches.	Yards.
Millimetre	·039	·001
Centimetre	·394	·011
Decimetre	3·937	·109
Metre	39·37	1·094
Kilometre	39370·79	1093·633

Square Measures.

—	Sq. yards.	Acres.
Centiare (square metre)	1·196	—
Are (100 square metres)	119·603	·025
Hectare	11960·333	2·471

Other Foreign Measures.

Russia	Sajen	= 7 feet.
	Verst (500 Sajen)	= 1,166·6 yds.
	Sq. Verst	= ·44 of a sq. mile.
	Desyatina	= 2·7 acres.
Denmark ...	Miil (2,400 Rode)	= 4·68 miles.
Persia	Farsakh	= 3·87 miles (about).
	Zar (16 Gercho)	= 40·95 in.
Egypt	Kadam	= 1 foot.
	Diraa or Pik	= 22·83 in.
	Kassaba	= 11·6 feet.
	Feddan	= 1·04 acres.
China	Ts'un	= 1·41 in.
	Ch'ih (10 Ts'un)	= 14·1 in.
	Chang (10 Ch'ih)	= 141 in.
	Li	= ⅓ mile (about).
Japan	Ri (36 Cho)	= 2·44 miles.
	Cho (60 Ken)	= 119·3 yds.
	Ken (6 Shaku)	= 1·988 yds.
	Shaku	= 11·93 ins.
	Square ri	= 5·955 sq. miles.
	„ cho	= 2·45 acres.
	Tsubo	= 3·95 sq. yds.
India	Ungul	= ·75 in.
	Hath	= 18 in.
	Gaz	= 1 yd.
	Kos	= 2,000 yds.
	Bigah	= 1,600 sq. yds.
United States ...	Same measures used as in England.	

Appendix II.

THE ANEROID BAROMETER.

Aneroid Barometers.—For military work a 2½-inch barometer reading to 6,000 feet is a useful pattern.

In settled weather the aneroid barometer is often useful in sketching, especially on small scales where the contour intervals

are large. For instance, in sketching on a scale of 1 inch to 1 mile, where the intervals will be 50 feet, or on the ½-inch scale with intervals of 100 feet, the aneroid will be found most useful. The aneroid should not be used in unsettled weather when the atmospheric pressure is varying.

An aneroid used for field sketching should be provided with a movable scale of heights in feet. If starting from a point of which the height is known, the scale should be set to that height before beginning work, or else a plausible height should be assumed; the reading should also be taken on returning. If there is a difference, the intermediate altitudes should be corrected in proportion to the time which has elapsed.

An aneroid should always be read in the same position, either always held vertically on a level with the eye, or always horizontally, the latter is better. Severe tapping is not good for an aneroid barometer.

In changeable weather barometers are, of course, quite unreliable.

Diurnal variation of the barometer. This variation, which is not very large, depends on the place and time of year. On account of this variation it is desirable, if possible, to arrange for checks on the barometer readings—usually impossible, however, in field sketching.

Appendix III.

FINISHING UP SKETCHES FOR TACTICAL SCHEMES.

1. Sketches should be finished up with clearness and decision.

"Can I read this in a poor light?"

"Can the eye rapidly pick up any special information likely to be wanted?"

"Is information given so definitely that a draughtsman could trace it without hesitation as to what is intended?"—are types of useful reflection.

2. Written information takes the form of :—

(*a*) Reports.

(*b*) Marginal notes.

Instructions for writing reports have been given in Chapter XII.

Short statements about particular features of the ground are better given in margins with a reference number, thus :—(3) on the feature in question and in the margin opposite it. They must not obscure the sketch.

3. In making a statement, distinguish between facts known to yourself and alleged facts based on information received, *e.g.*, a marginal note about a river : " Fordable for infantry at (7)," would be wrong if not ascertained personally, and should be " Farmer Schmidt of (4) states fordable at (7)."

4. It is important that points on the sketch, such as cross roads and underfeatures, farms, &c., of tactical importance, should have a designation on the sketch. It may be necessary to refer to them in reports, orders, &c. If such have no ascertainable name, or if there is doubt about it, a good expedient is to supply them with a letter, thus :—(M).

5. Be very careful about correct spelling of names, especially so if other places of similar names are near. On Ordnance Survey 1-inch maps of Brighton district there are two hills, Itford and Iford, only 3 miles apart, and separated by the River Ouse. There are two Hill Barns $2\frac{1}{2}$ miles apart on the Ordnance Survey 1-inch map of Worthing.

6. The heading, printing, notes, and heights should be entered so that they can be read easily when the sketch is held so that the ground can be examined when looking towards the enemy.

Enlargements will usually be made with the N. at the top, and the direction of printing, &c., may have to be adjusted to the new direction required.

7. All sketches should contain :—

(*a*) A scale about 6 inches long. A statement as to the V.I. used.

(*b*) A North Point lettered "Magnetic." If the variation of the compass is known, plot the true North Point also.

(*c*) Clear signature of sketcher, with date.

(*d*) State of the weather.

(*e*) Heading stating the general purpose of the sketch. To obviate wrongful deductions being made by anyone using a copy for another purpose.

APPENDIX IV.

MUTUAL VISIBILITY OF POINTS.

Two quick methods of determining whether any point B is visible from any other point A are given below :—

Draw a line joining A and B. Note any points on that line which are likely to obstruct the line of sight between A and B, and carefully estimate their position and height.

Suppose there be such a point D whose height is 260 feet, and suppose the height of A is 300 feet and that of B 200 feet. Scale off on the plan the distance A,D, and also the distance A,B; and suppose AD = 1,200 yards, and AB = 2,700 yards.

Slope AD = a drop of 40 feet in 1,200 yards

$$= \frac{40}{1{,}200 \times 3} = \frac{1}{90}.$$

Slope AB = a drop of 100 feet in 2,700 yards

$$= \frac{100}{2{,}700 \times 3} = \frac{1}{81}.$$

That is, the slope AB is steeper than AD; therefore, the point D will obstruct the line of sight AB.

Suppose D has been found to be below the line of sight AB, but that there were several others points E, F, &c., which might obstruct

FIG. 21.



the line of sight, each could be tested in turn. In this case it might be quicker to proceed by the second method.

This latter is best shown by an example :—

FIG. 22.



The above plan represents a portion of a map contoured at 20′ vertical interval. The line AB represents the line of sight: divide AB into a number of equal parts corresponding to the number of vertical intervals between A and B, in the example six. Then the figures on the line AB show the heights of various points on the line of sight. Consider each contour in turn.

Where the 280 contour crosses the line of sight at *d*, the height of the line of sight is (about) 284 feet, and consequently passes above the ground. Similarly at *e*.

But at *c*, where the 240 feet contour crosses the line of sight, the height of the latter is 237 feet (about), hence the ground is

higher than the line of sight at and close to this point. Now, as this line of sight is an even slope from A to B, therefore the ground near prevents A and B from being mutually visible.

A section is added to explain the argument, but is unnecessary for working out the problem.

FIG. 23.



In the example given, A and B have each been assumed to be on a contour. If this is the case, the problem is more easily and quickly solved. But it is not essential and a similar reasoning applies if, say, A had been 304 feet and B had been 187 feet. It is only necessary to graduate the line of sight (preferably to correspond with the contours shown on the map, *i.e.*, in even 20's, 25's, &c., according to the V.I. of the map contours), and then to compare the heights of the various points on the line of sight with those on the ground.

Appendix V.

NOTES ON THE MAPS ISSUED BY THE GEOGRAPHICAL SECTION OF THE GENERAL STAFF FOR THE USE OF THE BRITISH EXPEDITIONARY FORCE ON THE CONTINENT.

The principal maps issued to the Expeditionary Force on the Continent are as follows :—

(1) Large scale or tactical maps :—

France.—$\frac{1}{80000}$, or about $1\frac{1}{4}$ miles to 1 inch.
Belgium.—$\frac{1}{100000}$, or 1·58 miles to 1 inch.
Germany.—$\frac{1}{100000}$, or 1·58 miles to 1 inch.

(2) A map on the $\frac{1}{250000}$ scale or 4 miles to 1 inch of all three countries.

In addition to these maps there is a general map, commonly known as the strategical map, of Belgium and north-east France, but this is only issued to the Staffs of Corps and Divisions. Maps on larger scales are also issued, as required, of special areas.

A description will now be given of the principal maps.

(3) $\frac{1}{80000}$ map of France (Plate 11). This map has been reproduced from the original French map. The original is in black only, but on certain sheets (number 2 to 24 on the Index, Plate 25) contours at 20 metres interval have been added. These contours must only be considered as approximately correct. The shape of the ground is, however, well shown by hachures, which vary in strength according to the height and steepness of the ground.

It is important to appreciate the significance of the hachures. The clearness of the map has necessarily suffered in the photographic reproduction of the original engraved map, and the general appearance of a sheet will sometimes appear confused. When a map is actually in use, however, the general appearance is not the important point. The few square miles of country which are actually

being traversed, or on which the operations affecting the individual using the map are being carried on, are all that matter. A careful examination of the map will usually reveal the nature of that country, and in all cases it is fully worth while to make such an examination.

The conventional signs and translations of the French terms used on the map are given in the reference at the foot of each map. They should be carefully studied. This map is not divided into squares with reference numbers and letters in the margin.

(4) $\frac{1}{100000}$ map of Belgium. This map has been prepared by the Geographical Section of the General Staff. Details and names are black, water blue, contours brown, woods green, and the main roads are coloured red. The shape of the ground is well shown by the contours, which are at 10-metre intervals, or about 33 feet. Numerous heights are also given in red, and it is important to remember that these heights are also in metres. The class of the roads is indicated by colour, and in most cases the information given is reliable. The condition of roads, however, varies from time to time. The state of the road depends on the weather, and the classification of the roads must not be taken for more than it is worth. It represents the best information available at the time the map was prepared.

One special feature of this map is that it gives the populations of towns and villages, according to the latest information at the time the map was being drawn, which may be anything from 5 to 8 years ago. Here, again, a careful study of the reference on each map is well worth while. The map has reference numbers and letters in the margin, which refer to the sections into which the map is divided by the lines of latitude and longitude drawn across it.

(5) The $\frac{1}{1000000}$ map of North-west Europe, including Belgium and parts of France, Holland, and Germany, is in the same general style as the $\frac{1}{100000}$ map of Belgium, but the symbols used for railways are different. The map requires but little explanation. Contours are at 50-metre, or about 164-feet interval, and heights are also given in metres. The rivers and their names are boldly depicted, which makes it easy to read the map quickly.

For the most part the country is so flat that the contours are not sufficiently close to give a clear indication of the shape of the ground. Sometimes there will be no contours between two rivers, and often there will be but one or two. Where there are none the

country is practically flat, and where there is even one the contour height or value will indicate the extent of the rise.

Most of the area covered by these four sheets is very thickly inhabited. Numerous scattered houses will be observed. Many more have of course been omitted, but the endeavour has been throughout to indicate the general character of the country.

The Ardennes begin in the East of Sheet 4, and continue throughout Sheet 5, and these areas have a different character to the rest of the map. They are thickly covered with forest, and the contours are here close enough together to show the shape of the ground.

The map is divided into 2-inch squares, which can be referred to by the letters and numbers in the margin. The length of the sides of the square is 2 inches, or almost exactly 8 miles.

(6) $\frac{1}{250000}$ map of France. Maps of other areas have been hurriedly prepared by copying the French map on the $\frac{1}{200000}$ scale and reducing it to the $\frac{1}{250000}$ scale A large area of France has been prepared in this style and also two sheets to the East of the area covered by the N.W. Europe series. These maps require but little explanation, but it should be observed that the contours are at 40-metre intervals as on the map from which they were copied. It was also found necessary to alter the usual contour colour, and to print them in a subdued tint, in order to avoid as far as possible any confusion between the contours and the single-line red roads.

The sheets of N.W. Europe and of the French series are numbered consecutively, and are shown in one index on the sheets of the French maps. It will be seen from the index that there is a considerable overlap between the sheets of N.W. Europe and the sheets to the East. A new sheet to be called 2^a is in preparation, and lies immediately North of sheet 6.

(7) Maps of Germany are, or will be, available on the $\frac{1}{100000}$ and $\frac{1}{250000}$ scales. A specimen of the German $\frac{1}{100000}$ is given in Plate 10. The $\frac{1}{250000}$ will resemble the sheets of N.W. Europe, except that the contours will be at 40-metre intervals.

(8) The Strategical map of Belgium and N.E. France is prepared on the layer system, the shape of the ground being indicated by tints which vary in depth according to the height. It is on a scale of $\frac{1}{380160}$, or 6 miles to one inch, and is a very clear general map.

(9) *General Notes.*

It is important to realize clearly the scale of the map in use. On the

$\frac{1}{80000}$	scale one inch represents			1·26	miles.
$\frac{1}{100000}$	,,	,,	,,	1·58	,,
$\frac{1}{250000}$	,,	,,	,,	3·95	,,

For practical purposes one inch may be taken to represent $1\frac{1}{4}$, $1\frac{1}{6}$, and 4 miles respectively on the three scales.

More information must not be expected from a map than the scale will show. On the $\frac{1}{80000}$ scale practically every road, name, and place of any importance can be shown. On the $\frac{1}{100000}$ scale the attempt to do this usually results in overcrowding the maps. On the $\frac{1}{250000}$, or $\frac{1}{4}$ inch scale, it is impossible to show every road, name, or place, and a selection must be made. The area of paper available on the $\frac{1}{80000}$ and $\frac{1}{100000}$ scales is greater than that on the $\frac{1}{250000}$ scale in the proportion of about ten to one and six to one respectively, and the area available on the $\frac{1}{80000}$ scale is to that on the $\frac{1}{100000}$ scale as ten to six. The advantage of the smaller scales is that one sheet covers a large area, and it is usually possible to carry one sheet of the $\frac{1}{250000}$ scale where often it would not be possible to carry the ten sheets of the $\frac{1}{80000}$ scale, which would be necessary to cover the same area.

It must never be forgotten that maps are never quite up-to-date. They take a long time to compile and draw, and alterations on the ground, such as new roads and railways, are continually being made. Many new railways have been made since the maps of Belgium were prepared. A new edition of the $\frac{1}{250000}$ map is being prepared which, it is hoped, will show all the railways.

(10) The incidence of Sheets 2 to 24 of the tactical maps of France on the scale of $\frac{1}{80000}$, and of Sheets 1 to 10 of the tactical maps of Belgium on the scale of $\frac{1}{100000}$, will be seen by reference to the index diagram (Plate 25). An index to the *names* on the sheets has been prepared, called "Index to maps of Belgium and N.E. France," G.S.G.S. No. 2731. This index shows the sheet and square where every name on these particular maps may be found. Before using the index book, which is only issued to the Staff, the general instructions at the beginning of the book should be carefully read.

A new Sheet 4 of Belgium is being prepared which is not shown on the diagram or included in the index to names.

(11) All maps published by the Geographical Section of the General Staff have a number by which they are known. The numbers of the maps which have been briefly described are as follows:—

France - - - - -	$\frac{1}{80000}$	G.S.G.S	No. 2526
Belgium - - - -	$\frac{1}{100000}$	,,	,, 2364
Germany - - - -	$\frac{1}{100000}$	,,	,, 2739
France - - - - -	$\frac{1}{250000}$	,,	,, 2738
N.W. Europe - - -	$\frac{1}{250000}$	,,	,, 2733
Germany - - - -	$\frac{1}{250000}$	,,	,, 2740
Belgium and N.E. France -	$\frac{1}{380160}$	,,	,, 2517

INDEX.

PAGE

A.

A.B. 152 and 153, use of ...26, 65
Abbreviations for piquet, support, and reserve, to be used in outpost sketches 19
Accommodation, billeting, lists showing 62
Administration, local, reference to in road reports 59
Advance, line of, how indicated by compass at night 31
" prolongation of the line of at night ... 32
Aneroid barometer, use of for fixing levels 54
" " uses of the 83
Angle, intersection, size of ... 45
" method of finding from compass bearing ... 30
Angles, reading and plotting, method of 33
Approaches, reference to, in report of a river reconnaissance 61
Artillery position, value of a panorama drawing as an adjunct to a report on a ... 75
Attack, reconnaissance of an enemy's position with a view to 63

B.

Barometer, aneroid, use of for fixing levels ... 54
" aneroid, uses of the 83
" diurnal, variation of the 84
Base line, selection of (plane-table sketch) 69
" method of measuring the (plane-table sketch) ... 69

PAGE

Bearing, method of quoting ... 42
Bearings, forward, how taken ... 54
" magnetic 36
" true 36
" " and magnetic conversion of ... 36
Billeting accommodation, lists showing 62
" reconnaissance, information required in report of a 62
Blank paper, sketching on ... 6
Block letters, use of 19
Board, cavalry sketching, use of 51, *et seq.*
Bridge, nature of, to be indicated 18
Bridges, reference to, in reports 59

C.

Canter, allowance of time for the 54
Carbon paper, substitute for ... 26
Cavalry sketching board, description of the 51
" sketching board, rules for sketching with, either mounted or dismounted 53
" sketching board, setting compass of the ... 51
" sketching board, use of 51, *et seq.*
" sketching board, use of for making a road report 55
" sketching board, use of for work on foot ... 55
Chalks, use of 79
Classification of military maps 7
Clinometer, use of (cavalry sketching board) 51
" use of for measuring slopes ... 54
Colours, conventional, the ... 19

	PAGE
Combined sketches, method of executing	29
Compass, bearings and not angles given by the ...	30
„ dial, how graduated ...	30
„ service, description of	29
„ setting a map with the	43
„ setting the (cavalry sketching board) ...	51
„ taking rays with the	49
„ use of as a hand compass... ...	31
„ „ as a prismatic compass ...	31
„ „ for making intersections and resections ...	50
„ „ for night marching ...	31
„ „ for resection ...	44
„ „ in map reading and marching 29, *et seq.*	
„ variation of, method of finding the ...	36
„ bearing, marching on at night ...31,	81
„ „ method of finding angles from... ...	30
Construction of scales without the assistance of a protractor 14, *et seq.*	
Contours, advantages of ...	22
„ disadvantage of ...	22
„ exercises for studying	25
„ explanation of ...	20
„ points to be noted with regard to	22
Conventional colours, the ...	19
„ signs, use of ...	17
Copying maps, methods of ...	25
„ value of, to beginners	75
Country, study of, maps an aid to and not a substitute for	41
Country, words describing, how written	19
Cross, Southern, use of for finding the true north	40
Cultivation, how shown ...	18
Cycling, measuring distances when	55

D.

	PAGE
Date, insertion of, on sketches...	80
Defensive reconnaissance, points to be noted in a	64
Definitions of technical terms 9, *et seq.*	
„ of topographical forms	8
Degrees, slope given in, rule for expressing as a gradient ...	25
Detail, use of the eye for fixing	74
Details, road	59
Dial, compass, how graduated...	30
Dismounted, rules for sketching when	53
Distances, measuring of, by time	54
„ measuring of, when cycling	55
„ use of pacing for measuring ...	49
Diurnal variation of the barometer	84
Drawing, panorama ... 74, *et seq.*	

E.

Engines, traction, slopes, practicable for	25
Enlargement of small scale map, adding extra information to...	55
Enlarging maps	6
„ „ methods of ...	26
„ small scale maps, best procedure for ...	56
Error, triangle of	71
Exaggeration, liability to in panorama drawings	79
Example of mutual visibility of points ... ..., ...	88

PAGE

Example of perspective ... 78
Examples of method of constructing a scale without the protractor ... 14, *et seq.*
„ of slopes 24
Exercises for studying contours 25
„ peace 57
Eye sketching 64
„ use of for fixing detail ... 74

F.

Facts, importance of stating in a reconnaissance report... 58
„ to be stated in notes on maps and not orders ... 57
Features, hill, method of representing... ... ... 20, 22
Field sketch, definition of ... 7
„ „ features to be shown on a ... 7
„ sketches, approved conventional signs for 17
„ „ size of scale for 12
„ „ use of 7
„ sketching, method of showing hill features in ... 22
Finishing sketches, notes on ... 84
Foot, use of cavalry sketching board for work on 55
Foreign measures 83
Form lines, how shown... ... 18
„ numbering of ... 57
„ use of 22
Forward bearings, how taken ... 54
French map (specimen) ... 42

G.

General principles of sketching 47, *et seq.*
German map (specimen) ... 42
Glasses, field, use of 75

PAGE

Gradients, reference to, in road reconnaissance report ... 59
Ground, comparison of large and small scale maps with the 47
„ formation of, method of showing on an enlargement of a small scale map 56
„ map reading on the ... 45
„ necessity for visiting not obviated by maps ... 41
„ study of the, prior to commencing a panorama drawing ... 75

H.

Heath and heather, how shown 18
Heights, how shown 18
Hill features, methods of representing 20
„ „ method of showing in field sketching 22
Horse, paces of the 54
Horseback sketch, use of ... 54

I.

Ice, thickness of which will support troops, &c. 60
Inch, to find the number of miles to a 12
Information, adding extra to enlargement of small scale maps, importance of ... 55
„ as to enemy's troops and works to be shown on a sketch 57
„ form of written ... 85
„ military, lack of in maps 41
„ omission of, from an enlargement of a small scale map 55
„ preparation of ... 57

PAGE

Information regarding rivers to be shown... ... 18
„ regarding woods to be supplied ... 18
„ required in a reconnaissance of an enemy's position with a view to attack 63
„ required in a road reconnaissance ... 58
„ tactical, required in a road reconnaissance ... 58
„ to be included in report of a billeting reconnaissance 62
„ to be included in report of a railway reconnaissance 61
„ topographical, adding to a map ... 6
„ type of to be included in a reconnaissance report... 58
Instruments, over use of by beginners ... 74
„ sketching 8
„ sketching without 65
Intersection, use of, for fixing points (plane-table sketch) ... 69

K.

Knolls, fixing the position of, on an enlargement of a small scale map 57

L.

Layer system, maps on the 20, 42
Length, measures of (metric system)... 82
Lettering, essential conditions for 19
Levels, spot 42
„ use of aneroid barometer *for fixing* 54
Line, base, selection of the (plane-table sketch) 69
Local administration, reference to in road reports 59
Luminous paint, use of for preparing compass for night marching 31

M.

Magnetic bearing, method of finding the ... 39
„ bearings 36
„ north, how shown on service prismatic compass 31
„ variation, finding the 36
Manual, division of this ... 8
Map, adding topographical to a 6
„ enlarging 6
„ French (specimen) ... 42
„ German(„) ... 42
„ information omitted when enlarging 55
„ making, principles underlying 47
„ methods of setting ... 43
„ military, points to be shown on a 7
„ reading, on the ground ... 45
„ „ procedure for ... 41
„ small scale, method of showing ground formation on an enlargement of 56
„ *reading, standard for proficiency in* 6, 41
„ to find one's position on a 43
„ when "set" 42
Maps an aid to the study of ground and not a substitute for 41
„ copying, methods of ... 25

PAGE

Maps, detail omitted from small scale maps 46
" lack of military information in 41
" large and small scale, comparison of with the ground 45
" large scale, use of ... 7
" limitations of 41
" methods of enlarging ... 26
" military, classification of 7
" military, use of protractor for measuring distances on 13
" not to be considered a complete substitute for examination of country itself 41
" notes on, to state facts and not orders 57
" rarely up-to-date ... 55
" small scale, adding extra information to enlargement of... 55
" small scale, best procedure for enlarging 56
" small scale, enlarging ... 55
" small scale, use of ... 7
" strategical, use of ... 7
" uncontoured, failings of... 42
Marching by the stars, instruction in 81
" on a compass bearing at night 31
Margin, use of for giving information 85
Marsh, how shown 18
Measure, unit of, the 12
Measures. foreign 83
Methods of finding one's position on a map 43
Memory sketching 64
Metric system, countries in which used 82
" system, the 82
Miles, number of to an inch, to find 12
Military map, points to be shown on a 7

PAGE

Military sketch, essentials of ... 47
Minutes, scale of... 54
Models, use of for illustrating contours 20
Mounted, rules for sketching when 53
Mutual visibility of points 86, *et seq.*

N.

Names, correct spelling of to be observed 85
" of foreign towns, &c., spelling of 58
Naming points on a sketch ... 85
Night, line of advance by, indication of on the compass 31
" marching on a compass bearing at 81
" moonlight, use of a luminous compass on a ... 31
" prolongation of the line of advance at 32
" march, method of selecting a star as a bearing for 81
" marching, necessity for record of distances traversed in finding the line of advance ... 32
" work, use of compass for 30
Noon, position of the sun at ... 40
North, magnetic, how marked on service prismatic compass 31
" true, approximate methods of finding the ... 40
" " use of a watch for finding the ... 40
Notes, method of inserting in a sketch 85
" on maps to state facts and not orders 57

O.

Observation points, reference to in road reports 59
Obstacles, insertion of in panorama drawings 79

	PAGE
Officers, regimental, subjects in which to be proficient	5
„ selected, special instruction of	5, 8
Orders not to be contained in notes on maps	57
Ordnance Survey maps, conventional signs on...	17
Outpost sketches, abbreviations used in	19

P.

Pace, even, necessity for practice in maintaining an ...	54, *footnote*
Paces of the horse	54
Pacing, use of for measuring distances	49
Paint, luminous, use of	31
Panorama drawing ...	74, *et seq.*
„ „ details to be included in	79
„ „ points to be observed in executing a	76, *et seq.*
„ „ use of shading in a ...	75
„ „ value of, as an *adjust to a* report on an artillery position ...	75
„ execution of in sections	76
Patrol, method of showing in outpost sketches	19
Perspective, example of ...	78
„ rules regarding ...	77
Piquet, abbreviation for in outpost sketches	19
Plane-table, description of the	6
„ general maxims to be observed in mounting a ...	68
„ mounting a ...	67
Plane-table sketch, rules to be observed in executing a ...	69
„ sketching ...	67, *et seq.*
„ traversing... ...	74
Plotting angles, method of ...	33
„ resection, method of ...	44
Points, mutual visibility of ...	47
„ „ „ „ methods of determining	86
„ ruling, use of in map-*making*	40
Pole star, true bearing of the ...	48
Position, enemy's, reconnaissance of, with a view to attack	63
„ fixing by resection ...	45
„ on a map, to find ...	43
Positions of troops and works, when shown on a sketch ...	57
Primaries, use of...	13
Printing company, R.E., capabilities of a	29
Printing, &c., direction of, on a sketch	85
Protractor, constructing scales without the use of a	14
„ scale of miles shown on the	33
„ scale of yards shown on the	33
„ service, description of the...	33
„ use of, for drawing scales	13
„ use of, for plotting and reading angles	33
„ use of, for reading bearings on a map or sketch	36
„ use of, to measure distances on military maps... ...	13

Q.

Quays, information regarding to be included in a river reconnaissance report	61

PAGE

R.

Railway, how shown 18
„ reconnaissance, information to be included in report of a 61
Rapidity, value of in producing work 74
Ray, method of drawing when using a plane table 68
Rays, method of taking... ... 49
Reading angles, method of ... 33
Reconnaissance, billeting, information required in report of a ... 68
„ defensive ... 64
„ of an enemy's position with a view to attack ... 63
„ railway, information to be included in report of a ... 61
„ report, information to be included in a 58
„ river, information required in a 60
„ road, information required in a 58
„ sketches, size of scale for ... 12
R.F., definition of 12
Regimental officers, subjects in which to be proficient ... 5
Report, reconnaissance, importance of distinguishing between facts and hearsay in a 58
„ reconnaissance, information to be included in a 58
„ road, use of cavalry sketching board for making a 55

PAGE

Report, written, value of a rough sketch in addition to 6
Resection from three points (plane-table sketch) 70, *et seq.*
„ from two points (plane-table sketch) 73
„ method of (plane-table sketch) ... 70
„ method of plotting ... 44
„ process of 44
„ use of for filling in detail (plane-table sketch) 70
„ use of prismatic compass for 44
Reserve, abbreviation for, in outpost sketches 19
River, information regarding, to be added to a sketch 18
„ method of drawing a ... 18
„ reconnaissance, information required in ... 60
„ velocity of a, method of finding the 60
R.M.A., use of the manual for cadets of the 5
R.M.C., use of the manual for cadets of the 5
Road, curves and bends of, as shown on small scale maps 46
„ details 59
„ method of drawing ... 17
„ particulars of to be noted 17
„ reconnaissance, information required in a ... 58
„ report, use of cavalry sketching board for making a 55
Rule for expressing as a gradient a slope given in degrees ... 25
Rules for sketching, mounted or dismounted, with the cavalry sketching board 53
Rules regarding perspective ... 77

PAGE

S.

Scale, example of a 13
" method of expressing a ... 12
" of miles shown on the protractor 33
" of minutes, method of drawing 54
" of yards shown on the protractor 33
" primary divisons of a ... 13
" secondary divisions of a... 13
Scales ... ... 11, *et seq.*
" construction of without the aid of the protractor ... ... 14, *et seq.*
" length of 12
" use of protractor for drawing 13
Section drawing, use of for instruction 23
Sections, execution of a panorama drawing in 76
Service compass, description of the 29
Shading, use of in a panorama drawing 75
Sight rule, description of the ... 67
Signs, conventional, use of ... 17
Sketch, field, features to be shown on a 7
" horseback, use of ... 54
" improvisation of names to identify points on a 85
" information as to enemy's troops and works to be shown on a 57
" military, essentials of ... 47
" plane-table, rules to be observed in executing a 69
" reconnaissance, scale for 12
" rough, value of as addition to a written report... 6
" telescopic, method of producing a 80
Sketches, combined, method of executing 29

PAGE

Sketches, execution of without instruments ... 65
" field approved conventional signs for ... 17
" field, scale for ... 12
" " use of 7
" finishing up for tactical schemes 84
" notes on finishing up 64
" outpost, abbreviations used in 19
" points to be contained in all 85
Sketching board, cavalry, use of 51, *et seq.*
" eye and memory ... 64
" field, method of showing hill features in 22
" general principles of 47, *et seq.*
" instruments carried for 8
" on blank paper ... 6
" on blank paper, regimental officers to be instructed in ... 5
" plane-table ... 67, *et seq.*
Slope given in degrees, rule for expressing as a gradient ... 25
Slopes, method of expressing ... 24
" practicable for traction engines 25
" practicable for wheeled vehicles 25
" uniform, convex and concave, examples of ... 24
" use of clinometer for measuring 54
Small scale maps, enlargement of 55
Southern Cross, use of for finding the true north 40
Spelling of names of foreign towns, &c. 58
Spot levels 42
Square measures (metric system) 82
Squares, use of for enlarging maps 26
Star, method of selecting as a bearing for a night march 81

	PAGE
Star, pole, true bearing of the...	40
Stars, instruction in marching by the	81
Sun, position of at noon ...	40
Supplies, reference to in reports	59
Support, abbreviation for in outpost sketches	19

T.

Tactical information required in a road reconnaissance	58
„ schemes, finishing up sketches for	84
Tracing cloth, use of	26
Technical terms, definitions of	9, *et seq.*
Telescope, field, use of	75
Telescopic sketch, method of producing a	80
Time allowance of, for the canter	54
„ „ for the trot...	54
„ „ for the walk (mounted)	54
„ measuring distances by ...	54
Topographical forms, definitions of	8
„ information, addition of to a map	6
Traversing, plane-table... ...	74
„ use of in map-making	50
„ when used (plane-table sketch) ...	74
Triangle, error of	71
Triangulation, use of in map-making...	48
Trough-compass, the	67
Troops, method of showing ...	19
Trot, allowance of time for the	54
True bearing, examples of finding the... ...	36
„ only to be quoted	42
True bearings	36
True north, approximate, methods of finding the	40
Turnings, reference to in road reports	59

V.

Variation of compass, method of finding the	36
Vehicles, reference to in report of a billeting reconnaissance	62
„ wheeled, slopes practicable for	25
Velocity of a river, method of determining the	60
View, choice of a point of, before commencing a panorama drawing	75
Visibility of points, example of mutual	88
„ of points, mutual, methods of determining	86

W.

Walk, allowance of time for (mounted)	54
Watch, use of, for finding the true north	40
Weather, state of, to be recorded on panorama drawings ...	80
Whistle, use of at night in connection with the prolongation of the line of advance... ...	32
Woods, information regarding, to be noted	18

Z.

Zero of a scale where placed ...	13

NOTE.

Plates 5, 6, 7, 8, *and* 12, *of the* 1912 *Edition have not been included in this issue. Plates* 22, 23, 24, *and* 25 *have been added.*

CANADA.

Ordnance Survey Office, Southampton

Scale $\frac{1}{126,720}$ or 1 Inch to 2 Miles

Miles 1 ½ 0 1 2 3 4 5 Miles

Contour interval 25 Feet

GERMANY.



Ordnance Survey Office, Southampton

Scale 1/100,000 1·58 Miles to 1 inch

Mile 1 ¾ ½ ¼ 0 1 2 3 Miles

FRANCE



Ordnance Survey Office, Southampton

Scale $\frac{1}{50,000}$ 1·26 Miles to 1 inch

Miles 1 ¾ ½ ¼ 0 1 2 Miles

CONVENTIONAL METHODS OF SHEWING OBJECTS IN NATURE

Plate 17.

Trees

Buildings

Villages

Woods



Roads & Railways



Fences & Hedges



Cuttings & Embankments

H & C GRAHAM LTD. LITH PRS. LONDON, S.E.

First view of Fox Hills from FRIMLEY GREEN-ASH road.
Looking S.E. from a point E. of road opposite Anglers Rest P.H


Basingstoke Canal & L.S.W. Ry (Ascot branch) in cutting here.
Firwood
Fox Hills open heather 1300 yards
Embankment
To North Camp Stn L.S.W. Ry
Station about here: road under railway.

H & C GRAHAM LTD. LITHRS LONDON S.E.

PANORAMA FOR USE FROM AN ARTILLERY POSITION.

PLATE 19.



H & C. GRAHAM, LTD. LITHO. LONDON, S.E.

RANGE TAKERS CARD

From Position P.

PLATE 19.



LATERAL ANGLES

TO E	3°	30′	TO F	4°	
D	4°	20′	G	7°	30′
C	6°	40′	H	10°	30′
B	7°	40′	I	11°	30′
A	11°		J	13°	15′

H & C GRAHAM, LTD., LITHRS., LONDON S.

CHITRAL EXPEDITION

Plate 20.

Reconnaissance Sketch of Enemy's Position at

NISA GOL

12th April 1895

Showing position of British Troops and points of passage of the Gol during attack on enemy's position on 13th April, 1905.



H & C. GRAHAM LTD. LITHOS, LONDON, S.E.

Plate 21.

BATTLE OF LIAO-YANG

SCENE OF TURNING MOVEMENT BY THE 12TH AND 2ND JAPANESE DIVISIONS NORTH OF THE TAI-TZU HO.


Russian Howitzers (3) which enfiladed MANJU-YAMA on 2.9.04.
KUAN-TUN
Russian Infantry retiring followed by shrapnel 1.2 pm. 2.9.04.
Knoll captured by 4th Regt 2.9.04. but from which they were driven off with loss
HAI KUAN-TUN
HSIA-PU-TUN (behind hill)
HUANG-KU-PEN 1st Qrs 2nd D. 3.9.04. Russian batteries 1904.
HEI-YING-TAI
MANJU-YAMA (Rice cake Hill) captured by the 5th Bde (Akasaki) night of 1.9.04. Attacked 5 times during night of 2.9.04 by Russians but not retaken.
HOU HEI-YING-TAI
WU-HSIEN SHAN (5 Head Hill) taken by 12th Div. 1.9.04.
Russian battery 1 & 2. 9.04.
Japanese mountain battery 2.9.04. silenced the Russian guns by indirect Fire.
SSU-HSIEN SHAN (4 Head Hill) coal mines
J. advance
N
Russian Artʸ mistook this ridge for the ridge the guns were on. Their shells went over all day, only 1 killed, 5 wounded in Japanese Artʸ
Japanese
Russians
1st Pontoon bridge 160 yards long by which the 12th & 2nd Divisions crossed the Tai-tzu Ho on 31st August 1904. The bridge was concealed from the Russians by "Swallows nest Hill" First Army Hd Qrs spent the night of 31/8-1/9 in this village.

1771. H. & C. GRAHAM LTD. LITHRS, LONDON, S.E.

TRAINING MAP.



Scale of Two Miles to One Inch REDUCED.

2 1½ 1 ½ 0 2 4 Miles

Contour interval 100 Feet

NOTE.—This map is printed from the Outline, Water, and Contour plates only of the Normal Edition.

NORTH WEST EUROPE

1:250,000

War Office 1914

Scale $\frac{1}{250,000}$ 3·95 Miles to 1 Inch

Miles 1 0 1 2 3 4 5 6 7 8 9 10 *Miles*

BELGIUM

1:100,000



War Office, 1914.

Scale $\frac{1}{100,000}$ 1·58 Miles to 1 Inch

Miles 1 — 0 — 1 — 2 — 3 *Miles*


Index to maps of
BELGIUM & NORTH-EAST FRANCE
LONDON
ROTTERDAM
ANTWERP 3
GHENT 2
OSTEND
DUNKERQUE 2
Straits of Dover
BOULOGNE 3
ST. OMER 4
TOURNAI 5
BRUSSELS 6
LIEGE 7
COLOGNE
MONTREUIL 6
ARRAS 7
LILLE 8
MONS 7
NAMUR 8
MARCHE 9
ABBEVILLE 11
AMIENS 12
CAMBRAI 13
ROCROI 14
ARLON 10
YVETOT 19
HAVRE
NEUFCHÂTEL 20
MONTDIDIER 21
LAON 22
RETHEL 23
MEZIERES 24
LUXEMBURG
52°
51°
50°
49°
0°
1°
2°
3°
4°
5°
6°
7°
Extent of sheets of
Strategical 1/80,160
France 1/80,000
Belgium 1/100,000
War Office, Oct. 1914.

Plate 25

(As to prices in brackets, see top of page 2.)

KIT PLATES:—
Artillery. Royal—
1. Horse and Field. Kit in Barrack Room. 1912. 2*d*. (2*d*.)
2. Ditto. Kit laid out for Inspection. 1903. 2*d*. (2*d*.) (*Under revision*)
6. Garrison. Kit laid out for Inspection. 1909. 2*d*. (2*d*.)
10. Ditto. Kit in Barrack Room. 1909. 2*d*. (2*d*.)

Cavalry. 1891. 1*d*. (1*d*.)
Engineers. Royal—
1. Dismounted. Detail of Shelf and Bedding, with Marching Order ready to put on. Detail of Shelf and Bedding, with Drill Order ready to put on. 1914. 1*d*. (1*d*.)
2. Dismounted. Full Kit laid out for Inspection in Barrack Room. 1914. 1*d*. (1*d*.)
4. Mounted N.C.O. or Driver and Field Troop Sapper. Full Kit laid out for Inspection in Barrack Room. 1910. 1*d*. (1*d*.)
5. Mounted. Detail of Shelf and Bedding. 1910. 1*d*. (1*d*.)
6. Driver, with pair of Horses. Field Kit laid out for Inspection on Parade, including Articles carried in Valise on Baggage Wagon. 1899. 1*d*. (1*d*.)

Infantry—
1. Kit in Barrack Room. 1905. 2*d*. (2*d*.)
2. Kit laid out for inspection. 1905. 2*d*. (2*d*.)

Highland. 1884. 1*d*. (1*d*.)
Medical Corps. Royal Army. Kit in Barrack Room. 1912. 2*d*. (2*d*.)
Ordnance Corps. Army. For guidance at Marching Order and Kit Inspections. 2*d*. (2*d*.)

LAND WARFARE. An Exposition of the Laws and Usages of War on Land, for the guidance of Officers of H.M. Army. 1912. 1*s*. (10*d*.)

LARGE FORMATIONS. The Operations of. Translated from the German. (*In the press*)

LAW. Military. Manual of. 1914. 2*s*. (1*s*. 9*d*.)

LAW FOR THE RESERVE FORCES AND MILITIA. Manual of 1886. 1*s*. 6*d*. (1*s*. 2*d*.)

MACHINE-GUN. Tests of Elementary Training. 1*d*. (1*d*.)

MACHINE GUNS AND SMALL ARMS, 303-inch. Nomenclature of Parts, Stripping, Assembling, Action, Jams, Misfires, Failures, and Inspection of. Revised Edition. 1913. 3*d*. (3*d*.); Amendments, No. 1. 1*d*. (1*d*.)

MAGAZINES AND CARE OF WAR MATÉRIEL. Regulations for. 1913. 9*d*. (9*d*.); Amendments, July 1914. 1*d*. (1*d*.)

MAP READING AND FIELD SKETCHING. Manual. 1912. 1*s*. (11*d*.) (*And see* Schools, Army.) (*Reprinting*)

MECHANISM AS APPLIED TO ARTILLERY. Notes on. Second edition. 1902. 1*s*. (11*d*.)

MEDICAL CORPS. Royal Army:—
Admission to. Regulations for. Jan. 1912. 1*d*. (1*d*.)
Standing Orders. 1914. 1*s*. (10*d*.)
Training. 1911. 9*d*. (9*d*.)

MEDICAL DEPARTMENT. Army. Index to Appendices of Reports from 1859 to 1896. 3*d*. (3*d*.)

MEDICAL SERVICE. Army. Regulations. 1906. (Reprinted, with Amendments, 1914.) (*In the press*)

MEDICAL SERVICE. Strategical and Tactical Employment of the, as carried out in an Army Corps; with a series of Problems. Translated from the Austrian. 4*s*. 6*d*. (3*s*. 4*d*.)

MEDICAL SERVICES. Army. Advisory Board for. The Treatment of Venereal Disease and Scabies. First Report. 1904. 1*s.* 6*d.* (1*s.* 3*d.*); Second Report. 1905. 2*s.* (1*s.* 6*d*); Third Report. 1905. 1*s.* (10*d.*); Final Report. 1906. 6*d.* (5*d.*)

MEDICAL SERVICES OF FOREIGN ARMIES. Handbook of. Part I. FRANCE. 6*d.* (5*d.*) (*Under revision*); Part II. GERMANY. 6*d.* (5*d.*); Part III. AUSTRIA HUNGARY. 6*d.* (5*d.*); Part IV. RUSSIA. 6*d.* (5*d.*); Part V. ITALY. 6*d.* (5*d.*); Part VI. THE NETHERLANDS AND BELGIUM. 1911. 6*d.* (5*d.*)

MEKOMETER Handbook. 1911. 6*d.* (6*d.*)

MOBILIZATION Regulations. 1912. 6*d.* (6*d.*)
Ditto. Amendments, July 1913. 1*d.* (1*d.*)

MUSKETRY REGULATIONS:—
Part I. 1909. (Reprinted, with Amendments, 1914). 6*d.* (7*d.*)
Part II. Rifle Ranges and Musketry Appliances. 1910. (Reprinted, with Amendments, 1914.) 4*d.* (4*d.*) (*In the press*)

NIGHT OPERATIONS. Elementary Training in. 1911. 1*d.* (1*d.*)

NUMBER OF TROOPS TO THE YARD in the Principal Battles since 1850. Memo. on. With opinions of Modern Authorities on limits of extension at the present day. 1884. 9*d.* (7*d.*)

NURSING IN THE ARMY. Queen Alexandra's Imperial Military Nursing Service. Reprinted from "The British Medical Journal." 1905. 1*d.* (1*d.*)

NURSING SERVICE. Queen Alexandra's Imperial Military. Regulations for Admission to the. 1914. 1*d.* (1*d.*)

OFFICERS TRAINING CORPS:—
Regulations. 1912. 2*d.* (2*d.*) (*Under revision*)
Ditto. Appendix III. (*In the press*)
Ditto. (Inns of Court). 1*d.* (1*d.*) (*Under revision*)
Special A.O., March 16, 1908. 1*d.* (1*d.*)
Junior Division. Instruction for the Annual Camps. 1913. 2*d.* (2*d.*)

OPERATION ORDERS. A Technical Study by Hans von Kiesling. Translated from the German. 1*s.* 6*d.* (1*s.* 3*d.*)

OPTICAL MANUAL or Handbook of Instructions for the guidance of Surgeons. Third edition. 1885. 1*s.* 6*d.* (1*s.* 5*d.*)

OPTICS. Notes on. 6*d.* (5*d.*)

ORANGE FREE STATE. Topographical Survey of the, 1905–1911. Report on the. 10*s.* (7*s.*)

ORDNANCE COLLEGE (*and see* Artillery College):—
Advanced Classes. Reports on (up to the 33rd). Each 1*s.* (9*d.*)
Ditto. 34th. 6*d.* (5*d.*)
Dynamics. Notes on. Second edition. 3*s.* (2*s.* 5*s.*)
Officers' Mess (Royal Artillery) Management and First Principles of Book-keeping. 3*d.* (3*d.*)
Ordnance Courses. Reports on. Various. Each 1*s.* (9*d.*)
Regulations. 1907. 2*d.* (2*d.*)

ORDNANCE CORPS. Army. Standing Orders. 1912. 6*d.* (6*d.*)

ORDNANCE MANUAL (WAR). 1914. 6*d.* (5*d.*)

ORDNANCE SERVICE. Treatise on. Seventh edition. 1908. With volume of plates. 7*s.* 6*d.* (5*s.* 6*d.*); Amendments. June 1909, Dec. 1910, Dec. 1912. Each 1*d.* (1*d.*); Ditto. Dec. 1909, Dec. 1911. Each 2*d.* (2*d.*)

ORDNANCE SERVICES. ARMY. Regulations. Part I. 1912. (Reprinted, with Amendments, 1914.) (*In the press*); Part II. 1914. 1*s.* (*In the press*)

PATHOLOGICAL SPECIMENS in the Museum of the Army Medical Department, Netley. Descriptive Catalogue of. Third edition. Vol. I. By Sir W. Aitken, M.D. 1892. 5*s.* (3*s.* 8*d.*)

(As to prices in brackets, see top of page 2.)

PAY DUTIES of Officers Commanding Squadrons, Batteries, Companies, &c. *Instructions.* 1914. 1*d.* (1*d.*)

PHYSICAL TRAINING. Manual of. 1*s.* (11*d.*)
Ditto. Amendments, July 1913. 1*d.* (1*d.*)

PLACE-NAMES OCCURRING ON FOREIGN MAPS. Rules for the Transliteration of. 1906. 1*s.* (9*d.*)

PORTABLE SUB-TARGET (Mark I.), and How to Use it. 1911. (Reprinted, with Amendments, 1914.) 1*d.* (1*d.*) (*In the press*)

POSTAL SERVICES. ARMY. WAR. Manual of. 1913. 3*d.* (3*d.*)

PROJECTION, &c. Linear Perspective. A Text-Book for use of the R.M. Academy. Part I.—Text. Part II.—Plates. 1904. 6*s.* (4*s.* 5*d.*)

PUBLICATIONS (RECENT) OF MILITARY INTEREST. List of, Quarterly. Nos. 1 to 8. 2*d.* (2*d.*) *each*; *Nos.* 9 *to* 17. 4*d.* (4*d.*) each. (*Continued by* THE ARMY REVIEW).

RAILWAY DISTANCES. Ireland. Handbook of. Third edition. 1884. 7*s.* 6*d.* (5*s.* 3*d.*)

RAILWAY MANUAL (WAR). 6*d.* (5*d.*)

RAILWAYS. MILITARY. RECONNAISSANCE AND SURVEY OF. Notes on, for Officers of R.E. Railway Companies. 1910. 2*s.* 3*d.* (1*s.* 8*d.*)

RANGE-FINDER. Handbooks:—
Infantry, No. 1. (Marindin). 1913. 3*d.* (3*d.*)
Infantry No. 2. (Barr and Stroud). 31·5-inches base. 1913. 1*s.* (10*d.*)
Watkin. *Regulations for instruction in, and practice with.* 1882. 1*s.* (9*d.*)

RANGE FINDING. COAST DEFENCE. Manual of. Part I. 9*d.* (8*d.*)
Ditto. Amendments, June 30, 1914. 1*d.* (1*d.*)

RANGES, MINIATURE CARTRIDGE. (*Reprinted from* THE ARMY REVIEW, January 1914). 3*d.* (3*d.*)

RECRUITING FOR THE REGULAR ARMY AND THE SPECIAL RESERVE. Regulations. 1912. [Re-printed, with Amendments to Aug. 1914.] 3*d.* (3*d.*)

REMOUNT MANUAL (WAR). 1913. 2*d.* (2*d.*)

REMOUNT REGULATIONS. 1913. 3*d.* (3*d.*)

REQUISITIONING OF SUPPLIES, TRANSPORT, STORES, ANIMALS, LABOUR, &c., IN THE FIELD. Instructions for the. 1907. 1*d.* (1*d.*)

RESERVE (*and see* Motor Reserve; Special Reserve):—
Army Reserve. Class I. Regulations. 1911. 1*d.* (1*d.*
Ditto. Amendments, June 1913. 1*d.* (1*d.*)
National Reserve. Regulations. 1913. 1*d.* (1*d.*)

RIFLE RANGES. Care and Construction of. Instructions for. 1908. 3*d.* (3*d.*)

RIFLE RANGES, TRAINING GROUND, AND MUSKETRY CAMP, PENALLY. (Western Coast Defences). Standing Orders. 1910. 2*d.* (2*d.*)

RIFLES, &c. Cleaning of. Notes on the. 1911. 25 for 6*d.* (7*d.*)

RIFLES, SHORT AND CHARGER-LOADING, MAGAZINE, LEE-ENFIELD. Handbook for Serjeant-Instructors of Special Reserve, Officers Training Corps, and Territorial Force in regard to the Care, Inspection, &c., of. 3*d.* (3*d.*)

RUSSIAN MILITARY AND NAVAL TERMS. Dictionary of 1906. 3*s.* 6*d.* (2*s.* 6*d.*)

(As to prices in brackets, see top of page 2.)

RUSSO-JAPANESE WAR:—

Medical and Sanitary Reports from Officers attached to the Japanese and Russian Forces in the Field. 1908. 5*s.* (3*s.* 10*d.*)

Official History. Part I. Causes of the War. Opening Events up to and including the Battle of the Ya-lu. Second edition. 1909. 1*s.* 6*d.* (1*s.* 3*d.*); Part II. From the Battle of the Ya-lu to Liao-yang, exclusive. 1908. 5*s.* (3*s.* 8*d.*); Part III. The Siege of Port Arthur. 1909. 4*s.* 6*d.* (3*s.* 4*d.*); Part IV. Liao-yarg. 1910. 4*s.* (3*s.*); Part V Sha Ho. 1911. 4*s.* 6*d.* (3*s.* 5*d.*)

Official History (Naval and Military). Vol. I. To August 24, 1904. With case of Maps. 1910. 15*s.* (10*s.* 7*d.*); Vol. II. Liao-yang, the Sha-ho, Port Arthur. With case of Maps. 1912. 15*s.* (10*s.* 10*d.*)

Reports from British Officers attached to the Japanese and Russian Forces in the Field. In three vols., with two cases of Maps (*not sold separately*). 21*s.* (15*s.*)

SALISBURY PLAIN. SOUTHERN COMMAND. Standing Orders applicable to all Troops Encamped on Salisbury Plain, and applicable generally to Troops Quartered at Bulford and Tidworth. 1913. 3*d.* (3*d.*)

"SAM-BROWNE" BELT, SCABBARD, AND SWORD KNOT. Specification and Drawings. 1899. 1*d.* (1*d.*)

SCHOOLS. Army:—

Annual Reports on. 1911–12; 1912–13. Each 1*s.* (9*d.*)

Map Reading. Notes on. 1912. 3*d.* (3*d.*); Amendments. 1*d.* (1*d.*) (*And see* Map Reading and Field Sketching.)

Military and other Terms, and Words which Occur in Orders. Lists of. 1914. 2*d.* (2*d.*)

Physiology. Elementary. Handbook. 1901. 1*d.* (1*d.*)

Regulations. 1911. 4*d.* (4*d.*)

School Hygiene. Handbook of. For Teachers. 6*d.* (6*d.*)

Singing in. Regns. for Teaching. 1911. 1*d.* (1*d.*)

Standing Orders for Inspectors, Examiners, and Teachers. 1910. 6*d.* (5*d.*)

Type Exercises of Extracts from Regimental Orders for the use of Candidates for Third-class Certificates of Education. 1912. 3*d.* (3*d.*)

SCOUTS. Training and Use of. Lecture by Col. F. C. Carter. 1905. 2*d.* (2*d.*)

SCREWS. Standard Leading. Provision of, for Screw-cutting Lathes. Report of Committee. 1905. 1*s.* (10*d.*)

SEVASTOPOL. Siege of. 1854–55. 3 vols., with Case of Maps and Plans. Half Mor., £5 4*s.* Cloth, £4 4*s.*

Or separately:—Vol. I. Engineer Operations. £1 6*s.*; Vol. II. Ditto. With Case of Maps and Plans. £2 10*s.*; Vol. III. Artillery Operations. 10*s.*

SEWAGE. Practical Treatment of. The latest development of. 1903. 6*d.* (5*d.*)

SHOEBURYNESS GARRISON. Standing Orders. 1913. 1*s.* 6*d.* (1*s.* 1*d.*)

SIEGE OPERATIONS in the Campaign against France, 1870–71. (*Von Tiedemann.*) Translated. 4*s.* 6*d.* (3*s.* 3*d.*)

SIGNALLING. Training Manual. 1907. [Reprinted, with Amendments to May 1, 1911.] 6*d.* (6*d.*); Amendments. Nov. 1912, May 1913, April 1914. Each 1*d.* (1*d.*); Appendix IV. Despatch Riding. 1*d.* (1*d.*)

SIGNALLING. Training Manual. Part II. 1914. 6*d.* (6*d.*)

SIGNALLING DISC. Directions for Use. 1911. 1*d.* (1*d.*)

SIGNAL SERVICE. THE ARMY. 1*d.* (1*d.*)

SIGNAL SERVICE. ARMY. Manual of—WAR. Provisional. 1914. 2*d.* (2*d.*)

SMALL ARMS Text Book. 1909. With Tables. 2*s.* 6*d.* (2*s.* 1*d.*)

SMALL WARS. Their Principles and Practice. Third Edition. 1906. (*Reprinted* 1909.) 4*s.* (3*s.*)

(As to prices in brackets, see top of page 2.)

SOMALILAND. Military Report on. 1907. Vol. I. Geographical, Descriptive, and Historical. 2*s.* (1*s.* 7*d.*)

Ditto. Operations in, 1901-04. Official History. Vol. I. 3*s.* (2*s.* 4*d.*); Vol. II. 4*s.* (3*s.*)

SOUTH AFRICAN WAR, 1899-1902:—

Medical Arrangements. 7*s.* 6*d.* (5*s.* 6*d.*)

Medical History. An Epidemiological Essay. [Reprinted from "The Journal of the Royal Army Medical Corps."] 3*s.* 9*d.* (2*s.* 9*d.*)

Railways. 4*s.* (3*s.*)

Surgical Cases Noted. 7*s.* 6*d.* (5*s.* 6*d.*)

Telegraph Operations. 10*s.* (7*s.* 1*d.*)

Voluntary Organizations in aid of the Sick and Wounded. Report of the Central British Red Cross Committee on. 1902. 3*s.* (2*s.* 5*d.*)

SPECIAL RESERVE:—

Commission in the Special Reserve of Officers. Short Guide to obtaining a; &c. 1*d.* (1*d.*) (*Under revision*)

Officers. Instructions relating to First Appointment, Training, &c. June 1908. 1*d.* (1*d.*)

Regulations for Officers of the Special Reserve of Officers, and for the Special Reserve. 1911. 4*d.* (5*d.*)

Scheme for the Provision, Organization, and Training of the Special Reserve required to supplement the Regular Army, and the Application of the Scheme to the existing Militia. (Special A.O., Dec. 23, 1907.) 2*d.* (2*d.*)

Scheme for the Provision, Organization, and Training of that portion which will be drawn from the Territorial Force to supplement the Regular Army on Mobilization being ordered. (Special A.O., Nov. 20, 1908.) 2*d.* (2*d.*)

STAFF COLLEGE Regulations (Camberley). 1905. Reprinted with Amendments up to Nov. 30, 1910. 1*d.* (1*d.*)

STAFF. General. Duties of. (*Von Schellendorff.*) Fourth Edition. 1905. (*Out of print*)

STATIONS OF UNITS OF THE REGULAR FORCES, MILITIA, *SPECIAL RESERVE, AND TERRITORIAL FORCE.* Quarterly. 2*d.* (2*d.*)

STATUTES relating to the War Office and to the Army. 1880. 5*s.* (3*s.* 9*d.*)

STATUTORY POWERS of the Secretary of State, Ordnance Branch. 1879. 5*s.* (3*s.* 9*d.*)

STEAM ENGINES AND BOILERS AND GAS AND OIL ENGINES. Management of. Notes and Memoranda. 1911. 1*d.* (1*d.*)

SUDAN ALMANAC. 1914. Compiled in the Intelligence Department. Cairo. 1*s.* (9*d.*) (*Under revision*)

SUDAN. BRITISH FORCE IN THE. Standing Orders. 1914. 9*d.* (7*d.*)

SUDAN. The Anglo-Egyptian. A Compendium prepared by Officers of the Sudan Government:—

Vol. I. Geographical, Descriptive, and Historical (*with Eighty-two Illustrations*). 10*s.* (7*s.* 4*d.*)

Vol. II. Routes. 7*s.* 6*d.* (5*s.* 5*d.*) (*Not containing Chapter VII., Supplement (A).*)

Ditto. In Separate Chapters. 1*s.* (10*d.*) each:—

I. and II., *Nil.* III. North-Eastern Sudan. IV. Eastern Sudan. V. Central Sudan. VI. South-Eastern Sudan. VII. Bahr-el-Ghazal. VIII. Kordofan. IX. North-Western Sudan.

Ditto. Chapter VII Supplement (A). Bahr-el-Ghazal. Additional Routes. 1*s.* (10*d.*)

SUDAN CAMPAIGN. History of the. Two parts, and Maps. 1890. 15*s.* (10*s.* 11*d.*)

(As to prices in brackets, see top of page 2.)

SUPPLY MANUAL (WAR). 1909. 6*d.* (6*d.*)

SUPPLY, REORGANIZED SYSTEMS OF, and of Ammunition Supply of the Expeditionary Force in War, consequent on the Introduction of Mechanical Transport. Memorandum explaining the. Feb. 1912. 1*d.* (1*d.*)

SUPPLY, TRANSPORT, AND BARRACK SERVICES. Regulations. 1908. 9*d.* (8*d.*) (*Under revision*)

SURVEYING. Topographical and Geographical. Text Book of. Second edition. 1913. 7*s.* 6*d.* (5*s.* 6*d.*)

Ditto. 1905. Appendix XI. Tables for the Projection of Graticules for squares on 1° side on scale of 1:250,000, and for squares on ½° side on scale of 1:125,000; with other Tables used in Projecting Maps. 4*d.* (4*d.*)

Ditto. 1905. Appendix XII. Tables for the Projection of Graticules for Maps on the scale of 1:1,000,000. 1910. 2*d.* (2*d.*)

TACTICAL RIDES AND TOURS ON THE GROUND. The Preparation and Conduct of. Translated from the German. 1*s.* 3*d.* (1*s.* 1*d.*)

TELEGRAPH LINES, FIELD. Instruction in Laying and Maintaining. 6*d.* (5*d.*)

TELEGRAPHY AND TELEPHONY. Army. Instruction in. Vol. I. Instruments. 1*s.* 6*d.* (1*s.* 4*d.*); Vol. II. Lines. 1*s.* (11*d.*); Amendments, Sept. 1912, to Vols. I. and II. 1*d.* (1*d.*); Amendments to Vol. II., Chap. V. 1*d.* (1*d.*)

TELEPHONES IN THE FIELD. Technical Instructions for the Use of Provisional. 1908. 2*d.* (2*d.*)

TELESCOPIC SIGHTS. Handbook. Land Service. 1904. 4*d.* (4*d.*)

TERRITORIAL FORCE. (*And see* Equipment; Establishments):—

Cadet List. A List of all Cadet Units which had received Official Recognition on 31st December, 1913. 6*d.* (6*d.*)

Cadet Units in the British Isles. Regulations governing the Formation, Organization, and Administration of. 1914. 1*d.* (1*d.*)

Commissions in the. Guide for the Use of Candidates for. 1913. 1*d.* (1*d.*)

Exemption from Jury Service. ½*d.* (½*d.*)

Field Kits. Officers and Men. 1*d.* (1*d.*)

Hospitals, General, of the. Regulations for. 1912. 2*d.* (2*d.*)

Leaflets:—No. 1. Organization and Principles; Service of the Imperial Yeomanry. 1*d.* each, or 6*d.* per dozen, or 3*s.* per 100.

Medical Corps. Royal Army. Syllabus of Training. 1914. 1*d.* (1*d.*)

Mobilization of a Territorial Infantry Battalion. (*Reprinted from* THE ARMY REVIEW, July 1913.) 3*d.* (3*d.*)

Nursing Service. Standing Orders. 1912. 1*d.* (1*d.*)

Organization and Establishment. Special A.O., March 18, 1908. 6*d.* (6*d.*)

Regulations for the, and for County Associations. 1912. (Reprinted, with Amendments, 1914.) 6*d.* (7*d.*) (*In the press*)

Reserve. Regulations. Issued with Special A.O., April 1, 1913. 1*d.* (1*d.*)

Scheme for the Transfer of the Honourable Artillery Company, the Imperial Yeomanry in Great Britain, and the Volunteer Force, and their Reorganization into the Territorial Force. Special A.O., March 18, 1908. 2*d.* (2*d.*)

Service in the. Its Terms and Conditions. 1*d.* (1*d.*)

Training, Provisional. 2*d.* (2*d.*)

Transfer of Units to the. Special A.O., March 20, 1908, enclosing the Order in Council dated March 19, 1908. 2*d.* (2*d.*)

Uniform. Special A.O., June 12, 1908. 1*d.* (1*d.*)

(As to prices in brackets, see top of page 2.)

Territorial Force—*continued.*

Voluntary Aid:—

Scheme for the Organization of, in England and Wales, Dec. 1910. 2*d.* (2*d.*)

Ditto. Ditto. Amendments. 1*d* (1*d.*)

Ditto, in Scotland. Oct. 1911. 2*d.* (2*d.*)

Ditto. Ditto. Amendments. 1*d.* (1*d.*)

Training. (Extracts from "Medical Corps. Royal Army. Training. 1911.") 6*d.* (7*d.*)

TRACTOR TRIALS held by the Experimental Sub-Committee of the Mechanical Transport Committee at Aldershot, Sept. and Oct. 1903. Report on. 6*d.* (5*d.*)

TRAINING AND MANŒUVRE REGULATIONS. 1913. 4*d.* (5*d.*)

TRANSPORT MANUAL. Field Service. 1905. Part I. Provisional. 4*d.* (4*d.*)

TRANSPORT. MECHANICAL:—

Heavy Pontoon Bridge for use by, Provisional. 1914. 2*d.* (2*d.*)

Regulations for the Appointment of Inspectors of. 1*d.* (1*d.*)

TRANSPORT. PACK. Notes on. 1*d.* (1*d.*)

TRUMPET AND BUGLE SOUNDS for the Army. With Instructions for the Training of Trumpeters and Buglers. 1914. 9*d.* (8*d.*)

TYPHOID (ANTI-) COMMITTEE. Report. 1912. 2*s.* 6*d.* (1*s.* 11*d.*)

TYPHOID (ANTI-) INOCULATION COMMITTEE. Report on Blood Changes following Typhoid Inoculation. 1905. 1*s.* 6*d.* (1*s.* 2*d.*)

URDU-ENGLISH PRIMER. For the use of Colonial Artillery. 1899. 15*s.* (10*s.* 2*d.*)

VALISE EQUIPMENT. Instructions for Fitting:—

Pattern 1888 with pattern 1894 Pouch opening outwards. 1895. 1*d.* (1*d.*)

Bandolier pattern. 1903. 2*d.* (2*d.*)

VALPARAISO. The Capture of, in 1891. 1*s.* (10*d.*)

VENEREAL DISEASE. *See* Medical Services.

VETERINARY CORPS. *Army:*—

Regulations for Admission. 1910. 2*d.* (2*d.*)

Standing Orders. 1906. 4*d.* (4*d.*)

VETERINARY SERVICES. Army. Regulations. 1906. 3*d.* (3*d.*)

VOLUNTARY AID. *See* Territorial Force.

WAR OFFICE LIST, AND ADMINISTRATIVE DIRECTORY FOR THE BRITISH ARMY. 1914. *Sold by Harrison & Sons, 45, Pall Mall.* 5*s. net.*

WARFARE. *See* LAND WARFARE.

WATER SUPPLY MANUAL. 1*s.* 6*d.* (1*s.* 4*d.*); Appendix I. 1*d.* (1*d.*)

WORKS MANUAL. (WAR.) 1913. 4*d.* (4*d.*); Corrections (*In the press*)

X-RAY APPARATUS. Hints regarding the Management and use of. 3*d.* (3*d.*)

YEOMANRY AND MOUNTED RIFLE TRAINING. Parts I. and II. 1912. 6*d.* (6*d.*)

ZULU WAR OF 1879. Narrative of the Field Operations connected with the. 1881. (*Reprinted* 19..) 5*s.* (2*s.* 4*d.*)